


# FCC and ISED Canada Testing of the

Acuity Brands Lighting, Inc.  
BTRMJOT2

In accordance with FCC 47 CFR part 15.247 and  
ISED Canada's Radio Standards Specifications  
RSS-247

Prepared for: Acuity Brands Lighting, Inc.  
One Lithonia Way  
Conyers, GA 30012

FCC ID: 2ADCB-BTRMJOT2  
IC: 6715C-BTRMJOT2



## COMMERCIAL-IN-CONFIDENCE

Document Number: TP72158956.103 | Version Number: 04

RESPONSIBLE FOR	NAME	DATE	SIGNATURE
Authorized Signatory	Peter Walsh	2020 -May-08	
Testing	Thierry Jean Charles	2020-May-08	

Signatures in this approval box have checked this document in line with the requirements of TÜV SÜD Product Service document control rules.

FCC Accreditation Designation Number US1063 Tampa, FL Test Laboratory  
Innovation, Science, and Economic Development Canada Accreditation Site Number 2087A-2 Tampa, FL Test Laboratory

**EXECUTIVE SUMMARY**  
Samples of this product were tested and found to be in compliance with 15.247 and ISED Canada's RSS-247.

 A2LA Cert. No. 2955.15	<b>DISCLAIMER AND COPYRIGHT</b> This non-binding report has been prepared by TÜV SÜD America with all reasonable skill and care. The document is confidential to the potential Client and TÜV SÜD America. No part of this document may be reproduced without the prior written approval of TÜV SÜD America. © TÜV SÜD.
	<b>DISCLAIMER AND COPYRIGHT</b> Our A2LA Accreditation does not cover opinions and interpretations and any expressed are outside the scope of our A2LA Accreditation. Results of test not covered by our A2LA Accreditation Schedule are marked NUA (Not A2LA Accredited).

TÜV SÜD America  
5610 West Sligh Ave., Suite 100  
Tampa, FL 33634

Phone: 813-284-2715  
[www.tuv-sud-america.com](http://www.tuv-sud-america.com)



## Contents

<b>1</b>	<b>Report Summary .....</b>	<b>3</b>
1.1	Report Modification Record.....	3
1.2	Introduction.....	3
1.3	Brief Summary of Results .....	5
1.4	Product Information .....	6
1.5	Deviations from the Standard.....	8
1.6	EUT Modification Record .....	9
1.7	Test Location .....	9
<b>2</b>	<b>Test Details .....</b>	<b>10</b>
2.1	Antenna Requirements.....	10
2.2	6 dB Bandwidth .....	11
2.3	99% Bandwidth .....	14
2.4	Peak Output Power .....	17
2.5	Band-Edge Compliance of RF Conducted Emissions .....	20
2.6	RF Conducted Spurious Emissions .....	23
2.7	Radiated Spurious Emissions into Restricted Frequency Bands.....	26
2.8	Power Spectral Density .....	34
2.9	Power Line Conducted Emissions .....	37
<b>3</b>	<b>Test Equipment Information .....</b>	<b>41</b>
3.1	General Test Equipment Used.....	41
<b>4</b>	<b>Diagram of Test Set-ups.....</b>	<b>42</b>
<b>5</b>	<b>Measurement Uncertainty .....</b>	<b>45</b>
<b>6</b>	<b>Accreditation, Disclaimers and Copyright.....</b>	<b>46</b>



# 1 Report Summary

## 1.1 Report Modification Record

Alterations and additions to this report will be issued to the holders of each copy in the form of a complete document.

Issue	Description of Change	Date of Issue
1	First Issue	2020-April-16
2	Corrected typos in sections 2.5.6 and 2.6.6.	2020-April-20
3	Corrected typos in sections 2.2.6 and 2.3.6.	2020-May-01
4	Corrected a typo in Section 1.4.1	2020-May-08

## 1.2 Introduction

The purpose of this report is to demonstrate compliance with Part 15 Subpart C of the FCC's Code of Federal Regulations Section 15.247 and Innovation Science and Economic Development Canada's Radio Standards Specification RSS-247 for the tests documented herein.



Applicant	Acuity Brands Lighting, Inc.
Manufacturer	Acuity Brands Lighting, Inc.
Applicant's Email Address	<a href="mailto:Alex.Bahk@AcuityBrands.com">Alex.Bahk@AcuityBrands.com</a>
Model Number(s)	BTRMJOT2
Serial Number(s)	1, 3
FCC ID	2ADCB-BTRMJOT2
ISED Certification Number	6715C-BTRMJOT2
Hardware Version(s)	N/A
Software Version(s)	N/A
Number of Samples Tested	2
Test Specification/Issue/Date	US Code of Federal Regulations (CFR): Title 47, Part 15, Subpart C: Radio Frequency Devices, Intentional Radiators, 2019  Innovation, Science and Economic Development Canada Radio Standards Specification: RSS-247 — Digital Transmission Systems (DTSS), Frequency Hopping Systems (FHSs) and Licence-Exempt Local Area Network (LE-LAN) Devices, Issue 2, February 2017
Test Plan/Issue/Date	2020-March-10
Order Number	72158956
Date	2020-March-26
Date of Receipt of EUT	2020-March-23
Start of Test	2020-March-23
Finish of Test	2020-April-09
Name of Engineer(s)	Jean N. Rene, Thierry Jean-Charles
Related Document(s)	ANSI C63.10-2013: American National Standard of Procedures for Compliance Testing of Unlicensed Wireless Devices.  US Code of Federal Regulations (CFR): Title 47, Part 2, Subpart J: Equipment Authorization Procedures, 2018.  FCC OET KDB 558074 D01 15.247 Meas Guidance v05r02: Guidance for Compliance Measurements on Digital Transmission System, Frequency Hopping Spread Spectrum System, and Hybrid System Devices Operating under Section 15.247 of the FCC Rules.  Innovation, Science and Economic Development Canada Radio Standards Specification: RSS-GEN - General Requirements for Compliance of Radio Apparatus, Issue 5, Amendment 1, March 2019



**1.3 Brief Summary of Results**

A brief summary of the tests carried out in accordance with FCC Part 15.247 and ISED Canada’s RSS-247 is shown below.

**Table 1.3-1: Test Result Summary**

Test Parameter	Test Plan (Yes/No)	Test Result	FCC 47 CFR Rule Part	ISED Canada’s RSS	Test Report Page No
Antenna Requirement	Yes	Pass	15.203, 15.204	-----	10
6 dB Bandwidth	Yes	Pass	15.247(a)(2)	RSS-247 5.2(a)	11
99% Bandwidth	Yes	Pass	-----	RSS-GEN 6.6	14
Peak Output Power	Yes	Pass	15.247(b)(3)	RSS-247 5.4(d)	17
Band-Edge Compliance of RF Conducted Emissions	Yes	Pass	15.247(d)	RSS-247 5.5	20
RF Conducted Spurious Emissions	Yes	Pass	15.247(d)	RSS-247 5.5	23
Radiated Spurious Emissions into Restricted Frequency Bands	Yes	Pass	15.205, 15.209	RSS-GEN 8.9, 8.10	26
Power Spectral Density	Yes	Pass	15.247(e)	RSS-247 5.2(b)	34
Power Line Conducted Emissions	Yes	Pass	15.207	RSS-GEN 8.8	37



**1.4 Product Information**

**1.4.1 Technical Description**

The EUT is a BLE module to provide wireless connectivity to LED lighting and control products.

The EUT was tested for two antenna configurations: integrated trace antenna and an external flag antenna. The device does not support simultaneous transmissions.

Technical Details

Mode of Operation: IEEE 802.15.1 Bluetooth Low Energy (BLE 5.0)  
 Frequency Range: 2402 MHz - 2480 MHz  
 Number of Channels: 40  
 Channel Separation: 2 MHz  
 Data Rate: 1 Mbps  
 Modulations: GFSK  
 Antenna Type/Gain: PCB Trace Antenna / 2.1 dBi  
 External Flag Antenna / 1.5 dBi  
 Input Power: 3.3 VDC

A full description and detailed product specification details are available from the manufacturer.

**Table 1.4.1-1 – Cable Descriptions**

Cable/Port	Description
Power Leads	0.1 m, Not shielded, Battery Holder to EUT
Power	1.5 m, Not Shielded, Power Supply to EUT
Coaxial Cable	0.25 m, shielded, External Antenna to EUT

**Table 1.4.1-2 – Support Equipment Descriptions**

Make/Model	Description
Pulse Electronics / W3525BWT100	1.5 dBi Flag Antenna
UM-3x2	2x AA Battery Holder
XP Power / VEL05US050-US-JA	5V Switching Power Supply
Laird / 28A0350-0B2	Ferrite on UM-3x2 power leads



**Declaration of Build Status**

EQUIPMENT DESCRIPTION	
Model Name/Number	BTRMJOT2
Part Number	501-01251-101, 510-01251-102
Hardware Version	NA
Software Version	NA
FCC ID (if applicable)	2ADCB-BTRMJOT2
ISED ID (if applicable)	6715C-BTRM2
Technical Description (Please provide a brief description of the intended use of the equipment)	BTRMJOT2 is a BLE module to provide wireless connectivity to LED lighting and control products.

UN-INTENTIONAL RADIATOR	
Highest frequency generated or used in the device or on which the device operates or tunes	2480 MHz
Lowest frequency generated or used in the device or on which the device operates or tunes	2402 MHz
Class A Digital Device (Use in commercial, industrial or business environment) <input checked="" type="checkbox"/>	
Class B Digital Device (Use in residential environment only) <input checked="" type="checkbox"/>	

Power Source			
AC	Single Phase	Three Phase	Nominal Voltage
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
External DC	Nominal Voltage		Maximum Current
	5V		10mA
Battery	Nominal Voltage		Battery Operating End Point Voltage
	3V		3V

EXTREME CONDITIONS			
Maximum temperature	+85	°C	Minimum temperature
			-40 °C

Ancillaries
Please list all ancillaries which will be used with the device.
NA

I hereby declare that the information supplied is correct and complete.

Name: Alex Bahk   
 Position held: Lead RF Engineer Date: 4/1/2020



**1.4.2 Modes of Operation**

The EUT was to the continuous TX mode for the BLE radio using a software power setting of 90.

**1.4.3 Monitoring of Performance**

The EUT was evaluated for radiated, power line and RF Conducted Emissions.

TX radiated emissions were performed for the EUT in multiple orientations for both antenna configurations. The results documented in this test report correspond to the orientations leading to the highest emissions with respect to the limits.

EUT with Trace Antenna:

- TX Radiated Spurious and Band-Edge Emissions: Flat orientation

EUT with External Flag Antenna:

- TX Radiated Spurious Emissions: Side Orientation
- TX Radiated Band-Edge Emissions: Flat Orientation

The RF conducted emissions measurements were performed on a test sample with the U.FL connector to allow direct coupling to a spectrum analyzer.

The Power Line Conducted Emissions measurements were performed for both antenna configurations. PCB Trace Antenna configuration test results were the worst case and are documented in this test report.

**1.4.4 Performance Criteria**

The parameters evaluated are summarized below.

**Table 1.4.4 -1: Performance Criteria**

Parameter	Requirement
Antenna Requirement	FCC: Section 15.203. 15.204
6 dB Bandwidth	FCC: Section 15.247(a)(2); ISED Canada: RSS-247 5.2(a)
99% Bandwidth	ISED Canada: RSS-GEN 6.6
Peak Output Power	FCC: Section 15.247(b)(3); ISED Canada:RSS-247 5.4(d)
Band-Edge Compliance of RF Conducted Emissions	FCC: Section 15.247(d); ISED Canada: RSS-247 5.5
RF Conducted Spurious Emissions	FCC: Section 15.247(d); ISED Canada: RSS-247 5.5
Radiated Spurious Emissions into Restricted Frequency Bands	FCC: Sections 15.205, 15.209; ISED Canada: RSS-GEN 8.9, 8.10
Power Spectral Density	FCC: Section 15.247(e); ISED Canada: RSS-247(b)
Power Line Conducted Emissions	FCC: Section 15.207; ISED Canada: RSS-GEN 8.8

**1.5 Deviations from the Standard**

The EUT was evaluated without any deviations from the test standards.





**1.6 EUT Modification Record**

The table below details modifications made to the EUT during the test programme. The modifications incorporated during each test are recorded on the appropriate test pages.

Modification State	Description of Modification still fitted to EUT	Modification Fitted By	Date Modification Fitted

The equipment was tested as provided without any modifications.

**1.7 Test Location**

TÜV SÜD Product Service conducted the following tests at our Tampa FL Test Laboratory.

Test Name	Name of Engineer(s)	Accreditation
AC Powered Operating		
Antenna Requirement	Thierry Jean-Charles	A2LA
6 dB Bandwidth	Thierry Jean-Charles	A2LA
99% Bandwidth	Thierry Jean-Charles	A2LA
Peak Output Power	Thierry Jean-Charles	A2LA
Band-Edge Compliance of RF Conducted Emissions	Thierry Jean-Charles	A2LA
RF Conducted Spurious Emissions	Thierry Jean-Charles	A2LA
Radiated Spurious Emissions into Restricted Frequency Bands	Jean N. Rene	A2LA
Power Spectral Density	Thierry Jean-Charles	A2LA
Power Line Conducted Emissions	Jean N. Rene	A2LA

Office Address:

TÜV SÜD America, Inc.  
 5610 W. Sligh Ave, Suite 100  
 Tampa, FL 33634  
 USA



## 2 Test Details

### 2.1 Antenna Requirements

#### 2.1.1 Specification Reference

FCC: Section 15.203, 15.204

#### 2.1.2 Equipment Under Test and Modification State

S/N: 1, 3

#### 2.1.3 Date of Test

3/25/2020

#### 2.1.4 Test Method

N/A

#### 2.1.5 Environmental Conditions

Ambient Temperature	N/A
Relative Humidity	N/A
Atmospheric Pressure	N/A

#### 2.1.6 Test Results

Limit Clause FCC Sections: 15.203, 15,204

An intentional radiator shall be designed to ensure that no antenna other than that furnished by the responsible party shall be used with the device.

The EUT uses two types of antennas. The 2.1 dBi PCB trace antenna is integral to the PCB. The 1.5 dBi External Flag antenna provides a u.FL. connector to be connected to the u.FL. connector on the PCB of the module.

Both antenna configurations meet the requirements of FCC Section 15.203.

#### 2.1.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

As this is a visual inspection, no test equipment was used.



**2.2 6 dB Bandwidth**

**2.2.1 Specification Reference**

FCC: Section 15.247(a)(2)  
 ISED Canada: RSS-247 5.2(a)

**2.2.2 Equipment Under Test and Modification State**

S/N: 1

**2.2.3 Date of Test**

3/26/2020

**2.2.4 Test Method**

The 6dB bandwidth was measured in accordance with ANSI C63.10 Subclause 11.8.1 Option 1. The RBW of the spectrum analyzer was set to 100 kHz and VBW 300 kHz. Span was set large enough to capture the emissions and >> RBW. A peak detector was used for the measurements.

**2.2.5 Environmental Conditions**

Ambient Temperature 24.5°C  
 Relative Humidity 38.2 %  
 Atmospheric Pressure 1016.9 mbar

**2.2.6 Test Results**


AC Powered Operating

Limit Clause FCC Part 15.247(a)(2), ISED RSS-247 5.2(a)

The minimum 6 dB bandwidth shall be at least 500 kHz.


**Table 2.2.6-1: 6 dB Bandwidth Test Results**

Frequency (MHz)	6 dB Bandwidth (kHz)
2402	698.250
2440	698.500
2480	694.750




Date: 26.MAR.2020 10:58:20

Figure 2.2.6-1: 6 dB Bandwidth Test Results Low Channel



Date: 26.MAR.2020 11:06:36

Figure 2.2.6-2: 6 dB Bandwidth Test Results Middle Channel



Date: 26.MAR.2020 11:23:11

**Figure 2.2.6-3: 6 dB Bandwidth Test Results High Channel**

**2.2.7 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable



**2.3 99% Bandwidth**

**2.3.1 Specification Reference**

ISED Canada: RSS-GEN 6.7

**2.3.2 Equipment Under Test and Modification State**

S/N: 1

**2.3.3 Date of Test**

3/26/2020

**2.3.4 Test Method**

The 99% occupied bandwidth was measured with the spectrum analyzer span set to fully display the emission. The RBW was set to 1% to 5% of the approximated bandwidth. The occupied 99% bandwidth was measured by using 99% bandwidth equipment function of the spectrum analyzer using a peak detector.

**2.3.5 Environmental Conditions**

Ambient Temperature 24.5°C  
 Relative Humidity 38.2 %  
 Atmospheric Pressure 1016.9 mbar


**2.3.6 Test Results**

AC Powered Operating

Limit Clause ISED RSS-GEN 6.7


**Table 2.3.6-1: 99% Bandwidth Test Results**

Frequency (MHz)	99% Bandwidth (kHz)
2402	1034.375
2440	1038.750
2480	1038.750




Date: 26.MAR.2020 10:50:58

Figure 2.3.6-1: 99% Bandwidth Test Results Low Channel



Date: 26.MAR.2020 11:11:38

Figure 2.3.6-2: 99% Bandwidth Test Results Middle Channel



Date: 26.MAR.2020 11:16:21

**Figure 2.3.6-3: 99% Bandwidth Test Results High Channel**

### 2.3.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable





**2.4 Peak Output Power**

**2.4.1 Specification Reference**

FCC Section 15.247(b)(3)  
 ISED Canada: RSS-247 5.4(d)

**2.4.2 Equipment Under Test and Modification State**

S/N: 1

**2.4.3 Date of Test**

3/26/2020

**2.4.4 Test Method**

The fundamental emission output power was measured in accordance with ANSI C63.10 Subclause 11.9.1.1 RBW  $\geq$  DTS bandwidth. The RF output of the equipment under test was directly connected to the input of the spectrum analyzer through suitable attenuation.

**2.4.5 Environmental Conditions**

Ambient Temperature 24.8°C  
 Relative Humidity 37.5 %  
 Atmospheric Pressure 1016.8 mbar

**2.4.6 Test Results**


AC Powered Operating

Limit Clause FCC Part 15.247(b)(3), ISED RSS-247 5.4(d)

The Maximum Output Power allowed for systems using digital modulation is 1 Watt (30 dBm)


**Table 2.4.6-1: Maximum Output Power Results**

Frequency (MHz)	Output Power (dBm)
2402	11.33
2440	11.24
2480	11.21




Date: 26.MAR.2020 11:37:37

Figure 2.4.6-1: Maximum Output Power Results Low Channel



Date: 26.MAR.2020 11:53:54

Figure 2.4.6-2: Maximum Output Power Results Middle Channel



Date: 26.MAR.2020 11:32:50

**Figure 2.4.6-3: Maximum Output Power Results High Channel**

**2.4.7 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable



## **2.5 Band-Edge Compliance of RF Conducted Emissions**

### **2.5.1 Specification Reference**

FCC: Section 15.247(d)  
ISED Canada: RSS-247 5.5

### **2.5.2 Equipment Under Test and Modification State**

S/N: 1

### **2.5.3 Date of Test**

3/25/2020

### **2.5.4 Test Method**

The RF Conducted Emissions at the Band-Edges were measured in accordance with Subclause 11.11 of ANSI C63.10. The RF output port of the EUT was connected to the input of the spectrum analyzer through suitable attenuation. The EUT was investigated at the lowest and highest channel available to determine band-edge compliance. For each measurement the spectrum analyzer's RBW was set to 100 kHz, and the VBW was set to  $\geq 300$  kHz.

### **2.5.5 Environmental Conditions**


Ambient Temperature	25.1 °C
Relative Humidity	37.2 %
Atmospheric Pressure	1016.5 mbar

### **2.5.6 Test Results**

AC Powered Operating


Limit Clause FCC Section 15.247(d), ISED Canada: RSS-247 5.5

In any 100 kHz bandwidth outside of the frequency band the radio frequency power shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of desired power. If the transmitter complies with the conducted power limits based on the use of RMS averaging over a time interval, the attenuation required shall be 30 dB instead of 20 dB.



Date: 26.MAR.2020 12:54:58

Figure 2.5.6-1: RF Conducted Band-Edge Results Low Channel



Date: 26.MAR.2020 12:29:16

Figure 2.5.6-2: RF Conducted Band-Edge Results High Channel



**2.5.7 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable



## **2.6 RF Conducted Spurious Emissions**

### **2.6.1 Specification Reference**

FCC: Section 15.247(d)  
ISED Canada: RSS-247 5.5

### **2.6.2 Equipment Under Test and Modification State**

S/N: 1

### **2.6.3 Date of Test**

3/26/2020

### **2.6.4 Test Method**

The RF Conducted Spurious Emissions were measured in accordance with Subclause 11.11 of ANSI C63.10. The RF output port of the equipment under test was directly connected to the input of the spectrum analyzer. The EUT was investigated for conducted spurious emissions from 30 MHz to 25 GHz, 10 times the highest fundamental frequency. Measurements were made at the low, center and high channels of the EUT. For each measurement, the spectrum analyzer's RBW was set to 100 kHz and the VBW was set to 300 kHz. The peak Max Hold function of the analyzer was utilized.

### **2.6.5 Environmental Conditions**


Ambient Temperature	25.1 °C
Relative Humidity	37.2 %
Atmospheric Pressure	1016.5 mbar

### **2.6.6 Test Results**

AC Powered Operating


Limit Clause FCC Section 15.247(d), ISED Canada: RSS-247 5.5

In any 100 kHz bandwidth outside of the frequency band the radio frequency power shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of desired power. If the transmitter complies with the conducted power limits based on the use of RMS averaging over a time interval, the attenuation required shall be 30 dB instead of 20 dB.



Date: 26.MAR.2020 12:49:54


Figure 2.6.6-1: RF Conducted Spurious Emissions Results Low Channel



Date: 26.MAR.2020 12:07:23

Figure 2.6.6-2: RF Conducted Spurious Emissions Results Middle Channel





Date: 26.MAR.2020 12:24:51

Figure 2.6.6-3: RF Conducted Spurious Emissions Results High Channel

### 2.6.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable



## **2.7 Radiated Spurious Emissions into Restricted Frequency Bands**

### **2.7.1 Specification Reference**

FCC Sections: 15.205, 15.209;  
ISED Canada: RSS-GEN 8.9, 8.10

### **2.7.2 Equipment Under Test and Modification State**

S/N: 1, 3

### **2.7.3 Date of Test**

3/23/2020 to 4/9/2020

### **2.7.4 Test Method**

Radiated emissions tests were made over the frequency range of 9 kHz to 26 GHz, 10 times the highest fundamental frequency. Each emission found to be in a restricted band as defined by section 15.205, including any emission at the operational band-edge, was compared to the radiated emission limits as defined in Section 15.209.

For measurements below 30 MHz, the receive antenna height was set to 1 m and the EUT was rotated through 360 degrees. The resolution bandwidth was set to 200 Hz below 150 kHz and to 9 kHz above 150 kHz.

The EUT was rotated through 360° and the receive antenna height was varied from 1m to 4m so that the maximum radiated emissions level would be detected. For frequencies below 1000 MHz, quasi-peak measurements were made using a resolution bandwidth RBW of 120 kHz and a video bandwidth VBW of 300 kHz. For frequencies above 1000 MHz, peak measurements are made with RBW of 1 MHz and VBW of 3 MHz. Average measurements are performed in the linear scale using VBW of 30 Hz.

### **2.7.5 Duty Cycle Correction**

The EUT was configured to transmit at 100% duty cycle during the evaluation. A Duty Cycle Correction of 22.04% corresponding to  $20 \cdot \log(22.04/100) = -13.136$  dB was applied to the average measurements for the corrected average results.

### **2.7.6 Environmental Conditions**

Ambient Temperature	25 °C
Relative Humidity	38.5 %
Atmospheric Pressure	1020.8 mbar



**2.7.7 Test Results**

AC Powered Operating

Limit Clause FCC Sections 15.205, 15.209, ISED Canada: RSS-GEN 8.9, 8.10

Frequency (MHz)	Field Strength (microvolts/meter)	Measurement Distance (meters)
0.009-0.490	2400/F(kHz)	300
0.4090-1.705	24000/F(kHz)	30
1.705-30.0	30	30
30-88	100**	3
88-216	150**	3
216-960	200**	3
Above 960	500	3

**Table 2.7.7-1: Radiated Emissions Test Results – Trace Antenna**

Frequency (MHz)	Level (dBuV)		Antenna Polarity (H/V)	Correction Factors (dB)	Corrected Level (dBuV/m)		Limit (dBuV/m)		Margin (dB)	
	pk	Qpk/Avg			pk	Qpk/Avg	pk	Qpk/Avg	pk	Qpk/Avg
<b>Low Channel</b>										
<b>4804</b>	54.05	49.20	H	4.19	58.24	40.25	74.0	54.0	15.8	13.7
<b>4804</b>	50.95	45.40	V	4.19	55.14	36.45	74.0	54.0	18.9	17.5
<b>12010</b>	38.60	26.27	H	17.85	56.45	30.98	74.0	54.0	17.6	23.0
<b>12010</b>	38.48	26.05	V	17.85	56.33	30.76	74.0	54.0	17.7	23.2
<b>Middle Channel</b>										
<b>4880</b>	56.77	52.28	H	4.35	61.12	43.50	74.0	54.0	12.9	10.5
<b>4880</b>	49.31	43.56	V	4.35	53.66	34.78	74.0	54.0	20.3	19.2
<b>7320</b>	42.91	32.64	H	9.32	52.23	28.82	74.0	54.0	21.8	25.2
<b>7320</b>	42.41	31.92	V	9.32	51.73	28.10	74.0	54.0	22.3	25.9
<b>12200</b>	39.13	26.32	H	17.65	56.78	30.84	74.0	54.0	17.2	23.2
<b>12200</b>	39.01	26.75	V	17.65	56.66	31.27	74.0	54.0	17.3	22.7
<b>High Channel</b>										
<b>2483.5</b>	65.74	59.27	H	-1.54	64.20	44.60	74.0	54.0	9.8	9.4
<b>2483.5</b>	62.07	54.48	V	-1.54	60.53	39.81	74.0	54.0	13.5	14.2
<b>4960</b>	62.28	58.25	H	4.52	66.80	49.64	74.0	54.0	7.2	4.4
<b>4960</b>	53.83	49.25	V	4.52	58.35	40.64	74.0	54.0	15.6	13.4
<b>7440</b>	41.98	31.20	H	9.54	51.52	27.61	74.0	54.0	22.5	26.4
<b>7440</b>	41.62	30.56	V	9.54	51.16	26.97	74.0	54.0	22.8	27.0
<b>12400</b>	37.51	24.97	H	17.45	54.96	29.28	74.0	54.0	19.0	24.7
<b>12400</b>	37.64	25.36	V	17.45	55.09	29.67	74.0	54.0	18.9	24.3
<b>22320</b>	41.05	29.37	H	15.86	56.91	32.09	83.5	63.5	26.6	31.4
<b>22320</b>	40.62	28.07	V	15.86	56.48	30.79	83.5	63.5	27.0	32.7

**Notes:**

- A duty Cycle correction Factor of 22.04% was used for the Corrected Average Levels
- The emissions above 18 GHz were performed at a measurement distance of 1m. The limits are corrected using a distance factor of  $20 \cdot \log(1/3)$ .
- All emissions above 22.32 GHz were attenuated below the noise floor of the measurement equipment and the limits.



**Table 2.7.7-2: Radiated Emissions Test Results – External Antenna**

Frequency (MHz)	Level (dBuV)		Antenna Polarity (H/V)	Correction Factors (dB)	Corrected Level (dBuV/m)		Limit (dBuV/m)		Margin (dB)	
	pk	Qpk/Avg			pk	Qpk/Avg	pk	Qpk/Avg	pk	Qpk/Avg
<b>Low Channel</b>										
<b>4804</b>	42.21	32.92	H	4.19	46.40	23.97	74.0	54.0	27.6	30.0
<b>4804</b>	46.52	38.09	V	4.19	50.71	29.14	74.0	54.0	23.3	24.9
<b>12010</b>	38.61	25.68	H	17.85	56.46	30.39	74.0	54.0	17.5	23.6
<b>12010</b>	38.83	25.91	V	17.85	56.68	30.62	74.0	54.0	17.3	23.4
<b>Middle Channel</b>										
<b>4880</b>	41.02	30.63	H	4.35	45.37	21.85	74.0	54.0	28.6	32.2
<b>4880</b>	44.91	35.37	V	4.35	49.26	26.59	74.0	54.0	24.7	27.4
<b>7320</b>	42.98	33.19	H	9.32	52.30	29.37	74.0	54.0	21.7	24.6
<b>7320</b>	43.28	34.18	V	9.32	52.60	30.36	74.0	54.0	21.4	23.6
<b>12200</b>	36.87	22.94	H	17.65	54.52	27.46	74.0	54.0	19.5	26.5
<b>12200</b>	37.78	23.83	V	17.65	55.43	28.35	74.0	54.0	18.6	25.7
<b>High Channel</b>										
<b>2483.5</b>	63.69	56.42	H	-1.54	62.15	41.75	74.0	54.0	11.8	12.3
<b>2483.5</b>	56.39	48.15	V	-1.54	54.85	33.48	74.0	54.0	19.1	20.5
<b>4960</b>	50.58	45.48	H	4.52	55.10	36.87	74.0	54.0	18.9	17.1
<b>4960</b>	53.88	49.17	V	4.52	58.40	40.56	74.0	54.0	15.6	13.4
<b>7440</b>	44.13	34.24	H	9.54	53.67	30.65	74.0	54.0	20.3	23.4
<b>7440</b>	44.96	35.08	V	9.54	54.50	31.49	74.0	54.0	19.5	22.5
<b>12400</b>	37.48	24.18	H	17.45	54.93	28.49	74.0	54.0	19.1	25.5
<b>12400</b>	38.62	25.32	V	17.45	56.07	29.63	74.0	54.0	17.9	24.4
<b>19840</b>	38.24	24.43	H	14.49	52.73	25.78	83.5	63.5	30.8	37.7
<b>22320</b>	40.90	28.96	H	15.86	56.76	31.68	83.5	63.5	26.7	31.8
<b>22320</b>	39.99	28.14	V	15.86	55.85	30.86	83.5	63.5	27.7	32.6

**Notes:**

- A duty Cycle correction Factor of 22.04% was used for the Corrected Average Levels
- The emissions above 18 GHz were performed at a measurement distance of 1m. The limits are corrected using a distance factor of 20\*log(1/3).
- All emissions above 22.32 GHz were attenuated below the noise floor of the measurement equipment and the limits.




Figure 2.7.7-1: Radiated Emissions Representative Scan below 30 MHz




Figure 2.7.7-2: Radiated Emissions Representative Scan 30 MHz – 1 GHz – Horizontal Polarization




Figure 2.7.7-3: Radiated Emissions Representative Scan 30 MHz – 1 GHz – Vertical Polarization




Figure 2.7.7-4: Radiated Emissions Representative Scan 1 GHz – 18 GHz – Horizontal Polarization




Figure 2.7.7-5: Radiated Emissions Representative Scan 1 GHz – 18 GHz – Vertical Polarization





Figure 2.7.7-6: Radiated Emissions Representative Scan 18 GHz – 26 GHz – Horizontal Polarization



**Figure 2.7.7-7: Radiated Emissions Representative Scan 18 GHz – 26 GHz – Vertical Polarization**

**2.7.8 Sample Calculations**

$$R_c = R_u + CF_T$$

Where:

- CF<sub>T</sub> = Total Correction Factor (AF+CA+AG)-DC (Average Measurements Only)
- R<sub>U</sub> = Uncorrected Reading
- R<sub>C</sub> = Corrected Level
- AF = Antenna Factor
- CA = Cable Attenuation
- AG = Amplifier Gain
- DC = Duty Cycle Correction Factor

**Example Calculation: Peak**

Corrected Level: 54.05 + 4.19 = 58.24 dBμV/m  
 Margin: 74 dBμV/m – 58.24 dBμV/m = 15.76 dB

**Example Calculation: Average**

Corrected Level: 49.2 + 4.19 -13.136 = 40.25 dBμV/m  
 Margin: 54 dBμV/m – 40.25 dBμV/m = 13.75 dB





**2.7.9 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
9kHz-26.5GHz EMC analyzer/HYZ	Agilent	E7405A	BEMC00523	A.14.06	24	27-Nov-2020
10dB Attenuator	Merrimac	FAN-6-10K	BEMC02086	N/A	12	12-Oct-2020
Tile Automation Software	ETS Lindgren	TILE4! - Version 4.2.A	BEMC02095	4.2A	N/A	NCR
BI LOG PERIODIC, ANTENNA	Schaffner	CBL6112B	TEMC00005	N/A	24	31-Oct-2021
Loop Antenna	Com Power	AL-130	TEMC00025	N/A	24	26-Sep-2021
Horn Antenna	Schwarzbeck	BBHA-9170	TEMC00029	N/A	60	23-Aug-2021
EMC Chamber	Panashield	N/A	TEMC00031	N/A	36	28-Jan-2021
Double Ridge Guide Horn	ETS Lindgren	3117	TEMC00061	N/A	24	07-Feb-2022
18 GHz-40 GHz Microwave Preamplifier	COM-power	PAM-840A	TEMC00147	N/A	24	30-May-2020
PAM-118A	Com-Power Corporation	PAM-118A	TEMC00160	N/A	12	27-Apr-2020
4A & 4B Test Cables	MegaPhase, LLC	1GVT4	TEMC00171	N/A	24	30-May-2020
2.4 GHz Notch Filter	Micro-Tronics	BRM50702-01	TEMC00176	N/A	12	10-Apr-2020
Radiated Cable Set 30 MHz - 1 GHz	TUV SUD Tampa	Cable 2	TEMC00179	N/A	12	07-May-2020
Radiated Cable Set 9 kHz - 30 MHz	TUV SUD Tampa	Cable 2	TEMC00186	N/A	12	08-May-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable  
 NCR – No Calibration Required



**2.8 Power Spectral Density**

**2.8.1 Specification Reference**

FCC: Section 15.247(e)  
 ISED Canada: RSS-247 5.2(b)

**2.8.2 Equipment Under Test and Modification State**

S/N: 1

**2.8.3 Date of Test**

3/26/2020

**2.8.4 Test Method**

The power spectral density was measured in accordance with ANSI C63.10 Subclause 11.10.2 Method PKPSD (peak PSD). The RF output port of the EUT was directly connected to the input of the spectrum analyzer. Offset values were input for cable and external attenuation. The spectrum analyzer's RBW was set to 3 kHz and VBW to 10 kHz. The Span was adjusted to 1.5 times the DTS bandwidth and the sweep time was set to auto. The measurements were performed using a Peak detector.

**2.8.5 Environmental Conditions**

Ambient Temperature 25 °C  
 Relative Humidity 37.2 %  
 Atmospheric Pressure 1016.8 mbar

**2.8.6 Test Results**


AC Powered Operating

Limit FCC: Section 15.247(e), ISED Canada: RSS-247 5.2(b)

The power spectral density conducted from the intentional radiator to the antenna shall not be greater than 8 dBm in any 3 kHz band during any time of continuous transmission.


**Table 2.8.6-1: Power Spectral Density Results**

Frequency (MHz)	PSD (dBm)	Limit (dBm)	Margin (dB)
2402	-4.31	8.0	12.31
2440	-4.39	8.0	12.39
2480	-4.44	8.0	12.44




Date: 26.MAR.2020 11:45:51

Figure 2.8.6-1: Power Spectral Density Results – Low Channel



Date: 26.MAR.2020 11:49:39

Figure 2.8.6-2: Power Spectral Density Results – Middle Channel



Date: 26.MAR.2020 11:30:01

**Figure 2.8.6-3: Power Spectral Density Results – High Channel**

**2.8.7 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable



**2.9 Power Line Conducted Emissions**

**2.9.1 Specification Reference**

FCC: Section 15.207  
 ISED Canada; RSS-GEN 8.8

**2.9.2 Equipment Under Test and Modification State**

S/N: 1

**2.9.3 Date of Test**

3/31/2020

**2.9.4 Test Method**

ANSI C63.10 section 6.2 was the guiding document for this evaluation. Conducted emissions were performed from 150 kHz to 30 MHz with the spectrum analyzer's resolution bandwidth set to 9 kHz and the video bandwidth set to 30 kHz. The calculation for the conducted emissions is as follows:

**Corrected Reading = Analyzer Reading + LISN Loss + Cable Loss**  
**Margin = Applicable Limit - Corrected Reading**

**2.9.5 Environmental Conditions**

Ambient Temperature    24.9 °C  
 Relative Humidity        41.2 %  
 Atmospheric Pressure    1007.9 mbar

**2.9.6 Test Results**


Frequency of Emission (MHz)	Conducted Limit (dBµV)	
	Quasi-Peak	Average
0.15-0.5	66 to 56*	56 to 46*
0.5-5	56	46
5-30	60	50

\*Decreases with the logarithm of the frequency.



**Table 2.9.6-1: Power Line Conducted Emissions – Quasi-Peak Detector Results**

Frequency (MHz)	Quasi-peak (dBµV)	Line	Corr. (dB)	Margin (dB)	Limit (dBµV)
0.348000	26.12	L1	10.0	32.89	59.01
0.573000	20.40	L1	10.0	35.60	56.00
16.741500	23.64	L1	11.3	36.36	60.00
17.169000	22.46	L1	11.3	37.54	60.00
17.263500	22.57	L1	11.3	37.43	60.00
17.452500	21.24	L1	11.4	38.76	60.00



- Preview Result 2-AVG
- FCC Part 15 Class B Voltage on Mains QP
- Preview Result 1-PK+
- - - FCC Part 15 Class B Voltage on Mains Avg
- ◆ Final\_Result QPK
- ◆ Final\_Result AVG

**Figure 2.9.6-1: Composite Power Line Conducted Emissions Plots**



**2.9.7 Test Location and Test Equipment Used**

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
LISN	Rohde & Schwarz	ESH3-Z5	TEMC00002	N/A	24	30-Sep-2021
EMI Test Receiver	Rohde & Schwarz	ESCS30	TEMC00011	2.3002.0102.36	24	03-Oct-2021
RFI/EMI Shielded Enclosure	UNIVERSAL SHIELDING CORP.	N/A	TEMC00100	N/A	N/A	NCR
Test Software	Rohde & Schwarz	EMC32	TEMC00184	10.50.00	N/A	NCR

TU - Traceability Unscheduled  
 O/P MON - Traceability Unscheduled  
 N/A - Not Applicable  
 NCR – No Calibration Required






### 3 Test Equipment Information

#### 3.1 General Test Equipment Used


Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
9kHz-26.5GHz EMC analyzer/HYZ	Agilent	E7405A	BEMC00523	A.14.06	24	27-Nov-2020
10dB Attenuator	Merrimac	FAN-6-10K	BEMC02086	N/A	12	12-Oct-2020
Tile Automation Software	ETS Lindgren	TILE4! - Version 4.2.A	BEMC02095	4.2A	N/A	NCR
BI LOG PERIODIC, ANTENNA	Schaffner	CBL6112B	TEMC00005	N/A	24	31-Oct-2021
Loop Antenna	Com Power	AL-130	TEMC00025	N/A	24	26-Sep-2021
Horn Antenna	Schwarzbeck	BBHA-9170	TEMC00029	N/A	60	23-Aug-2021
EMC Chamber	Panashield	N/A	TEMC00031	N/A	36	28-Jan-2021
Double Ridge Guide Horn	ETS Lindgren	3117	TEMC00061	N/A	24	07-Feb-2022
18 GHz-40 GHz Microwave Pre-amplifier	COM-power	PAM-840A	TEMC00147	N/A	24	30-May-2020
PAM-118A	Com-Power Corporation	PAM-118A	TEMC00160	N/A	12	27-Apr-2020
4A & 4B Test Cables	MegaPhase, LLC	1GVT4	TEMC00171	N/A	24	30-May-2020
2.4 GHz Notch Filter	Micro-Tronics	BRM50702-01	TEMC00176	N/A	12	10-Apr-2020
Radiated Cable Set 30 MHz - 1 GHz	TUV SUD Tampa	Cable 2	TEMC00179	N/A	12	07-May-2020
Radiated Cable Set 9 kHz - 30 MHz	TUV SUD Tampa	Cable 2	TEMC00186	N/A	12	08-May-2020
Spectrum Analyzer	Rohde & Schwarz	FSP40	BEMC00283	4.50 SP5	24	04-Oct-2021
Attenuator 10dB, 2.9 mm-M/F, DC-40GHz 2 W	Aeroflex Inmet	40AH2W-10	BEMC02110	N/A	12	27-Jul-2020
LISN	Rohde & Schwarz	ESH3-Z5	TEMC00002	N/A	24	30-Sep-2021
EMI Test Receiver	Rohde & Schwarz	ESCS30	TEMC00011	2.3002.0102.36	24	03-Oct-2021
RFI/EMI Shielded Enclosure	UNIVERSAL SHIELDING CORP.	N/A	TEMC00100	N/A	N/A	NCR
Test Software	Rohde & Schwarz	EMC32	TEMC00184	10.50.00	N/A	NCR

TU - Traceability Unscheduled  
O/P MON - Traceability Unscheduled  
N/A - Not Applicable  
NCR – No Calibration Required


## 4 Diagram of Test Set-ups



**Figure 4-1 - Radiated Emissions Test Setup up to 1 GHz**



**Figure 4-2 - Radiated Emissions Test Setup above 1 GHz**



**Figure 4-3 – Conducted Emissions Test Setup**



## 5 Measurement Uncertainty

For a 95% confidence level, the measurement uncertainties for defined systems are:

**Table 6-1 - Values of  $U_{CISPR}$  and  $U_{Lab}$**

Measurement	$U_{CISPR}$	$U_{Lab}$
Conducted disturbance (mains port) (9 kHz – 150 kHz) (150 kHz – 30 MHz)	3.8 dB 3.4 dB	3.71 dB 3.31 dB
Conducted disturbance (telecom port) (150 kHz – 30 MHz 55 dB LCL) (150 kHz – 30 MHz 65 dB LCL) (150 kHz – 30 MHz 75 dB LCL)	5.0 dB 5.0 dB 5.0 dB	4.11 dB 4.50 dB 4.94 dB
Radiated disturbance (electric field strength on an open area test site or alternative test site) (30 MHz – 1 000 MHz) (1 – 6 GHz) (6-18 GHz)	6.3 dB 5.2 dB 5.5 dB	5.85 dB 4.48 dB 4.48 dB

**Notes:**

$U_{CISPR}$  resembles a value of measurement uncertainty for a specific test, which was determined by considering uncertainties associated with the quantities listed in CISPR 16-4-2:2011.



## 6 Accreditation, Disclaimers and Copyright

TÜV SÜD America Inc.'s reports apply only to the specific sample tested under stated test conditions. It is the manufacturer's responsibility to assure the continued compliance of production units of this model. TÜV SÜD America, Inc. shall have no liability for any deductions, inferences or generalizations drawn by the client or others from TÜV SÜD America, Inc.'s issued reports.

This report is the confidential property of the client. As a mutual protection to our clients, the public and TÜV SÜD America, Inc., extracts from the test report shall not be reproduced, except in full without TÜV SÜD America, Inc.'s written approval.

This report must not be used to claim product certification, approval, or endorsement by A2LA, NIST, or any agency of the federal government.