

Welcome

Thank you for choosing Triple+ CLM™ (Cloud Leak Management) system designed to detect Water leaks and prevent the subsequent damages. The Triple+ CLM™ system will give you peace of mind while at home and out of it

♦ Please note

Please read through the instructions carefully and follow the steps of the system's installation and commissioning.

Please maintain this document in a safe place for future reference. When in any doubt, contact your authorized distributor or installer.

♦ Triple+ CLM[™] system

The Triple+ CLMTM system detects and prevents water leaks. When the leak is detected, the system disconnects the water supply wirelessly by activating the shutoff units. Each installation can include multiple various detectors and shutoff units installed on water pipe.

The system is designed to minimize potential flooding damages by shutting down the water supply when the site is inactive and/or when a flooding indication is received.

In addition, the Shutoff can be deactivated manually throughout the End User APP or physical activation of the shut off units. The system is designed for internal use and should be installed by an authorized technician.

♦ Controller technical specification:


| Part No. | CLM-COAMAP-1-02, CLM-COEMEA-1-02 | | | |
|---------------------|---|--|--|--|
| Product description | Triple+ CLM™ HUB easily, securely and reliably communicates with the connected devices and tracks message delivery, allowing the understanding of devices' state. It is ready to take | | | |
| | action | | | |
| Dimensions | 25x68x131mm (1x2.68x5.16") | | | |
| Weight | 155gr (0.33Lbs) | | | |
| Power supply | External Adaptor Input 110-240 V AC | | | |
| Operation voltage | 5V | | | |
| Operating RF | 915 MHz | | | |
| Transmission range | Open space - up to 230m (750ft.) When a wall is within the space - up to 120m (390ft.) To avoid damaging the wireless communication, avoid installation within metal cabinets. | | | |
| Working Temperature | -20 to +50°C (-4 to +122°F) | | | |
| Certifications | FCC ID:2AFOICLMCTRL10 IC:20798-CLMCTRL10 | | | |

WiFi module disclaimer:

The HUB includes a WLAN Smart module (Murata LBWB1ZZYDZ-740) with the following certification information: FCC ID: VPYLBYD / IC ID:772C-LBYD. There have not been any changes to the WLAN Smart module and it is used for communicating bidirectional data between the router and system's elements.

♦ HUB description

- A. Power cable.
- B. Table mount bracket.
- C. Lower cover.
- D. HUB circuit body
- E. USB connector.
- F. RGB LED indicator.
- G. Wall mounting bracket (on the rear part).



HUB installation

When interested in HUB wall mounting, please follow the following instructions:

1. Detach the HUB from the table stand as described below



Attach the wall mounting bracket to intended location and mark the holes for the mounting screws





Detect. Connect. Protect.

 Connect the HUB to the AC/DC adaptor jack. Plug the LAN cable into the LAN inlet, if the HUB will be permanently operated via the LAN.



4. Position the HUB on its permanent location. For wall mounting, bring the HUB's rear mounting pins close to the wall and gently slide it down the wall mount's dimples. Please do not attempt to rotate the HUB on the mounting in order to avoid physical damage to the enclosure.



5. For table mounting, connect the table stand to the HUB and place it on the table.



Expected HUB LED behavior

- Normal functioning mode (when HUB operates on AC power): the HUB RGB LED should present the system statuses/alerts (as described below) repeatedly green blink every 5 seconds (see attached time diagram).
- Power saving mode (when HUB operates on its backup batteries): the HUB RGB LED should present the system statuses/alerts (as described below) once in 3 cycles (about 15 seconds)
- Maintenance mode (installation/reset): the HUB should present the maintenance status repeatedly

4. LED colors mapping

| Alert/Status type | RGB LED Indication | | | |
|---|------------------------------|---|----------|----------|
| | GREEN | BLUE | RED | |
| Faultless communication the HUB with the componer and with the server | all | Blinking | | |
| Failure in communicatic with the server with any of th system components | or ne | | Blinking | |
| Battery status at least one the shutoff units too low and is allowing to clo it (them) in ca of leak even | ne is not ise se | | | Blinking |
| Reset to facto settings | ry | ON steady for 10 seconds after the reset | | |

Warranty instructions

Please visit $\underline{\text{www.tripleplus.io/support}}$ for warranty, technical support, and self-solving tools.