RF exposure Estimation

1. Introduction

Product:	BLE Smart Home Module
Model no.:	IPBM-06
FCC ID:	2AOYS-IPBM06
Options and accessories:	Nil
Rating:	3.3V
RF Transmission Frequency:	2402MHz-2480MHz
No. of Operated Channel:	40
Modulation:	GFSK
Antenna Type:	Internal Antenna
Antenna Gain:	0dBi
Description of the EUT:	The Equipment Under Test (EUT) is BLE Smart Home Module operated at 2.4GHz

2. Limit and Guidelines on Exposure to Electromagnetic Fields

According to§15.247(e)(i) and §1.1307(b)(1), systems operating under the provisions of this section shall be operated in a manner that ensure that the public is not exposed to radio frequency energy level in excess of the Commission's guideline.

According to KDB 447498 D01 Mobile Portable RF Exposure v05r02, no SAR required if power is lower than the flowing threshold:

The 1-g and 10-g SAR test exclusion thresholds for 100 MHz to 6 GHz at test separation distances \leq 50 mm are determined by:

[(max. power of channel, including tune-up tolerance, mW)/(min. test separation distance, mm)] $[\sqrt{f(GHz)}] \le 3.0$ for 1-g SAR and ≤ 7.5 for 10-g extremity SAR, where

- f(GHz) is the RF channel transmit frequency in GHz
- Power and distance are rounded to the nearest mW and mm before calculation25
- The result is rounded to one decimal place for comparison
- 3.0 and 7.5 are referred to as the numeric thresholds in the step 2 below

The test exclusions are applicable only when the minimum test separation distance is \leq 50 mm and for transmission frequencies between 100 MHz and 6 GHz. When the minimum test separation distance is < 5 mm, a distance of 5 mm according to 5) in section 4.1 is applied to determine SAR test exclusion.

3. Calculation method

[(max. power of` channel, including tune-up tolerance, mW)/(min. test separation distance, mm)] $\cdot [\sqrt{f(GHz)}] \le 3.0$

Conducted Power + tune up tolerance = 4.15mW (6.18dBm) Distance = 5 mm f = 2.402 GHz [4.15/5] * SQRT(2.402) = 1.29 $1.29 \le 3.0$ Therefore, excluded from SAR testing.

TÜV SÜD Certification and Testing (China) Co., Ltd. Shenzhen Branch

Reviewed by:

Johnshi

John Zhi/ Project Manager Date: 2018-02-06

Prepared By:

Moon Xiong/Project Engineer Date: 2018-02-05