



FCC Radio Test Report

FCC ID: 2AXLP-CONNECTCHECK

: BTL-FCCP-4-2308T050 Report No.

Equipment : ConnectCheck™ **Model Name** : ConnectCheck™

Brand Name : IGT

: International Game Technology Applicant : 9295 Prototype Drive, Reno, NV Address

Radio Function : NFC (13.56 MHz)

FCC Rule Part(s) : FCC CFR Title 47, Part 15, Subpart C (15.225)

Measurement : ANSI C63.10-2013

Procedure(s)

Date of Receipt : 2022/11/17

Date of Test : 2022/11/29 ~ 2023/6/28

Issued Date : 2023/9/6

The above equipment has been tested and found in compliance with the requirement of the above standards by BTL Inc.

: Eddie Lee, Engineer Prepared by

Approved by

BTL Inc.

No.18, Ln. 171, Sec. 2, Jiuzong Rd., Neihu Dist., Taipei City 114, Taiwan

Tel: +886-2-2657-3299 Fax: +886-2-2657-3331 Web: www.newbtl.com Service mail: btl_qa@newbtl.com



Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **BTL** issued reports.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the **ISO/IEC 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

Project No.: 2308T050 Page 2 of 40 Report Version: R00





CONTENTS REVISION HISTORY 5 SUMMARY OF TEST RESULTS 6 1.1 **TEST FACILITY** 7 MEASUREMENT UNCERTAINTY 1.2 7 1.3 **TEST ENVIRONMENT CONDITIONS** 7 2 **GENERAL INFORMATION** 8 2.1 **DESCRIPTION OF EUT** 8 2.2 **TEST MODES** 9 2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED 10 2.4 SUPPORT UNITS 11 3 AC POWER LINE CONDUCTED EMISSIONS TEST 12 3.1 LIMIT 12 3.2 TEST PROCEDURE 12 **DEVIATION FROM TEST STANDARD** 3.3 12 3.4 **TEST SETUP** 13 **TEST RESULT** 3.5 13 RADIATED EMISSIONS TEST 14 4 4.1 14 LIMIT 4.2 **TEST PROCEDURE** 15 4.3 **DEVIATION FROM TEST STANDARD** 15 4.4 **TEST SETUP** 15 4.5 **EUT OPERATING CONDITIONS** 16 4.6 TEST RESULT - 9 KHZ TO 30 MHZ- FCC PART 15.209 16 4.7 TEST RESULT - 30 MHZ TO 1 GHZ - FCC PART 15.209 16 TEST RESULT - FCC PART 15.225 4.8 16 5 FREQUENCY STABILITY 17 5.1 LIMIT 17 5.2 **TEST PROCEDURE** 17 **DEVIATION FROM TEST STANDARD** 5.3 17 5.4 **EUT OPERATING CONDITIONS** 17 5.5 **TEST RESULT** 17 20 DB BANDWIDTH 18 6 6.1 LIMIT 18 6.2 **TEST PROCEDURE** 18 6.3 **DEVIATION FROM TEST STANDARD** 18 6.4 **TEST SETUP** 18 **EUT OPERATING CONDITIONS** 18 6.5 6.6 **TEST RESULT** 18 7 LIST OF MEASURING EQUIPMENTS 19 8 **EUT TEST PHOTO** 20 9 **EUT PHOTOS** 20 APPENDIX A AC POWER LINE CONDUCTED EMISSIONS 21 APPENDIX B RADIATED EMISSIONS - 9 KHZ TO 30 MHZ 26 APPENDIX C RADIATED EMISSIONS - 30 MHZ TO 1 GHZ 31 RADIATED EMISSIONS - FCC PART 15.225 APPENDIX D 34 APPENDIX E FREQUENCY STABILITY MEASUREMENT 37



APPENDIX F	20 DB BANDWIDTH	39

Project No.: 2308T050 Page 4 of 40 Report Version: R00



REVISION HISTORY

Report No.	Version	Description	Issued Date	Note
BTL-FCCP-4-2308T050	R00	Original Report.	2023/9/6	Valid

Project No.: 2308T050 Page 5 of 40 Report Version: R00



1 SUMMARY OF TEST RESULTS

Test procedures according to the technical standards.

Standard(s) Section	Description	Test Result	Judgement	Remark
15.207	AC Power Line Conducted Emissions	APPENDIX A	Pass	
15.35 15.205 15.209 15.225	Radiated Emissions	APPENDIX B APPENDIX C APPENDIX D	Pass	
15.225(e)	Frequency Stability	APPENDIX E	Pass	
15.203	Antenna Requirement		Pass	
15.215(c)	20 dB Bandwidth	APPENDIX F	Pass	

NOTE:

- (1) "N/A" denotes test is not applicable in this Test Report.
- (2) The report format version is TP.1.1.1.
- (3) According to the declaration of manufacturer, FCC ID: 2AXLP-CONNECTCHECK is a variant of FCC ID: 2AXLP-WINCHECKS2.

The differences as following:

FOOID	0.00
FCC ID	Differences
2AXLP-WINCHECKS2	WinCheck™S2
2AXLP-CONNECTCHECK	ConnectCheck™

The difference between two versions is that the equipment name & model name are changed, and the rests remain identical.

Thus, the test data of FCC ID: 2AXLP-WINCHECKS2, report no. BTL-FCCP-4-2210T119, is leveraged in this test report to demonstrate the compliance of FCC ID: 2AXLP-CONNECTCHECK.

Project No.: 2308T050 Page 6 of 40 Report Version: R00

1.1 TEST FACILITY

The test locations stated below are under the TAF Accreditation Number 0659.	
The test location(s) used to collect the test data in this report are:	
No. 68-1, Ln. 169, Sec. 2, Datong Rd., Xizhi Dist., New Taipei City 221, Taiwan	
(FCC DN: TW0659)	

 ⊠ C05 □ CB08 □ CB11 □ SR10

 No. 72, Ln. 169, Sec. 2, Datong Rd., Xizhi Dist., New Taipei City 221, Taiwan

(FCC DN: TW0659)

□ C06 ⊠ CB21 □ CB22

1.2 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement $\mathbf{y} \pm \mathbf{U}$, where expanded uncertainty \mathbf{U} is based on a standard uncertainty multiplied by a coverage factor of $\mathbf{k} = \mathbf{2}$, providing a level of confidence of approximately $\mathbf{95}$ %. The measurement instrumentation uncertainty considerations contained in CISPR 16-4-2. The BTL measurement uncertainty is less than the CISPR 16-4-2 $\mathbf{U}_{\text{cispr}}$ requirement.

A. AC power line conducted emissions test:

-				
	Test Site	Method	Measurement Frequency Range	U (dB)
	C05	CISPR	150 kHz ~ 30MHz	3.44

B. Radiated emissions test:

Test Site	Method	Measurement Frequency Range	U (dB)
CD04	CISPR	9 kHz ~ 150 kHz	2.82
CB21	CISER	150 kHz ~ 30 MHz	2.58

Test Site	Measurement Frequency Range	U (dB)
	0.03 GHz ~ 0.2 GHz	4.17
	0.2 GHz ~ 1 GHz	4.72
CB24	1 GHz ~ 6 GHz	5.21
CB21	6 GHz ~ 18 GHz	5.51
	18 GHz ~ 26 GHz	3.69
	26 GHz ~ 40 GHz	4.23

NOTE:

Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.

1.3 TEST ENVIRONMENT CONDITIONS

Test Item	Environment Condition	Test Voltage	Tested by
AC Power Line Conducted Emissions	19 °C, 65 %	AC 120V	Paul Shen
Radiated emissions (9KHz-30MHz)	Refer to data	AC 120V	Mark Wang
Radiated emissions (30MHz TO 1000MHz)	Refer to data	AC 120V	Mark Wang
Frequency Stability	23 °C, 55 %	AC 120V	Tim Lee
20 dB Bandwidth	23 °C, 55 %	AC 120V	Tim Lee

Project No.: 2308T050 Page 7 of 40 Report Version: R00



2 GENERAL INFORMATION

2.1 DESCRIPTION OF EUT

Equipment	ConnectCheck™	
Model Name	ConnectCheck™	
Brand Name	IGT	
Model Difference	N/A	
Power Source	DC Voltage supplied from AC/DC adapter.	
	EUT: 5V, 1A	
Power Rating	For Adapter:	
	I/P: 100-240V~50/60Hz 0.3A O/P: 5.0V 2.0A 10.0W	
Products Covered	* Adapter: NETZTEIL / ICP12-050-2000D	
Operation Frequency	13.56 MHz	
Max H-field strength	79.69 dBuV/m@3m(Peak)	
Test Model	ConnectCheck™	
Sample Status	Engineering Sample	
EUT Modification(s)	N/A	

NOTE:

- (1) The above EUT information is declared by manufacturer and for more detailed features description, please refers to the manufacturer's specifications or user's manual.
- (2) In this report, all the test results refer to BTL-FCCP-4-2210T119 report due to the device is identical to the referencing report and, after evaluated, no need to re-test.

(3) Channel List:

Channel	Frequency (MHz)
01	13.56

(4) Table for Filed Antenna:

Ant.	Brand	Model Name	Antenna Type	Connector	Gain (dBi)
NFC	N/A	N/A	loop antenna	N/A	N/A

(5) The above Antenna information are derived from the antenna data sheet provided by manufacturer and for more detailed features description, please refer to the manufacturer's specifications, the laboratory shall not be held responsible.

Project No.: 2308T050 Page 8 of 40 Report Version: R00



2.2 TEST MODES

Test Items	Test mode	Channel	Note
AC power line conducted emissions	Normal/Idle	-	-
Radiated emissions (9KHz-30MHz)	TX	01	-
Radiated emissions (30MHz TO 1000MHz)	TX	01	
Frequency Stability	TX	01	-
20 dB Bandwidth	TX	01	-

NOTE:

(1)	 The Radiated emissions test was verified based on the worst 	t conducted power and Bandwidth test results
	reported in the original report.	


Project No.: 2308T050 Page 9 of 40 Report Version: R00




2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED

Equipment letters and Cable numbers refer to item numbers described in the tables of clause 2.4.

AC Power Line Conducted Emissions Test



Radiated Emissions Test



Project No.: 2308T050 Page 10 of 40 Report Version: R00



2.4 SUPPORT UNITS

Item	Equipment	Brand	Model No. Series No.		Remarks
Α	Adapter	NETZTEIL	ICP12-050-2000D	N/A	Supplied by test requester.
В	NB	ASUS	X450J N/A F		Furnished by test lab.
С	USB Mouse	DELL	MOCZUL	CN-049TWY-PR C00-79E-01HA	Furnished by test lab.
D	PC	DELL	OptiPlex 7080	9T3HN A00	Furnished by test lab.
E	NB	HP	TPN-I119	N/A	Furnished by test lab.
F	USB	Lexar	S60	N/A	Supplied by test requester.

Item	Shielded	Ferrite Core	Length	Cable Type	Remarks
1	N/A	N/A	1.2m	Power Cable	Furnished by test lab.
2	N/A	N/A	2m	RJ-45 Cable	Furnished by test lab.
3	N/A	N/A	1.2m	USB A to B	Furnished by test lab.
4	N/A	FC1000	1m	RJ45 Cable	Furnished by test lab.
5	N/A	N/A	1.8m	Type A To USB Cable	Supplied by test requester.



3 AC POWER LINE CONDUCTED EMISSIONS TEST

3.1 LIMIT

Frequency	Limit (dBμV)		
(MHz)	Quasi-peak	Average	
0.15 - 0.5	66 - 56 *	56 - 46 *	
0.50 - 5.0	56	46	
5.0 - 30.0	60	50	

NOTE:

- (1) The tighter limit applies at the band edges.
- (2) The limit of " * " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.
- (3) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor (if use)

Margin Level = Measurement Value - Limit Value

Calculation example:

Reading Level		Correct Factor		Measurement Value
38.22	+	3.45	=	41.67

Measurement Value		Limit Value		Margin Level
41.67	-	60	=	-18.33

The following table is the setting of the receiver.

Receiver Parameter	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 KHz

3.2 TEST PROCEDURE

- a. The EUT was placed 0.8 m above the horizontal ground plane with the EUT being connected to the power mains through a line impedance stabilization network (LISN).
 - All other support equipment were powered from an additional LISN(s).
 - The LISN provides 50 Ohm/50uH of impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle to keep the cable above 40 cm.
- c. Excess I/O cables that are not connected to a peripheral shall be bundled in the center.
 - The end of the cable will be terminated, using the correct terminating impedance.
 - The overall length shall not exceed 1 m.
- d. The LISN is spaced at least 80 cm from the nearest part of the EUT chassis.
- e. For the actual test configuration, please refer to the related Item EUT TEST PHOTO.

NOTE:

- (1) In the results, each reading is marked as Peak, QP or AVG per the detector used. BW=9 kHz (6 dB Bandwidth)
- (2) All readings are Peak unless otherwise stated QP or AVG in column of Note. Both the QP and the AVG readings must be less than the limit for compliance.


3.3 DEVIATION FROM TEST STANDARD

No deviation.

Project No.: 2308T050 Page 12 of 40 Report Version: R00



3.4 TEST SETUP



3.5 TEST RESULT

Please refer to the APPENDIX A.



4 RADIATED EMISSIONS TEST

4.1 LIMIT

	FCC Part 15.209						
Frequency	Field Strength Limitation		Field Strength Limitation at 3m Measurement Dist				
(MHz)	(uV/m)	Dist	(uV/m)	(dBuV/m)			
0.009 - 0.490	2400 / F(KHz)	300m	10000 * 2400/F(KHz)	20log 2400/F(KHz) + 80			
0.490 - 1.705	24000 / F(KHz)	30m	100 * 24000/F(KHz)	20log 24000/F(KHz) + 40			
1.705 – 30.00	30	30m	100* 30	20log 30 + 40			
30.0 - 88.0	100	3m	100	20log 100			
88.0 – 216.0	150	3m	150	20log 150			
216.0 – 960.0	200	3m	200	20log 200			
Above 960.0	500	3m	500	20log 500			
		FCC P	art 15.225(a)/(b)/(c)				
Frequency	Field Strength Lir	nitation	Field Strength Limitation at 3m Measurement Dist				
(MHz)	(uV/m)	Dist	(uV/m)	(dBuV/m)			
13.553 – 13.567	15,848	30 m	15,848*100	124			
13.567 – 13.710	334	30 m	334*100	90.5			
13.110 – 13.410 13.710 – 14.010	1 106 130 m i		106*100	80.5			

NOTE:

- (1) The tighter limit shall apply at the boundary between two frequency range.
- (2) Limitation expressed in dBuV/m is calculated by 20log Emission Level (uV/m).
- (3) If measurement is made at 3m distance, then F.S Limitation at 3m distance is adjusted by using the formula of $L_{d1} = L_{d2} * (d_2/d_1)^2$.

Example:

F.S Limit at 30m distance is 30uV/m , then F.S Limitation at 3m distance is adjusted as L_{d1} = L₁ = 30uV/m * $(10)^2$ = 100 * 30 uV/m

(4) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor(if use)

Margin Level = Measurement Value – Limit Value

Project No.: 2308T050 Page 14 of 40 Report Version: R00



4.2 TEST PROCEDURE

- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(below 1GHz).
- b. The height of the equipment or of the substitution antenna shall be 0.8 m or 1.5m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- c. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- d. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.
- e. For the actual test configuration, please refer to the related Item –EUT Test Photos.

NOTE: (FCC PART 15.209)

- a. Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode with Detector BW=120 kHz.
- b. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.

NOTE: (FCC PART 15.225)

- a. Spectrum Setting:
 - 9 KHz 150 KHz, RBW= 200Hz, VBW=200Hz, Sweep time = 200 ms.
 - 150 K Hz -30 MHz, RBW= 10 KHz, VBW=10 KHz, Sweep time = 200 ms.
 - 30 MHz 1000 MHz, RBW= 100 KHz, VBW=100 KHz, Sweep time = 200 ms.
- b. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.
- c. The Log-Bicon Antenna will use to test frequency range from 30MHz to 1000MHz and the Loop Antenna will use to test frequency below 30MHz.


4.3 DEVIATION FROM TEST STANDARD

No deviation.

4.4 TEST SETUP

9 KHz to 30 MHz RX Antenna Im Metal Full Soldered Ground Plane Spectrum Analyzer / Receiver





4.5 EUT OPERATING CONDITIONS

The EUT was programmed to be in continuously transmitting mode.

4.6 TEST RESULT - 9 kHZ TO 30 MHZ- FCC PART 15.209

Please refer to the APPENDIX B

4.7 TEST RESULT - 30 MHZ TO 1 GHZ - FCC PART 15.209

Please refer to the APPENDIX C.

4.8 TEST RESULT - FCC PART 15.225

Please refer to the APPENDIX D.

NOTE:

(1) No limit: This is fundamental signal, the judgment is not applicable. For fundamental signal judgment was referred to Peak output test.

Project No.: 2308T050 Page 16 of 40 Report Version: R00



5 FREQUENCY STABILITY

5.1 LIMIT

FCC Part 15.225(e)

The frequency tolerance of the carrier signal shall be maintained within +/-0.01% of the operating frequency over a temperature variation of - 20 degrees to + 50 degrees C at normal supply voltage, and for a variation in the primary supply voltage from 85% to 115% of the rated supply voltage at a temperature of 20 degrees C.

For battery operated equipment, the equipment tests shall be performed using a new battery.

5.2 TEST PROCEDURE

- a. The equipment under test was connected to an external AC power supply and the RF output was connected to a frequency counter via feed through attenuators. The EUT was placed inside the temperature chamber.
- b. At room temperature (25±5°C), an external variable AC power supply was connected to the EUT. The frequency of the transmitter was measured for 115%, 100% and 85% of the nominal operating input voltage.

5.3 DEVIATION FROM TEST STANDARD

No deviation.

5.4 EUT OPERATING CONDITIONS

The EUT was programmed to be in continuously transmitting mode.

5.5 TEST RESULT

Please refer to the APPENDIX E.

Project No.: 2308T050 Page 17 of 40 Report Version: R00

6 20 DB BANDWIDTH

6.1 LIMIT

FCC Part 15.215(c)

Intentional radiators operating under the alternative provisions to the general emission limits, as contained in §15.217 through §15.257 and in subpart E of this part, must be designed to ensure that the 20 dB bandwidth of the emission, or whatever bandwidth may otherwise be specified in the specific rule section under which the equipment operates, is contained within the frequency band designated in the rule section under which the equipment is operated.

6.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting: RBW= 1 kHz, VBW=1 kHz, Sweep time = 20 ms.

6.3 DEVIATION FROM TEST STANDARD

No deviation.

6.4 TEST SETUP

EUT	SPECTRUM
	ANALYZER

6.5 EUT OPERATING CONDITIONS

The EUT was programmed to be in continuously transmitting mode.

6.6 TEST RESULT

Please refer to the APPENDIX F.

Project No.: 2308T050 Page 18 of 40 Report Version: R00

LIST OF MEASURING EQUIPMENTS

	AC Power Line Conducted Emissions								
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until			
1	TWO-LINE V-NETWORK	R&S	ENV216	101521	2022/9/28	2023/9/27			
2	Test Cable	EMCI	EMCCFD300-BM -BMR-5000	220331	2022/3/31	2023/3/30			
3	EMI Test Receiver	R&S	ESR 7	101433	2022/11/16	2023/11/15			
4	Measurement Software	EZ	EZ_EMC (Version NB-03A1-01)	N/A	N/A	N/A			

	Radiated Emissions								
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until			
1	Preamplifier	EMCI	EMC330N	980850	2022/9/19	2023/9/18			
2	Preamplifier	EMCI	EMC001340	980579	2022/9/30	2023/9/29			
3	Test Cable	EMCI	EMC104-SM-SM- 1000	220319	2023/3/14	2024/3/13			
4	Test Cable	EMCI	EMC104-SM-SM- 3000	220322	2023/3/14	2024/3/13			
5	Test Cable	EMCI	EMC104-SM-SM- 7000	220324	2023/3/14	2024/3/13			
6	EXA Signal Analyzer	keysight	N9020B	MY57120120	2023/2/24	2024/2/23			
7	Loop Ant	Electro-Metrics	EMCI-LPA600	291	2022/9/19	2023/9/18			
8	Log-bicon Antenna	Schwarzbeck	VULB9168	1369	2023/5/9	2024/5/8			
9	6dB Attenuator	EMCI	EMCI-N-6-06	AT-06001	2023/5/9	2024/5/8			
10	Measurement Software	EZ	EZ_EMC (Version NB-03A1-01)	N/A	N/A	N/A			

	Frequency Stability Measurement										
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	erial No. Calibrated Date						
1	Spectrum Analyzer	R&S	FSV7	103032	2022/8/9	2023/8/8					
2	Thermal Chamber	HOLINK	H-TH-2SP-B	EK04101902	2022/6/27	2023/6/26					

	20 dB Bandwidth Measurement									
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until				
1	Spectrum Analyzer	R&S	FSP38	101139	2022/3/2	2023/3/1				

Remark: "N/A" denotes no model name, no serial no. or no calibration specified. All calibration period of equipment list is one year.

Project No.: 2308T050 Page 19 of 40 Report Version: R00



8 EUT TEST PHOTO
Please refer to document Appendix No.: TP-2308T050-FCCP-1 (APPENDIX-TEST PHOTOS).
9 EUT PHOTOS
Please refer to document Appendix No.: EP-2308T050-2 (APPENDIX-EUT PHOTOS).


Project No.: 2308T050 Page 20 of 40 Report Version: R00



APPENDIX A	AC POWER LINE CONDUCTED EMISSIONS

Project No.: 2308T050 Page 21 of 40 Report Version: R00

Ш				
	Test Mode	Normal	Tested Date	2022/12/22
	Test Frequency	-	Phase	Line




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1590	30.13	9.64	39.77	65.52	-25.75	QP	
2		0.1590	17.63	9.64	27.27	55.52	-28.25	AVG	
3	*	0.4402	38.67	9.66	48.33	57.06	-8.73	QP	
4		0.4402	26.83	9.66	36.49	47.06	-10.57	AVG	
5		0.7710	29.51	9.69	39.20	56.00	-16.80	QP	
6		0.7710	16.27	9.69	25.96	46.00	-20.04	AVG	
7		1.7790	26.37	9.73	36.10	56.00	-19.90	QP	
8		1.7790	14.20	9.73	23.93	46.00	-22.07	AVG	
9		10.0095	26.48	9.95	36.43	60.00	-23.57	QP	
10		10.0095	13.00	9.95	22.95	50.00	-27.05	AVG	
11		26.6235	17.60	10.05	27.65	60.00	-32.35	QP	
12		26.6235	12.82	10.05	22.87	50.00	-27.13	AVG	

REMARKS:

(1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value - Limit Value.

Ш					
	Test Mode	Normal	Tested Date	2022/12/22	
	Test Frequency	-	Phase	Neutral	




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1613	28.61	9.65	38.26	65.40	-27.14	QP	
2		0.1613	15.33	9.65	24.98	55.40	-30.42	AVG	
3		0.4425	33.57	9.67	43.24	57.01	-13.77	QP	
4	*	0.4425	25.88	9.67	35.55	47.01	-11.46	AVG	
5		0.8002	23.81	9.70	33.51	56.00	-22.49	QP	
6		0.8002	14.51	9.70	24.21	46.00	-21.79	AVG	
7		1.4663	22.65	9.72	32.37	56.00	-23.63	QP	
8		1.4663	13.52	9.72	23.24	46.00	-22.76	AVG	
9		2.4068	21.03	9.76	30.79	56.00	-25.21	QP	
10		2.4068	12.38	9.76	22.14	46.00	-23.86	AVG	
11		9.7373	19.12	9.98	29.10	60.00	-30.90	QP	
12		9.7373	8.27	9.98	18.25	50.00	-31.75	AVG	

REMARKS:

(1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value - Limit Value.

Project No.: 2308T050 Report Version: R00 Page 23 of 40

Test Mode	Idle	Tested Date	2022/12/22
Test Frequency	-	Phase	Line




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1590	28.87	9.65	38.52	65.52	-27.00	QP	
2		0.1590	16.23	9.65	25.88	55.52	-29.64	AVG	
3		0.4425	33.67	9.67	43.34	57.01	-13.67	QP	
4	*	0.4425	25.63	9.67	35.30	47.01	-11.71	AVG	
5		0.8002	23.49	9.70	33.19	56.00	-22.81	QP	
6		0.8002	14.39	9.70	24.09	46.00	-21.91	AVG	
7		1.7790	21.71	9.74	31.45	56.00	-24.55	QP	
8		1.7790	13.44	9.74	23.18	46.00	-22.82	AVG	
9		2.4068	20.78	9.76	30.54	56.00	-25.46	QP	
10		2.4068	13.16	9.76	22.92	46.00	-23.08	AVG	
11		9.7170	19.59	9.98	29.57	60.00	-30.43	QP	
12		9.7170	8.28	9.98	18.26	50.00	-31.74	AVG	

REMARKS:

(1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value - Limit Value.

Ш				
	Test Mode	Idle	Tested Date	2022/12/22
	Test Frequency	-	Phase	Neutral



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1613	29.33	9.64	38.97	65.40	-26.43	QP	
2		0.1613	15.69	9.64	25.33	55.40	-30.07	AVG	
3	*	0.4402	37.69	9.66	47.35	57.06	-9.71	QP	
4		0.4402	24.02	9.66	33.68	47.06	-13.38	AVG	
5		0.7980	28.93	9.69	38.62	56.00	-17.38	QP	
6		0.7980	16.65	9.69	26.34	46.00	-19.66	AVG	
7		1.1512	27.73	9.70	37.43	56.00	-18.57	QP	
8		1.1512	14.55	9.70	24.25	46.00	-21.75	AVG	
9		1.7745	26.43	9.73	36.16	56.00	-19.84	QP	
10		1.7745	13.19	9.73	22.92	46.00	-23.08	AVG	
11		9.9983	24.25	9.95	34.20	60.00	-25.80	QP	
12		9.9983	11.26	9.95	21.21	50.00	-28.79	AVG	

REMARKS:

(1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value - Limit Value.

Project No.: 2308T050 Page 25 of 40 Report Version: R00



APPENDIX B RADIATED EMISSIONS - 9 KHZ TO 30 MHZ

Project No.: 2308T050 Page 26 of 40 Report Version: R00

	Test Mod	de		TX		Test Date		202	3/6/7	
Te	st Freque	ency	13.	.56MHz		Polarization		Ver	tical	
	Temp	•		26°C		Hum.		63	3%	
50.0 d	BuV/m									
40	_									-
130										_
20										_
										┪
10										
100			_							\dashv
90			1 X							4
80										
70										
υ <u> </u>										
io										\dashv
50 —										4
10										
80										
20.0				2.27	2.00				0.15	⅃
0.009	0.02	0.04	0.05	0.07		09 0.11		2	0.15	MH
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over			
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comm	ent
1	*	0.0422	65.25	25.17	90.42	134.18	-43.76	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.

	Test Mo					TX				Test D				3/6/7	
Te	est Frequ					6MHz				Polariza	ation			tical	
130.0	Temp)			2	6°C				Hun	า.		63	3%	
120 110 100 90 80															
70 — 60 — 60 — 60 — 60 — 60 — 60 — 60 —	1 ×	2 X	3 X	4 X							5 X		6 ×		
10 0.0 0.150	3.14	6.12		9.10		12.09		15.08	18	3.06	21.0)4 24,1	03	30.00	
No.	Mk.	Freq		Rea Le	ding vel	Corr Fac			sure- ent	Lim	it	Over			
		MHz		dB	uV	dE	3	dΒι	ıV/m	dBuV	/m	dB	Detector	Comm	ent
1		2.118	0	47.	.64	-2.9	97	44	.67	88.6	2	-43.95	QP		
2	*	4.745		53.		-5.5			.50	88.6		-41.12	QP		
3		7.040	4	48.	.36	-4.9	94	43	.42	88.6	2	-45.20	QP		
4		8.623		47		-4.3			.15	88.6		-45.47	QP		
5		20.711			.22	-4.5			.70	88.6		-45.92	QP		
6		25.977		47.		-2.0			.19	88.6		-43.43	QP		

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.

	Test Mod			TX		Test Date			3/6/7	
Tes	st Freque	ency		6MHz	i i	Polarization			zontal	
	Temp		2	6°C		Hum.		6	3%	
50.0 dB	BuV/m									_
_	_									
40	_									1
30										4
20										-
										7
10										+
00										-
o			1 X							
0										-
o										-
0										
0										1
0										-
:0										
0.0										
0.009	0.02	0.04	0.05	0.07	0.08 0.		0.12		0.15	MI
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over			
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comm	ent
	*	0.0428	66.65	25.04	91.69	134.06	-42.37	AVG	2	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.

	Test Mo	de		TX		Test Date		202	3/6/7	
Te	st Frequ	iency	13.	56MHz		Polarization	n	Hori	zontal	
	Temp)		26°C		Hum.		6	3%	
130.0 d	BuV/m									_
120										
- A										
10										_
00										_
00										
30										
70										\dashv
so										
1 1										
50 ×										T
40			3 4 X X							
30		2 X	× ×	5 X						_
20										
10										-
D.O										
0.150	3.14	6.12	9.10	12.09	15.08 1		.04 24.	03	30.00	МН
No.	Mk.	Freq.	Reading		Measure-	Limit	Over			
			Level	Factor	ment				_	
	*	MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comm	nent
1	*	1.0664	52.15	0.52	52.67	86.12	-33.45	QP		
2		4.7121	37.06	-5.57	31.49	88.62	-57.13	QP		
3		7.8682	39.56 41.03	-4.64	34.92	88.62	-53.70	QP OB		
<u>4</u> 5		9.2801 10.7584	35.02	-4.11 -3.93	36.92 31.09	88.62 88.62	-51.70 -57.53	QP QP		
6		27.1215	32.94	-3.93 -1.47	31.09	88.62	-57.53 -57.15	QP QP		

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.



APPENDIX C RADIATED EMISSIONS - 30 MHZ TO 1 GHZ

Project No.: 2308T050 Page 31 of 40 Report Version: R00

-	Test Mo	de		TX		Test Date		2023	3/6/28	
Tes	st Frequ			56MHz		Polarization	1		tical	
	Temp		2	5°C		Hum.		5′	1%	
80.0 dE	luV/m									٦
70										
60										
50								_		1
40 —	ķ	2 X				4 3× ×	5 X	6 ×		
30	_^									-
20										-
10										-
0.0										
30.000	127.00	224.00	321.00	418.00	515.00	312.00 709	9.00 800	6.00	1000.00	_MH
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over			
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comme	ent
1		94.5557	51.93	-17.34	34.59	43.50	-8.91	peak		
2		185.9326	50.23	-14.09	36.14	43.50	-7.36	QP		
3		605.9536	42.59	-3.88	38.71	46.00	-7.29	QP		
4		617.9814	44.98	-3.71	41.27	46.00	-4.73	QP		
		700 4000	40.07	4 00	20.47	46.00	7.50	0.0		
5 6	*	738.1360 874.9981	40.27 41.12	-1.80 0.16	38.47 41.28	46.00	-7.53 -4.72	QP QP		

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.

-	Test Mo	de		TX		Test Date		2023	3/6/28	
Tes	t Frequ	iency	13.5	56MHz		Polarization	1	Horiz	zontal	
	Temp)	2	5°C		Hum.		5′	51%	
80.0 dB	uV/m									7
70										
60										
50										
40	1 X	2 3 X X	4 X				5 X	6 ×		
30	_									
20										
10										
0.0										
30.000	127.00	224.00	321.00	418.00	515.00 6	12.00 709	9.00 800	6.00	1000.00	_мн
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over			
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comme	ent
1	*	98.4150	55.93	-16.95	38.98	43.50	-4.52	QP		
2		149.9566	50.29	-11.95	38.34	43.50	-5.16	QP		
3		185.9320	52.36	-14.09	38.27	43.50	-5.23	QP		
4		359.9940	46.36	-9.93	36.43	46.00	-9.57	QP		
5		749.9663	39.52	-1.51	38.01	46.00	-7.99	QP		
6		874.9991	40.88	0.16	41.04	46.00	-4.96	QP		

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.



APPENDIX D RADIATED EMISSIONS - FCC PART 15.225

Project No.: 2308T050 Page 34 of 40 Report Version: R00

٦	est Mod	de	-	ГΧ		Test Date	Э	202	3/6/7	
Tes	t Freque	ency		6MHz		Polarizatio	on		rtical	
	Temp		20	6°C		Hum.		6	3%	
50.0 dB	uV/m									_
40										1
30										4
20										
20										1
10										4
00										_
0										-
o										4
					*					
0										
0										-
o										
0										+
0.0										
13.510	13.52	13.53	13.54	13.55	13.56	13.57 1	3.58 13.	59	13.61	MH
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure ment	- Limit	Over			
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comm	ent
1	*	13.5600	79.42	-4.20	75.22	143.07	-67.85	peak		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.

1	Test Mod	de		TX		Test Date		202	3/6/7	
Tes	t Freque	ency	13.5	6MHz		Polarization	ı	Horiz	zontal	
	Temp	•	2	6°C		Hum.		63	3%	
50.0 dB	uV/m									
40										
30										-
20										-
10										
00										
0					-					1
0					×					
0										1
0										-
0										-
10										-
0.0	12.52	12.52	13.54	12 55	12 50 1	2 5 7 12	E0 12	En	12.01	
13.510 No.	13.52 Mk.	13.53 Freq.	13.54 Reading Level	13.55 Correct Factor	Measure- ment	3.57 13. Limit	.58 13. Over	29	13.61	MH
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comm	ent
1	*	13.5600	83.89	-4.20	79.69	143.07	-63.38	peak		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



APPENDIX E	FREQUENCY STABILITY MEASUREMENT

Project No.: 2308T050 Page 37 of 40 Report Version: R00



Test Mode	тх	Tested Date	2022/12/26

	Condition					Frequency I	Error (ppi	m)				
Temperature	Modulation Mode	Test Freq.	0 min	2 min	5 min	10 min	0 min	2 min	5 min	10 min	Limit (ppm)	Result
				•	•	Nori	nal	•	•			•
T _{20°C} Vmax	CW	13.56	13.559826	13.559826	13.559827	13.559827	-12.83	-12.83	-12.79	-12.79	100	PASS
T _{20°C} Vmin	CW	13.56	13.559826	13.559826	13.559826	13.559827	-12.83	-12.83	-12.83	-12.76	100	PASS
						Extre	eme					
T _{45°C} Vnom	CW	13.56	13.559855	13.559855	13.559856	13.559856	-10.69	-10.69	-10.62	-10.62		PASS
T _{40°C} Vnom	CW	13.56	13.559855	13.559855	13.559856	13.559856	-10.69	-10.69	-10.62	-10.62		PASS
T _{30°C} Vnom	CW	13.56	13.559855	13.559855	13.559855	13.559856	-10.69	-10.69	-10.69	-10.62		PASS
T _{20°C} Vnom	CW	13.56	13.559826	13.559826	13.559826	13.559827	-12.83	-12.83	-12.83	-12.76	100	PASS
T _{10°C} Vnom	CW	13.56	13.559826	13.559826	13.559826	13.559827	-12.83	-12.83	-12.83	-12.76		PASS
T5 _{°C} Vnom	CW	13.56	13.559826	13.559826	13.559826	13.559826	-12.83	-12.83	-12.83	-12.83		PASS

NOTE: 0.01 % = 100 ppm.

Project No.: 2308T050 Page 38 of 40 Report Version: R00




Report No.: BTL-FCCP-4-2308T050 APPENDIX F 20 DB BANDWIDTH

Project No.: 2308T050 Page 39 of 40 Report Version: R00



Test Mode TX

Frequency (MHz)	20 dB Bandwidth (MHz)	Operated Frequency Range (MHz)	Designated Frequency Band (MHz)	Result
13.56	13.56	0.002489	0.014	Complied



Date: 26.DEC.2022 15:41:50

End of Test Report