

# **FCC &ISED Radio Test Report**

FCC ID: ACJ-SU-GX70 IC:216A-SUGX70

The report concerns: Original Grant

Report Reference No.....: 22EFSS10067 11211

Date Sample(s) Received.....: 2022-11-25

Date of Tested....: From 2022-11-25 to 2022-12-28

Date of issue....: 2022-12-28

Testing Laboratory .....: DongGuanShuoXin Electronic Technology Co., Ltd.

Zone A, 1F, No. 6, XinGang Road YuanGang Street,

XinAn District, ChangAn Town, DongGuan City, Address .....:

GuangDong, China

Panasonic Corporation of North America Applicant's name for FCC.....

Two Riverfront Plaza, 9th Floor, Newark, New Address for FCC....:

Jersey,07102-5490,United States

Panasonic Canada Inc. Applicant's name for IC.....

5770 Ambler Drive Mississauga ON L4W 2T3 Address for IC....:

Canada

Manufacturer....: Panasonic Corporation

**Network Audio Amplifier** Equipment....:

Trade Mark .....: **Technics** Model ....: SU-GX70

I/P: 120V/60Hz 63W Ratings .....:

**Test Engineer:** 

**Responsible Engineer:** 

Smile Wang

**Authorized Signatory:** 

King Wang



Table of Contents	Page
1. TEST REPORT DECLARE	5
2. SUMMARY OF TEST RESULTS	6
2.1. MEASUREMENT UNCERTAINTY	7
3. GENERAL INFORMATION	8
3.1. GENERAL DESCRIPTION OF EUT	8
3.2. DESCRIPTION OF TEST MODES	10
3.3. PARAMETERS OF TEST SOFTWARE	11
3.4. BLOCKDIAGRAMSHOWINGTHECONFIGURATIONOFSYSTEMTESTED	11
3.5. SUPPORT UNITS	11
3.6. TEST ENVIRONMENT CONDITIONS	12
4. AC POWER LINE CONDUCTED EMISSIONS TEST	13
4.1. LIMIT	13
4.2. TEST PROCEDURE	13
4.3. MEASUREMENT INSTRUMENTS LIST	13
4.4. TESTSETUP	14
4.5. EUT OPERATING CONDITIONS	14
4.6. TEST RESULTS	15
5. RADIATED EMISSION TEST	17
5.1. LIMIT	17
5.2. TEST PROCEDURE AND SETTING	18
5.3. MEASUREMENT INSTRUMENTS LIST	19
5.4. TESTSETUP	19
5.5. EUT OPERATING CONDITIONS	20
5.6. TEST RESULTS - 9 KHZ TO 30MHZ	21
5.7. TEST RESULTS ABOVE 1000MHZ	22 24
5.8. TEST RESULTS - ABOVE 1000MHZ(BAND EDGE) 5.9. TEST RESULTS - ABOVE 1000MHZ(HARMONIC)	32
· · · · · · · · · · · · · · · · · · ·	
6. NUMBER OF HOPPING FREQUENCY	44
6.1. LIMIT 6.2. TEST PROCEDURE AND SETTING	44 44
6.2. TEST PROCEDURE AND SETTING 6.3. MEASUREMENT INSTRUMENTS LIST	44 44
6.4. TEST SETUP	44
VT. 1201 V21V1	77



Table of Contents	Page
6.5. EUT OPERATION CONDITIONS	44
6.6. TEST RESULTS	45
7. AVERAGE TIME OF OCCUPANCY	46
7.1. LIMIT	46
7.2. TEST PROCEDURE AND SETTING	46
7.3. MEASUREMENT INSTRUMENTS LIST	46
7.4. TEST SETUP	46
7.5. EUT OPERATION CONDITIONS	46
7.6. TEST RESULTS	47
8. HOPPING CHANNEL SEPARATION MEASUREMENT	49
8.1. LIMIT	49
8.2. TEST PROCEDURE AND SETTING	49
8.3. MEASUREMENT INSTRUMENTS LIST	49
8.4. TEST SETUP	49
8.5. EUT OPERATION CONDITIONS	49
8.6. TEST RESULTS	50
9. BANDWIDTH TEST	52
9.1. LIMIT	52
9.2. TEST PROCEDURE AND SETTING	52
9.3. MEASUREMENT INSTRUMENTS LIST	52
9.4. TEST SETUP	52
9.5. EUT OPERATION CONDITIONS	52
9.6. TEST RESULTS	53
10. MAXIMUM OUTPUT POWER	55
10.1. LIMIT	55
10.2. TEST PROCEDURE AND SETTING	55
10.3. MEASUREMENT INSTRUMENTS LIST	55
10.4. TEST SETUP	55
10.5. EUT OPERATION CONDITIONS	55
10.6. TEST RESULTS	56
11. CONDUCTED SPURIOUS EMISSION	59
11.1. LIMIT	59
11.2. TEST PROCEDURE AND SETTING	59
11.3. MEASUREMENT INSTRUMENTS LIST	59





Table of Contents	Page
11.4. TEST SETUP	59
11.5. EUT OPERATION CONDITIONS	59
11.6. TEST RESULTS	60
12. FREQUENCY STABILITY MEASUREMENT	62
12.1. LIMIT	62
12.2. TEST PROCEDURE	62
12.3. MEASUREMENT INSTRUMENTS LIST	62
12.4. TEST SETUP	62
12.5. EUT OPERATION CONDITIONS	62
12.6. TEST RESULTS	63



#### **1TEST REPORT DECLARE**

Applicant for FCC	Panasonic Corporation of North America
Address for FCC	Two Riverfront Plaza, 9th Floor, Newark, New Jersey,07102-5490,United States
Applicant for IC	Panasonic Canada Inc.
Address for IC	5770 Ambler Drive Mississauga ON L4W 2T3 Canada
Manufacturer	Panasonic Corporation
Address	1006, Oaza Kadoma, kadoma-shi, Osaka, 571-8501, Japan
Factory	Panasonic AVC Networks Johor Malaysia
Address	IE,PLO 460, Jalan Bandar, 81700 Pasir Gudang, Johor, Malaysia
Equipment	Network Audio Amplifier
Model No.	SU-GX70
Trade Mark	Technics
Standard	FCC Part15, Subpart C (15.247) RSS-247 Issue 2, Feb. 2017 RSS-Gen Issue 5, Apr. 2018 ANSI C63.10-2013

#### We Declare:

The equipment described above is tested by DongGuanShuoXin Electronic Technology Co., Ltd(ATT). and in the configuration tested the equipment complied with the standards specified above. The test results are contained in this test report and DongGuanShuoXin Electronic Technology Co., Ltd.(ATT) is assumed of full responsibility for the accuracy and completeness of these tests.

ATT is not responsible for the sampling stage, so the results only apply to the sample as received.

ATT's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. ATT shall have no liability for any declarations, inferences or generalizations drawn by the client or others from ATT issued reports.



# **2SUMMARY OF TEST RESULTS**

The EUT have been tested according to the applicable standards as referenced below:

Standard(s	s) Section	Test Item	Judgment	Remark
FCC	ISED	iest item	Judgment	Kemark
15.207	RSS-Gen8.8	AC Power Line Conducted Emissions	PASS	
15.247(d) 15.205(a) 15.209(a)	RSS-247 5.5 RSS-Gen 8.9 RSS-Gen 8.10	Radiated Emission	PASS	
15.247(a)(1)(iii)	RSS-247 5.1 (d)	Number of Hopping Frequency	PASS	
15.247(a)(1)(iii)	RSS-247 5.1 (d)	Average Time Of Occupancy	PASS	
15.247(a)(1)	RSS-247 5.1 (b)	Hopping Channel Separation	PASS	
15.247(a)(1)	RSS-247 5.1 (a) RSS-Gen 6.7	Bandwidth	PASS	
15.247(a)(1)	RSS-247 5.1 (b)	Maximum Output Power	PASS	
15.247(d)	RSS-247 5.5	Conducted Spurious Emission	PASS	
-	RSS-Gen6.11	Frequency Stability	PASS	
15.203	-	Antenna Requirement	PASS	Note(2)

#### Note:

- (1) "N/A" denotes test is not applicable in this test report
- (2) The device what use a permanently attached antenna were considered sufficient to comply with the provisions of 15.203.



#### 2.1 MEASUREMENT UNCERTAINTY

Test Item	Uncertainty
Uncertainty for Conduction emission test (9kHz-150kHz)	3.7 dB
Uncertainty for Conduction emission test (150kHz-30MHz)	3.3 dB
Uncertainty for Radiation Emission test (30MHz-200MHz)	4.60 dB (Polarize: V)
Officertainty for Radiation Emission test (30km/2-200km/2)	4.60 dB (Polarize: H)
Lincortainty for Padiation Emission toot (200MHz 1CHz)	6.10 dB (Polarize: V)
Uncertainty for Radiation Emission test (200MHz-1GHz)	5.08 dB (Polarize: H)
Uncertainty for Dadiation Emission toot (10Hz 60Hz)	5.01 dB (Polarize: V)
Uncertainty for Radiation Emission test (1GHz-6GHz)	5.01 dB (Polarize: H)
Uncertainty for Dadiation Emission test (CCUT 19CUT)	5.26 dB (Polarize: V)
Uncertainty for Radiation Emission test (6GHz-18GHz)	5.26 dB (Polarize: H)
Lineartainty for Dadiction Emission toot (1901 - 1901 -	5.06 dB (Polarize: V)
Uncertainty for Radiation Emission test (18GHz-40GHz)	5.06 dB (Polarize: H)
Uncertainty for radio frequency	±0.048kHz
Uncertainty for conducted RF Power	±0.32dB

#### Note:

This uncertainty represents an expanded uncertainty expressed at approximately the 95%confidence level using a coverage factor of k=2.

# **Test Facility:**

The Test site used by DongGuanShuoXin Electronic Technology Co., Ltd. to collect test data is located on the Zone A, 1F, No. 6, XinGang Road YuanGang Street, XinAn District, ChangAn Town, DongGuan City, GuangDong, China

The test facility is recognized, certified, or accredited by the following organizations:

Item	Registration No.	Expiration Date
CNAS	L3098	2024-08-27
A2LA	4893.01	2024-06-30
Innovation, Science and Economic Development Canada (ISED)	11033A CAB identifer:CN0083	2024-06-30
Federal Communications Commission (FCC)	171688 Designation No.:CN1235	2024-06-30



# **3 GENERAL INFORMATION**

# 3.1 GENERAL DESCRIPTION OF EUT

Equipment	Network Audio Amplifier	
Brand Name	Technics	
Test Model	SU-GX70	
Series Model	N/A	
Model Difference(s)	N/A	
Hardware Version	PR	
Software Version	22.02	
Power Source	AC Mains	
Power Rating	120V~ 63W 60Hz	
Operation Frequency	2402 MHz ~ 2480 MHz	
Modulation Technology	GFSK, π/4-DQPSK, 8-DPSK	
Bit Rate of Transmitter	1Mbps /2Mbps /3Mbps	
Antenna Information	Antenna Type: PCB	Maximum Peak Gain:1.69dBi
Max. Output Power	1Mbps: 7.964dBm (0.00626W) 2Mbps: 8.471dBm (0.00703W) 3Mbps: 9.047dBm (0.00803W)	

# Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the user's manual.





# 2. Channel List:

Channel	Frequency (MHz)	Channel	Frequency (MHz)	Channel	Frequency (MHz)
00	2402	27	2429	54	2456
01	2403	28	2430	55	2457
02	2404	29	2431	56	2458
03	2405	30	2432	57	2459
04	2406	31	2433	58	2460
05	2407	32	2434	59	2461
06	2408	33	2435	60	2462
07	2409	34	2436	61	2463
08	2410	35	2437	62	2464
09	2411	36	2438	63	2465
10	2412	37	2439	64	2466
11	2413	38	2440	65	2467
12	2414	39	2441	66	2468
13	2415	40	2442	67	2469
14	2416	41	2443	68	2470
15	2417	42	2444	69	2471
16	2418	43	2445	70	2472
17	2419	44	2446	71	2473
18	2420	45	2447	72	2474
19	2421	46	2448	73	2475
20	2422	47	2449	74	2476
21	2423	48	2450	75	2477
22	2424	49	2451	76	2478
23	2425	50	2452	77	2479
24	2426	51	2453	78	2480
25	2427	52	2454		
26	2428	53	2455		



#### 3.2 DESCRIPTION OF TEST MODES

The test system was pre-tested based on the consideration of all possible combinations of EUT operation mode.

Pretest Mode	Description
Mode 1	TX Mode <b>NOTE (1)</b>
Mode 2	TX Mode Channel 39_3Mbps

Following mode(s) was (were) found to be the worst case(s) and selected for the final test.

AC power line conducted emissions test		
Final Test Mode	Description	
Mode 2	TX Mode Channel 39 _3Mbps	

Radiated emissions test - Below 1GHz		
Final Test Mode	Description	
Mode 2	TX Mode Channel 39 _3Mbps	

Radiated emissions test - Above 1GHz				
Final Test Mode Description				
Mode 1 TX Mode <b>NOTE (1)</b>				

Conducted test				
Final Test Mode Description				
Mode 1	TX Mode <b>note</b> (1)			

#### Note:

- (1) The measurements are performed at the high, middle, low available channels.
- (2) The measurements for Hopping Channel Separation, Bandwidth and Maximum Output Power were tested during 1Mbps, 2Mbps and 3Mbps, the worst case are 1Mbps and 3Mbps, only worst case was documented.




#### 3.3PARAMETERS OF TEST SOFTWARE

During testing, channel & power controlling software provided by the customer was used to control the operating channel as well as the output power level. The RF output power selection is for the setting of RF output power expected by the customer and is going to be fixed on the firmware of the final end product power parameters of FHSS

Test Software	N/A			
Frequency (MHz)	2402	2441	2480	
Parameters(1Mbps)	Default	Default	Default	
Parameters(3Mbps)	Default	Default	Default	

#### 3.4BLOCKDIAGRAMSHOWINGTHECONFIGURATIONOFSYSTEMTESTED



### 3.5SUPPORT UNITS

Item	Equipment	Brand	Model No.	Series No.
AE	Notebook	Lenovo	1	1

Item	Cable Type	Shielded Type	Ferrite Core	Length
C1	DC Cable	NO	NO	0.8m





# **3.6TEST ENVIRONMENT CONDITIONS**

Test Item	Temperature	Humidity	Test Voltage
AC Power Line Conducted Emissions	25°C	53%	AC 120V
Radiated Emissions-9K-30MHz	25°C	60%	AC 120V
Radiated Emissions-30 MHz to 1GHz	24°C	68%	AC 120V
Radiated Emissions-Above 1000 MHz	24°C	68%	AC 120V
Number of Hopping Frequency	24.8°C	40.9%	AC 120V
Average Time Of Occupancy	24.8°C	40.9%	AC 120V
Hopping Channel Separation	24.8°C	40.9%	AC 120V
Bandwidth	24.8°C	40.9%	AC 120V
Maximum Output Power	24.8°C	40.9%	AC 120V
Conducted Spurious Emission	24.8°C	40.9%	AC 120V



#### **4AC POWER LINE CONDUCTED EMISSIONS TEST**

#### 4.1LIMIT

Fraguency of Emission (MHz)	Limit (dBμV)			
Frequency of Emission (MHz)	Quasi-peak	Average		
0.15 - 0.50	66 to 56*	56 to 46*		
0.50 - 5.0	56	46		
5.0 - 30.0	60	50		

#### Note:

(1) The tighter limit applies at the band edges.

(2) The limit of " \* " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.

The following table is the setting of the receiver

Receiver Parameters	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 kHz

#### **4.2TEST PROCEDURE**

- a. The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipment powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- c. I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- d. LISN at least 80 cm from nearest part of EUT chassis.


#### **4.3MEASUREMENT INSTRUMENTS LIST**

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Pulse Limiter	MTS-systemtec hnik	MTS-IMP-136	261115-010-0024	12/11/2023
2	<b>EMI Test Receiver</b>	R&S	ESCI	101308	12/12/2023
3	LISN	AFJ	LS16	16011103219	05/26/2023
4	LISN	Schwarzbeck	NSLK 8127	8127-432	12/11/2023
5	Measurement Software	Farad	EZ-EMC (Ver.ATT-03A)	N/A	N/A

Report No.: 22EFSS10067 11211



# 4.4TESTSETUP




# **4.5EUT OPERATING CONDITIONS**

The EUT was configured for testing in a typical function (as a customer would normally use it), EUT was programmed to be in continuously transmitting data or hopping on mode.



# **4.6TEST RESULTS**

Test Mode: TX Mode Channel 39 \_3Mbps




No.	Frequency	Reading	Correct	Result	Limit	Margin	Remark
	(MHz)	(dBuV)	Factor(dB)	(dBuV)	(dBuV)	(dB)	
1	0.1500	21.89	10.72	32.61	65.99	-33.38	QP
2	0.1500	16.89	10.72	27.61	55.99	-28.38	AVG
3	0.2540	22.68	10.62	33.30	61.62	-28.32	QP
4	0.2540	15.21	10.62	25.83	51.62	-25.79	AVG
5	0.7260	22.87	10.73	33.60	56.00	-22.40	QP
6	0.7260	21.63	10.73	32.36	46.00	-13.64	AVG
7	2.4020	20.62	10.79	31.41	56.00	-24.59	QP
8	2.4020	16.98	10.79	27.77	46.00	-18.23	AVG
9	13.9100	20.78	10.75	31.53	60.00	-28.47	QP
10	13.9100	16.14	10.75	26.89	50.00	-23.11	AVG
11	22.0140	25.05	10.69	35.74	60.00	-24.26	QP
12	22.0140	22.14	10.69	32.83	50.00	-17.17	AVG

# Remarks:

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



Test Mode: TX Mode Channel 39 \_3Mbps



No.	Frequency	Reading	Correct	Result	Limit	Margin	Remark
	(MHz)	(dBuV)	Factor(dB)	(dBuV)	(dBuV)	(dB)	
1	0.2540	22.15	10.62	32.77	61.62	-28.85	QP
2	0.2540	13.88	10.62	24.50	51.62	-27.12	AVG
3	0.7220	22.59	10.72	33.31	56.00	-22.69	QP
4	0.7220	22.40	10.72	33.12	46.00	-12.88	AVG
5	1.1380	17.44	10.61	28.05	56.00	-27.95	QP
6	1.1380	13.90	10.61	24.51	46.00	-21.49	AVG
7	2.4020	20.36	10.79	31.15	56.00	-24.85	QP
8	2.4020	16.35	10.79	27.14	46.00	-18.86	AVG
9	11.8780	22.87	10.75	33.62	60.00	-26.38	QP
10	11.8780	20.27	10.75	31.02	50.00	-18.98	AVG
11	21.9900	29.18	10.69	39.87	60.00	-20.13	QP
12	21.9900	26.75	10.69	37.44	50.00	-12.56	AVG

# Remarks:

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



#### **5 RADIATED EMISSION TEST**

#### **5.1LIMIT**

In case the emission fall within the restricted band specified on15.205(a) &RSS-Gen 8.10, then the 15.209(a) &RSS-Gen 8.9 limit in the table below has to be followed.

#### LIMITS OF RADIATED EMISSION MEASUREMENT (9 kHz-1000MHz)

Frequency	Field Strength	Measurement Distance
(MHz)	(microvolts/meter)	(meters)
0.009-0.490	2400/F(kHz)	300
0.490-1.705	24000/F(kHz)	30
1.705-30.0	30	30
30-88	100	3
88-216	150	3
216-960	200	3
Above 960	500	3

#### LIMITS OF RADIATED EMISSION MEASUREMENT (9 kHz-30 MHz)

Frequency	Magnetic field strength (H-Field)	Measurement Distance
(MHz)	(μA/m)	(meters)
0.009-0.490	6.37/F(kHz)	300
0.490-1.705	6.37/F(kHz)	30
1.705-30.0	0.08	30

#### LIMITS OF RADIATED EMISSION MEASUREMENT (30 MHz-1000MHz)

Frequency	Field Strength
(MHz)	(μV/m at 3m)
30-88	100
88-216	150
216-960	200
Above 960	500

# LIMITS OF RADIATED EMISSION MEASUREMENT (Above 1000MHz)

Frequency (MHz)	(dBuV/n	n at 3 m)
	Peak	Average
Above 1000	74	54

#### Note:

- (1) The limit for radiated test was performed according to FCC PART 15C and RSS-247.
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).



#### **5.2TEST PROCEDURE AND SETTING**

- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(below 1GHz)
- b. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 1.5 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(above 1GHz)
- c. The height of the equipment or of the substitution antenna shall be 0.8m or 1.5m; the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- d. For each suspected emission, the EUT was arranged to its worst case and then the antenna was tuned to heights find the maximum reading (used Bore sight function).
- e. The receiver system was set to peak and average detect function and specified bandwidth with maximum hold mode when the test frequency is above 1GHz.
- f. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- g. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform. (below 1GHz)
- h. All readings are Peak Mode value unless otherwise stated AVG in column of Note. If the Peak Mode Measured value compliance with the Peak Limits and lower than AVG Limits, the EUT shall be deemed to meet both Peak & AVG Limits and then only Peak Mode was measured, but AVG Mode didn't perform. (above 1GHz)
- i. The test result is calculated as the following:
  - (1) Result = Reading + Correct Factor
  - (2) Correct Factor = Antenna Factor + Cable Loss Amplifier Gain + Attenuator
  - (3) Margin = Result Limit

Spectrum Parameter	Setting
Attenuation	Auto
Start Frequency	1000 MHz
Stop Frequency	10th carrier harmonic
RBW / VBW	RBW 1MHz VBW 3MHz peak detector for Pk value
(Emission in restricted band)	RMS detector for AV value

Receiver Parameter	Setting
Attenuation	Auto
Start ~ Stop Frequency	9 kHz~90 kHz for PK/AVG detector
Start ~ Stop Frequency	90 kHz~110 kHz for QP detector
Start ~ Stop Frequency	110 kHz~490 kHz for PK/AVG detector
Start ~ Stop Frequency	490 kHz~30 MHz for QP detector
Start ~ Stop Frequency	30MHz~1000MHz for QP detector




# **5.3MEASUREMENT INSTRUMENTS LIST**


Item	Equipment	Manufacturer	Model No.	Serial No.	Calibrated until
1	EMI Test Receiver	R&S	ESCI	101307	12/11/2023
2	Spectrum Analyzer	Agilent	E4407B	US40240708	11/10/2023
3	Loop antenna	SCHWARZBECK K	FMZB1519	1519-062	01/15/2024
4	Broadband antenna	SCHWARZBECK	VULB9168	VULB9168-192	07/04/2023
5	HORN ANTENNA	SCHWARZBECK	BBHA9120D	9120D 1065	04/18/2023
6	Preamplifier Amplifier	HP	8447F	3113A05680	12/19/2023
7	PRE-AMPLIFIER	EMEC	EM01G26G	980136	04/18/2023
8	RF Cable	R&S	Test Cable 4	4	12/11/2023
9	RF Cable	R&S	Test Cable 5	5	12/11/2023
10	RF Cable	R&S	Test Cable 9	9	04/18/2023
11	RF Cable	R&S	Test Cable 10	10	04/18/2023
12	Measurement Software	Farad	EZ-EMC (Ver.ATT-03A)	N/A	N/A

# **5.4TESTSETUP**

# 9 kHz-30 MHz




# 30 MHz to 1 GHz





# **Above 1 GHz**



# **5.5EUT OPERATING CONDITIONS**

The EUT was programmed to be in continuously transmitting mode.

Report No.: 22EFSS10067 11211



# 5.6TEST RESULTS - 9 kHz TO 30MHz

TX Mode Channel 39 _3Mbps

Freq.	Reading	Limit	Margin	State
(MHz)	(dBuV/m)	(dBuV/m)	(dB)	P/F
				Р
				Р

#### Note:

The amplitude of spurious emissions which are attenuated by more than 20dB below the permissible value has no need to be reported.

Distance extrapolation factor =20 log (specific distance/test distance)(dB); Limit line = specific limits(dBuv) + distance extrapolation factor



# 5.7TEST RESULTS- 30 MHz TO 1000MHz

Test Mode: TX Mode Channel 39 \_3Mbps

# Vertical



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		43.0505	31.19	-13.54	17.65	40.00	-22.35	QP	200	244	
2		54.0711	33.89	-12.66	21.23	40.00	-18.77	QP	100	215	
3	*	73.1025	37.41	-14.75	22.66	40.00	-17.34	QP	100	169	
4		101.2885	35.14	-14.55	20.59	43.50	-22.91	QP	200	95	
5		190.4050	27.86	-11.40	16.46	43.50	-27.04	QP	100	45	
6		896.9965	22.58	2.91	25.49	46.00	-20.51	QP	100	321	


\*:Maximum data x:Over limit !:over margin

Reference Only



Test Mode: TX Mode Channel 39 \_3Mbps

# Horizontal



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		73.6170	31.08	-16.45	14.63	40.00	-25.37	QP	100	63	
2	*	110.5687	33.87	-14.20	19.67	43.50	-23.83	QP	200	321	
3	1	191.0738	28.21	-9.45	18.76	43.50	-24.74	QP	100	244	
4	8	199.9856	28.37	-9.03	19.34	43.50	-24.16	QP	100	159	
5	8	281.9946	26.64	-6.22	20.42	46.00	-25.58	QP	200	64	
6		517.2480	23.21	-5.35	17.86	46.00	-28.14	QP	300	76	


<sup>\*:</sup>Maximum data x:Over limit !:over margin Reference Only



# 5.8TEST RESULTS - ABOVE 1000MHz(BAND EDGE)

Test Mode: TX 2402 MHz\_CH00\_1Mbps

# Vertical




No.	Mk	. Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		2390.000	48.48	-12.02	36.46	74.00	-37.54	peak	150	303	
2		2390.000	37.31	-12.02	25.29	54.00	-28.71	AVG	150	303	
3	X	2401.875	95.43	-11.98	83.45	74.00	9.45	peak	150	303	NO LIMIT
4	*	2402.000	94.98	-11.98	83.00	54.00	29.00	AVG	150	303	NO LIMIT

<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2402 MHz\_CH00\_1Mbps

# Horizontal




No.	Mk	. Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		2390.000	49.25	-12.02	37.23	74.00	-36.77	peak	150	360	
2		2390.000	37.22	-12.02	25.20	54.00	-28.80	AVG	150	360	
3	X	2401.875	101.80	-11.98	89.82	74.00	15.82	peak	150	360	NO LIMIT
4	*	2402.000	101.32	-11.98	89.34	54.00	35.34	AVG	150	360	NO LIMIT

<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2480 MHz\_CH78\_1Mbps

# Vertical




No.	Mk	. Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1	Χ	2479.875	93.73	-11.74	81.99	74.00	7.99	peak	150	303	NO LIMIT
2	*	2480.000	93.19	-11.74	81.45	54.00	27.45	AVG	150	303	NO LIMIT
3		2483.500	53.20	-11.72	41.48	74.00	-32.52	peak	150	303	
4		2483.500	39.61	-11.72	27.89	54.00	-26.11	AVG	150	303	

<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only}



Test Mode: TX 2480 MHz\_CH78\_1Mbps

#### Horizontal




<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2402 MHz\_CH00\_3Mbps

# Vertical



No.	Mk	. Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		2390.000	48.75	-12.02	36.73	74.00	-37.27	peak	150	303	
2		2390.000	37.31	-12.02	25.29	54.00	-28.71	AVG	150	303	
3	X	2402.000	94.97	-11.98	82.99	74.00	8.99	peak	150	303	NO LIMIT
4	*	2402.000	90.97	-11.98	78.99	54.00	24.99	AVG	150	303	NO LIMIT

<sup>\*:</sup>Maximum data x:Over limit !:over margin (Reference Only


2377.000 2382.00


2387.00

2392.00

2397.00







No.	Mk.	. Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Over		Antenna Height	Table Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		2390.000	48.96	-12.02	36.94	74.00	-37.06	peak	150	344	
2		2390.000	37.30	-12.02	25.28	54.00	-28.72	AVG	150	344	
3	X	2402.000	102.08	-11.98	90.10	74.00	16.10	peak	150	344	NO LIMIT
4	*	2402.000	98.10	-11.98	86.12	54.00	32.12	AVG	150	344	NO LIMIT

2402.00

2407.00

2412.00

2417.00

2427.00 MHz

<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)

3

2483.500

2483.500

50.45

39.63


-11.72

-11.72

38.73

27.91





74.00

54.00

-35.27

-26.09

peak

AVG

150

150


304

304

\*:Maximum data x:Over limit !:over margin

Reference Only





No.	Mk	c. Freq.	Level	Factor	ment	Limit	Over		Height	Degree	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1	X	2480.000	107.42	-11.74	95.68	74.00	21.68	peak	150	345	NO LIMIT
2	*	2480.000	103.59	-11.74	91.85	54.00	37.85	AVG	150	345	NO LIMIT
3		2483.500	52.86	-11.72	41.14	74.00	-32.86	peak	150	345	
4		2483.500	41.21	-11.72	29.49	54.00	-24.51	AVG	150	345	


<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



# 5.9TEST RESULTS - ABOVE 1000MHz(HARMONIC)

Test Mode: TX 2402 MHz\_CH00\_1Mbps

# **Vertical**



	No.	Mk.	Freq.	Level		ment	Limit	Over		Height	Degree	
_			MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
	1	4	4804.000	53.00	-7.53	45.47	74.00	-28.53	peak	150	63	
	2	* 4	4804.000	43.69	-7.53	36.16	54.00	-17.84	AVG	150	63	


Reference Only

<sup>\*:</sup>Maximum data x:Over limit !:over margin



Test Mode: TX 2402 MHz\_CH00\_1Mbps

# Horizontal




<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2441 MHz\_CH39\_1Mbps

# Vertical



<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2441 MHz\_CH39\_1Mbps

# Horizontal



No.	Mł	k. Freq.	Reading Level		Measure- ment	Limit	Over		Antenna Height		
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		4882.000	52.69	-7.31	45.38	74.00	-28.62	peak	150	239	
2	*	4882.000	43.46	-7.31	36.15	54.00	-17.85	AVG	150	239	

 $\langle \, \mathsf{Reference} \,\, \mathsf{Only} \,\,$ 

<sup>\*:</sup>Maximum data x:Over limit !:over margin



Test Mode: TX 2480 MHz\_CH78\_1Mbps

# Vertical




No.	M	k. Freq.	Reading Level		Measure- ment	Limit	Over		Antenna Height		
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
1		4960.000	52.26	-7.09	45.17	74.00	-28.83	peak	150	259	
2	*	4960.000	43.30	-7.09	36.21	54.00	-17.79	AVG	150	259	

<sup>\*:</sup>Maximum data x:Over limit !:over margin Reference Only



Test Mode: TX 2480 MHz\_CH78\_1Mbps

# Horizontal



<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2402 MHz\_CH00\_3Mbps

## Vertical




	No.	Mk	. Freq.	Level	Factor	ment	Limit	Over		Height		
Ī			MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector	cm	degree	Comment
	1		4804.000	51.09	-7.53	43.56	74.00	-30.44	peak	150	91	
_	2	*	4804.000	41.18	-7.53	33.65	54.00	-20.35	AVG	150	91	

<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2402 MHz\_CH00\_3Mbps

## Horizontal




*:Maximum data	x:Over limit	Lover margin	(Reference Only



Test Mode: TX 2441 MHz\_CH39\_3Mbps

## **Vertical**




*:Maximum data	x:Over limit	!:over margin	(Reference Only



Test Mode: TX 2441 MHz\_CH39\_3Mbps

#### Horizontal




<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2480 MHz\_CH78\_3Mbps

## Vertical




<sup>\*:</sup>Maximum data x:Over limit !:over margin \( \text{Reference Only} \)



Test Mode: TX 2480 MHz\_CH78\_3Mbps

# Horizontal



*:Maximum data	x:Over limit	!:over margin	Reference Only



## **6NUMBER OF HOPPING FREQUENCY**

#### 6.1LIMIT

FCC Part15, Subpart C (15.247)&RSS-247				
Section Test Item				
15.247(a)(1)(iii) RSS-247 5.1 (d)	Number of Hopping Frequency			

#### **6.2TEST PROCEDURE AND SETTING**

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.
- b. Spectrum Setting: RBW=100 kHz, VBW=300 kHz, Sweep time = Auto.

Spectrum Parameters	Setting
Attenuation	Auto
Span Frequency	> Operating Frequency Range
RBW	100kHz
VBW	300kHz
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

#### **6.3MEASUREMENT INSTRUMENTS LIST**

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A


#### **6.4TEST SETUP**




#### **6.5EUT OPERATION CONDITIONS**



Hopping Mode_1Mbps					
Number of Hopping	Measurement result(CH)	Limit(CH)			
Frequency	79	≥15			



	Hopping Mode_3Mbps	
Number of Hopping	Measurement result(CH)	Limit(CH)
Frequency	79	≥15





#### **7AVERAGE TIME OF OCCUPANCY**

#### 7.1LIMIT

FCC Part15, Subpart C (15.247)&RSS-247						
Section	Section Test Item Limit					
15.247(a)(1)(iii) RSS-247 5.1 (d)	Average Time of Occupancy	0.4sec				


#### 7.2TEST PROCEDURE AND SETTING

- a. The transmitter output (antenna port) was connected to the spectrum analyzer
- b. Set RBW of spectrum analyzer to 1MHz and VBW to 1MHz
- c. Use a video trigger with the trigger level set to enable triggering only on full pulses
- d. Sweep Time is more than once pulse time
- e. Set the center frequency on any frequency would be measure and set the frequency span to zero span
- f. Measure the maximum time duration of one single pulse
- g. Set the EUT for DH1, DH3 and DH5 packet transmitting
- h. Measure the maximum time duration of one single pulse
- i. DH1 Packet permit maximum 1600 / 79 / 2 = 10.12 hops per second in each channel (1 time slot TX, 1 time slot RX). So, the dwell time is the time duration of the pulse times  $10.12 \times 31.6 = 320$  within 31.6 seconds
- j. DH3 Packet permit maximum 1600 / 79 / 4 = 5.06 hops per second in each channel (3 time slots TX, 1 time slot RX).So, the dwell time is the time duration of the pulse times 5.06 x 31.6 = 160 within 31.6 seconds
- k. DH5 Packet permit maximum 1600/ 79 / 6 = 3.37 hops per second in each channel (5 time slots TX, 1 time slot RX).So, the dwell time is the time duration of the pulse times 3.37 x 31.6 = 106.6 within 31.6 seconds

## 7.3MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A


#### 7.4TEST SETUP



#### 7.5EUT OPERATION CONDITIONS



TX Mode_1Mbps						
Mode	Channel Frequency	Pulse Time	Dwell Time	Limit		
Wiode	(MHz)	(ms)	(ms)	(ms)		
DH1	2441	0.389	124.5	400		
DH3	2441	1.653	264.5	400		
DH5	2441	2.900	309.3	400		







TX Mode_3Mbps					
Mode	Channel Frequency	Pulse Time	Dwell Time	Limit	
Mode	(MHz)	(ms)	(ms)	(ms)	
DH1	2441	0.397	127.0	400	
DH3	2441	1.649	263.8	400	
DH5	2441	2.902	309.5	400	


# 2441MHzDH1

# 2441MHzDH3

# 2441MHzDH5









#### 8HOPPING CHANNEL SEPARATION MEASUREMENT

#### 8.1LIMIT

Frequency hopping systems operating in the 2400-2483.5 MHz band may have hopping channel carrier frequencies that are separated by 25 kHz or two-thirds of the 20 dB bandwidth of the hopping channel, whichever is greater, provided the systems operate with an output power no greater than 125 mW.

#### **8.2TEST PROCEDURE AND SETTING**

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.
- b. Span = wide enough to capture the peaks of two adjacent channels

Resolution (or IF) Bandwidth (RBW) ≥ 1% of the span

Video (or Average) Bandwidth (VBW) ≥ RBW

Sweep = Auto

Detector function = Peak

Trace = Max Hold

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	> Measurement Bandwidth or Channel Separation
RBW	10 kHz
VBW	30 kHz
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

#### **8.3MEASUREMENT INSTRUMENTS LIST**

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A

#### **8.4TEST SETUP**

EUT	SPECTRUM
	ANALYZER

#### **8.5EUT OPERATION CONDITIONS**



TX Mode_1Mbps				
Channel	Frequency (MHz)	Channel Separation(MHz)	Limit (MHz)	Result
CH00	2402	1.002	>(25KHz or 2/3*20dB Bandwidth)	PASS
CH39	2441	1.002	>(25KHz or 2/3*20dB Bandwidth)	PASS
CH78	2480	1.008	>(25KHz or 2/3*20dB Bandwidth)	PASS







	TX Mode_3Mbps				
Channel	Frequency	Channel	Limit	Result	
on anno	(MHz)	Separation(MHz)	(MHz)	rtoodit	
CH00	2402	1.002	>(25KHz or 2/3*20dB	PASS	
240	2402	1.002	Bandwidth)	17.00	
CH39	2441	1.002	>(25KHz or 2/3*20dB	PASS	
01139	2 <del>74</del> 1	1.002	Bandwidth)	FAGG	
CH78	2490	1 002	>(25KHz or 2/3*20dB	PASS	
CH76	2480	1.002	Bandwidth)	PASS	





#### **9BANDWIDTH TEST**

#### **9.1LIMIT**

· <del></del>				
FCC Part15, Subpart C (15.247)&RSS-247				
Section	Test Item			
15.247(a)(1)				
RSS-Gen 6.7	Bandwidth			
RSS-247 5.1 (a)				

## 9.2TEST PROCEDURE AND SETTING

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.
- b. Spectrum Setting: RBW= 30 kHz, VBW=100 kHz, Sweep Time = Auto.

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	> Measurement Bandwidth
RBW	30kHz
VBW	100kHz
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

#### 9.3MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A

#### 9.4TEST SETUP



#### 9.5EUT OPERATION CONDITIONS



TX Mode_1Mbps				
Channel	Frequency	20dB Bandwidth	99 % Emission Bandwidth	Result
	(MHz)	(MHz)	(MHz)	
CH00	2402	1.039	0.923	PASS
CH39	2441	1.040	0.921	PASS
CH78	2480	1.040	0.923	PASS





TX Mode_3Mbps					
Channel	Frequency	20dB Bandwidth	99 % Emission Bandwidth	Result	
	(MHz)	(MHz)	(MHz)		
CH00	2402	1.267	1.174	PASS	
CH39	2441	1.267	1.174	PASS	
CH78	2480	1.268	1.174	PASS	





#### **10MAXIMUM OUTPUT POWER**

#### **10.1LIMIT**

FCC Part15 , Subpart C (15.247)&RSS-247				
Section Test Item Limit				
15.247(a)(1) RSS-247 5.1 (b)  Maximum Output Power 0.125Watt or 21dBm				

#### Note:

Frequency hopping systems shall have hopping channel carrier frequencies separated by a minimum of 25 kHz or the 20 dB bandwidth of the hopping channel, whichever is greater. Alternatively, frequency hopping systems operating in the 2400-2483.5 MHz band may have hopping channel carrier frequencies that are separated by 25 kHz or two-thirds of the 20 dB band width of the hopping channel, whichever is greater, provided the systems operate with an output power no greater than 125 mW.

#### **10.2TEST PROCEDURE AND SETTING**

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.
- b. Spectrum Setting: RBW= 1MHz/3MHz, VBW= 1MHz/3MHz, Sweep time = Auto.

#### 10.3MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A


#### **10.4TEST SETUP**

EUT	SPECTRUM
	ANALYZER

# **10.5EUT OPERATION CONDITIONS**




TX Mode_1Mbps				
Channel	Frequency	Output Power	Output Power	Result
	(MHz)	(dBm)	(W)	Result
CH00	2402	7.398	0.00549	PASS
CH39	2441	7.964	0.00626	PASS
CH78	2480	7.565	0.00571	PASS
Limit	21dBm /0.125W			







	TX Mode_2Mbps				
Channel	Frequency	Output Power	Output Power	Result	
Chamer	(MHz)	(dBm)	(W)	Result	
CH00	2402	8.287	0.00674	PASS	
CH39	2441	8.471	0.00703	PASS	
CH78	2480	8.144	0.00652	PASS	
Limit	21dBm /0.125W				







TX Mode_3Mbps					
Channel	Frequency	Output Power	Output Power	Result	
Chamilei	(MHz)	(dBm)	(W)	Result	
CH00	2402	8.928	0.00781	PASS	
CH39	2441	9.047	0.00803	PASS	
CH78	2480	8.692	0.00740	PASS	
Limit	21dBm /0.125W				





#### 11CONDUCTED SPURIOUS EMISSION

#### **11.1LIMIT**

#### For FCC

In any 100 kHz bandwidth outside the frequency band in which the spread spectrum or digitally modulated intentional radiator is operating, the radio frequency power that is produced by the intentional radiator shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of the desired power, based on either an RF conducted or a radiated measurement, provided the transmitter demonstrates compliance with the peak Output Power limits. If the transmitter complies with the Output Power limits based on the use of RMS averaging over a time interval, as permitted under paragraph (b)(3) of this section, the attenuation required under this paragraph shall be 30 dB instead of 20 dB. Attenuation below the general limits specified in Section 15.209(a) is not required.

#### For ISED

In any 100 kHz bandwidth outside the frequency band in which the spread spectrum or digitally modulated device is operating, the RF power that is produced shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of the desired power, based on either an RF conducted or a radiated measurement, provided that the transmitter demonstrates compliance with the peak Output Power limits. If the transmitter complies with the Output Power limits based on the use of root-mean-square averaging over a time interval, as permitted under section 5.4(d), the attenuation required shall be 30 dB instead of 20 dB. Attenuation below the general field strength limits specified in RSS-Gen is not required.


#### 11.2TEST PROCEDURE AND SETTING

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.
- b Spectrum Setting: RBW= 100 kHz, VBW=300 kHz, Sweep time = Auto.

#### 11.3MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A


#### 11.4TEST SETUP




#### 11.5EUT OPERATION CONDITIONS





# TX Mode\_1Mbps






**Bandedge- Hopping on (Lower)** 








10th Harmonic of the fundamental frequency




















# 10th Harmonic of the fundamental frequency CH00 CH39









## 12FREQUENCY STABILITY MEASUREMENT

#### **12.1LIMIT**

	RSS-Gen					
Section Test Item		Limit	Frequency Range (MHz)			
RSS-Gen 6.11	Frequency Stability	Specified in the user's manual	2402-2480			

#### **12.2TEST PROCEDURE**

a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below.


b. Spectrum Setting:

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	Entire absence of modulationemissionsbandwidth
RBW	10 kHz
VBW	10kHz
Sweep Time	Auto

## 12.3MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum analyzer	KEYSIGHT	N9010A	MY55150427	2023/05/26
2	Attenuator	Mini-Circuits	BW-S10W2	101109	N/A
3	RF Cable	Mi-cable	C10-01-01-1	100309	N/A
4	Temperature conditioning	Guan Jian.HTH1000	-20-130°C	GJ1000-10D001	N/A
5	DC Power Supply	G.KE	IPR-10010D	010931954	N/A

# 12.4 TEST SETUP



## **12.5EUT OPERATION CONDITIONS**

The EUT was programmed to be in continuously transmitting mode.



	Temperature vs. Frequency Stability		
Voltage	Temperature	Measurement Frequency (MHz)	
	(°C)	2402	
120V	0	2401.9998	
1200	25	2401.9996	
	40	2401.9993	
89V	25	2401.9997	
Max. Deviation (MHz)		-0.007	
Max. Devia	ation (ppm)	-0.29	

Note:89V is the end point voltage, and products below 3.5V will cease working.

## **END OF TEST REPORT**