RADIATED EMISSIONS
Location #1 FCC Part 15 Class B

Client: Fujitsu Ten corp of America
Date : 25-Feb-99
File # 96064-1
Engr.: Yancey Staples
Rep. : Mark Kubota
System: Vehicle Security

Freq (MHz)	Meas'd (dBuV)	Amp Factors (dB)	Cable Factors (dB)	Antenna Factors (dB)	Total Factors (dBuV/m)	Total (dBuV/m)	3 FCC Limit (dBuV/m)	Delta (dB)	Azimuth (degree)	Height (m)	Hor/ Vert	HP/ R&S	Meas Type Ave Peak	Comments
#######	46.0	27.5	3.8	28.9	5.2	51.2	54.9	-3.7	56	1.00	Vert	HP/	Ave	Harmonics
#######	40.9	27.7	4.1	29.6	6.0	46.9	54.9	-8.0	66	1.00	Vert	HP/	Ave	Harmonics
#######	39.2	26.5	3.4	27.4	4.3	43.5	54.9	-11.4	26	1.00	Vert	HP/	Ave	Harmonics
#######	38.6	23.8	3.0	24.1	3.3	41.9	54.9	-13.0	86	1.00	Vert	HP/	Ave	Harmonics
#######	33.8	26.9	3.6	28.7	5.4	39.2	54.9	-15.7	337	1.00	Vert	HP/	Ave	Harmonics
911.654	27.8	26.4	9.8	23.0	6.4	34.2	54.9	-20.7	129	1.50	Hor/	R&S	Ave	Harmonics
607.776	29.1	26.7	7.6	20.7	1.6	30.7	54.9	-24.2	176	1.50	Hor/	R&S	Ave	Harmonics
#######	27.3	26.4	3.3	25.3	2.2	29.5	54.9	-25.4	323	1.00	Vert	HP/	Ave	Harmonics
303.880	69.8	25.2	5.4	16.7	-3.1	66.7	74.9	-8.2	80	1.85	Vert	R&S	Ave	Fundamental
303.880	65.8	25.2	5.4	16.7	-3.1	62.7	74.9	-12.2	155	1.75	Hor/	R&S	Ave	Fundamental