



849 NW STATE ROAD 45
NEWBERRY, FL 32669 USA
PH: 888.472.2424 OR 352.472.5500
FAX: 352.472.2030
EMAIL: INFO@TIMCOENGR.COM
[HTTP://WWW.TIMCOENGR.COM](http://WWW.TIMCOENGR.COM)

FCC PART 15B SUBPART B RECEIVER TEST REPORT

| | |
|----------------------|--|
| Applicant | SCIENTIFIC TOYS, LTD. |
| Address | 13/F., CHAI WAN INDUSTRIAL CENTRE 20 LEE CHUNG STREET CHAI WAN, HONG KONG |
| FCC ID | BY33822-49XR |
| Product Description | 49.86 MHz Wireless R/C Toy Receiver |
| Date Sample Received | 12/4/2006 |
| Date Tested | 12/6/2006 |
| Tested By | Richard Block |
| Approved By | Mario de Aranzeta |
| Timco Report No. | 3297UT6TestReport.PDF |
| Test Results | <input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail |

**THE ATTACHED REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL
WITHOUT THE WRITTEN APPROVAL OF TIMCO ENGINEERING, INC.**



Certificate # 0955-01

TABLE OF CONTENTS

| | |
|-----------------------------------|---|
| STATEMENT OF COMPLIANCE..... | 3 |
| REPORT SUMMARY..... | 4 |
| TEST ENVIRONMENT AND SYSTEM | 4 |
| DUT SPECIFICATION..... | 5 |
| EMC EQUIPMENT LIST | 6 |
| TEST PROCEDURE | 7 |
| RADIATION INTERFERENCE | 8 |

STATEMENT OF COMPLIANCE

This equipment has been tested in accordance with the standards identified in the referenced test report. To the best of my knowledge and belief, these tests were performed using the measurement procedures described in this report and demonstrate that the equipment complies with the appropriate standards.

I attest that the necessary measurements were made by me or under my supervision, at Timco Engineering, Inc. located at 849 N.W. State Road 45, Newberry, Florida 32669 USA.



Certificate #0955-01

Authorized by: Mario de Aranzeta
Signature: On file
Function: Engineer
Date: December 7, 2006
Tested by: Richard Block
Signature: on file
Date: December 6, 2006

REPORT SUMMARY

| | |
|------------------------|---|
| Disclaimer | The test results relate only to the item tested. |
| Purpose of Test Report | To demonstrate DUT compliance with FCC Pt 15.109 requirements for a R/C toy receiver. |
| Applicable Rule(s) | FCC Pt 15.109, ANSI C63.4 2003 |
| Related Report | No related report |

TEST ENVIRONMENT AND SYSTEM

| | |
|--|--|
| Test Facility | Timco Engineering Inc. 849 NW State Road 45 Newberry, FL 32669 USA. Timco accreditations are on file with regulatory agencies. |
| Test Condition: | The DUT was tested in a laboratory environment with normal temperature and humidity. The temperature was 26°C with a relative humidity of 50%. |
| Test Exercise (e.g software description, test signal, etc.): | The DUT was placed in continuous receiver mode of operation. |
| Supporting Peripheral Equipment | Not applicable. The device is a stand-alone radio. |
| Deviation to the standard(s) | No deviation from the standard(s) |
| Modification to the DUT: | No modification was made to the DUT. |

DUT SPECIFICATION

| | | | |
|---------------------|--|--|--|
| Manufacturer | Scientific Toys, Ltd. | | |
| Description | R/C Toy Receiver | | |
| FCC ID | BY33822-49XR | | |
| Model Name | N/A | | |
| Operating Frequency | 49.86 MHz | | |
| DUT Power Source | <input type="checkbox"/> 110-120Vac/50- 60Hz | | |
| | <input type="checkbox"/> DC Power | | |
| | <input checked="" type="checkbox"/> Battery Operated Exclusively | | |
| Test Item | <input type="checkbox"/> Prototype | <input checked="" type="checkbox"/> Pre-Production | <input type="checkbox"/> Production |
| Type of Equipment | <input type="checkbox"/> Fixed | <input type="checkbox"/> Mobile | <input checked="" type="checkbox"/> Portable |
| Antenna | Integrated | | |

EMC EQUIPMENT LIST

| Device | Manufacturer | Model | Serial Number | Cal/Char Date | Due Date |
|---|-----------------|----------|--------------------------|-------------------|----------|
| 3/10-Meter OATS | TEI | N/A | N/A | Listed 3/27/04 | 3/26/07 |
| 3-Meter OATS | TEI | N/A | N/A | Listed 1/11/06 | 1/10/09 |
| Antenna: Biconnical | Eaton | 94455-1 | 1057 | CAL 12/12/05 | 12/12/07 |
| Antenna: Biconnical | Eaton | 94455-1 | 1096 | CAL 10/11/06 | 10/11/08 |
| Antenna: Biconnical | Electro-Metrics | BIA-25 | 1171 | CAL 4/29/05 | 4/29/07 |
| Analyzer Blue Tower Quasi-Peak Adapter | HP | 85650A | 2811A01279 | CAL 4/13/05 | 4/13/07 |
| Analyzer Blue Tower RF Preselector | HP | 85685A | 2926A00983 | CAL 9/5/05 | 9/5/07 |
| Analyzer Blue Tower Spectrum Analyzer | HP | 8568B | 2928A04729 2848A18049 | CAL 4/13/05 | 4/13/07 |
| LISN | Electro-Metrics | ANS-25/2 | 2604 | CAL 10/5/06 | 10/5/08 |
| LISN | Electro-Metrics | EM-7820 | 2682 | CAL 4/28/05 | 4/28/07 |
| Antenna: Log-Periodic | Eaton | 96005 | 1243 | CAL 12/14/05 | 12/14/07 |

TEST PROCEDURE

Radiation Interference: The test procedure used was ANSI standard C63.4-2003 using an Agilent spectrum analyzer with a preselector. The bandwidth of the spectrum analyzer was 100 kHz with an appropriate sweep speed. The analyzer was calibrated in dB above a microvolt at the output of the antenna. The resolution bandwidth was 100 kHz and the video bandwidth was 300 kHz.

Formula Of Conversion Factors: The field strength at 3m was established by adding the meter reading of the spectrum analyzer (which is set to read in units of dBuV) to the antenna correction factor supplied by the antenna manufacturer. The antenna correction factors are stated in terms of dB. The gain of the preselector was accounted for in the spectrum analyzer meter reading.

Example:

Freq (MHz) METER READING + ACF +CL= FS

33 20 dBuV + 10.36 dB/m+1.2 = 31.56 dBuV/m @ 3m

ANSI Standard C63.4-2003 10.1.7 Measurement Procedures: The DUT was placed on a table 80 cm high and with dimensions of 1m by 1.5m. The DUT was placed in the center of the table. The table used for radiated measurements is capable of continuous rotation. The spectrum was scanned from 30 MHz to 10th harmonic of the fundamental.

Peak readings were taken in three (3) orthogonal planes. The highest readings are reported.

When an emission was found, the table was rotated to produce the maximum signal strength. At this point, the antenna was raised and lowered from 1m to 4m. The antenna was placed in both the horizontal and vertical planes.

ANSI Standard C63.4-2003 Superregenerative Receiver: A signal generator was set to the unit under test operating frequency. An un-modulated continuous wave (CW) signal was radiated at the super-regenerative receiver operating frequency to cohere the characteristic broadband emissions from the receiver.

RADIATION INTERFERENCE

Rules Part No.: 15.109

Requirements:

| Fundamental Frequency (MHz) | Field Strength of Fundamental (dB μ V) |
|-----------------------------|--|
| 30 – 88 | 40.0 |
| 88 – 216 | 43.5 |
| 216 – 960 | 46.0 |
| Above 960 | 54.0 |

Test Data:

| Tuned Frequency MHz | Emission Frequency MHz | Meter Reading dB μ V | Ant. Polarity V/H | Coax Loss dB | Correction Factor dB/m | Field Strength dB μ V/m | Margin dB |
|---------------------|------------------------|--------------------------|-------------------|--------------|------------------------|-----------------------------|-----------|
| 49.9 | 45.23 | 15.3 | H | 0.48 | 11.20 | 26.98 | 13.02 |
| 49.9 | 45.77 | 19.3 | V | 0.48 | 10.25 | 30.03 | 9.97 |
| 49.9 | 50.25 | 11.6 | V | 0.50 | 11.14 | 23.24 | 16.76 |
| 49.9 | 53.95 | 10.1 | V | 0.51 | 11.65 | 22.26 | 17.74 |
| 49.9 | 73.43 | 11.8 | H | 0.58 | 7.47 | 19.85 | 20.15 |
| 49.9 | 73.82 | 15.2 | V | 0.58 | 6.97 | 22.75 | 17.25 |
| 49.9 | 84.76 | 17.9 | V | 0.61 | 7.75 | 26.26 | 13.74 |
| 49.9 | 87.39 | 13.2 | H | 0.62 | 7.68 | 21.50 | 18.50 |
| 49.9 | 87.77 | 16.9 | V | 0.62 | 8.74 | 26.26 | 13.74 |
| 49.9 | 131.40 | 14.7 | V | 0.68 | 13.29 | 28.67 | 14.83 |
| 49.9 | 131.70 | 16.0 | H | 0.68 | 13.10 | 29.78 | 13.72 |
| 49.9 | 138.30 | 18.7 | V | 0.69 | 12.87 | 32.26 | 11.24 |
| 49.9 | 138.67 | 19.2 | H | 0.69 | 13.10 | 32.99 | 10.51 |