Test Method:	FCC Part 15 Subpart C Radiated Emissions, Fundamental Emissions		
Customer:	Fisher Price, Inc.	**Job No.**	R-8535-1
Test Sample:	RF Remote Control	**Paragraph:**	15.227
Model No.:	77149T	**FCC ID:**	CCT77149T
Operating Mode:	Continuously Transmitting a 27.145 MHz Signal		
Technician:	Peter Lananna	**Date:**	May 17, 2000

Notes: Test Distance: 3 Meters
Detector: Peak, Unless otherwise specified

Test Freq.	Antenna Pol./Height	EUT Orientation	Meter Reading	Correction Factor	Corrected Reading	Converted Reading	Peak Limit
MHz	(V/H)/Meters	X / Y / Z	dBuV	dB	dBuV/m	uV/m	uV/m
27.145	H/1.0	X	73.2	8.8	82.0	12589.3	100000
27.145	H/1.0	Y	65.5	8.8	74.3	5188.0	100000
27.145	H/1.0	Z	61.3	8.8	70.1	3198.9	100000
27.145	V/1.0	X	71.0	8.8	79.8	9772.4	100000
27.145	V/1.0	Y	60.5	8.8	69.3	2917.4	100000
27.145	V/1.0	Z	56.4	8.8	65.2	1819.7	100000

Retlif Testing Laboratories

Retlif Job Number R-8535-1

Test Method:	FCC Part 15 Subpart C Radiated Emissions, Fundamental Emissions		
Customer:	Fisher Price, Inc.	**Job No.**	R-8535-1
Test Sample:	RF Remote Control	**Paragraph:**	15.227
Model No.:	77149T	**FCC ID:**	CCT77149T
Operating Mode:	Continuously Transmitting a 27.145 MHz Signal		
Technician:	Peter Lananna	**Date:**	May 17, 2000

Notes: Test Distance: 3 Meters — Duty Cycle: 71.85 %
Detector: Peak, unless otherwise specified — Duty Cycle Correction: - 2.9 dB

Test Freq.	Antenna Pol./Height	EUT Orientation	Peak Reading	Correction Factor	Corrected Reading	Converted Reading	Avg. Limit
MHz	(V/H)-Meters	X / Y / Z	dBuV	dB	dBuV/m	uV/m	uV/m
27.145	H/1.0	X	82.0	-2.9	79.1	9015.7	10000
27.145	H/1.0	Y	74.3	-2.9	71.4	3715.4	10000
27.145	H/1.0	Z	70.1	-2.9	67.2	2290.9	10000
27.145	V/1.0	X	79.8	-2.9	76.9	6998.4	10000
27.145	V/1.0	Y	69.3	-2.9	66.4	2089.3	10000
27.145	V/1.0	Z	65.2	-2.9	62.3	1303.2	10000

Retlif Testing Laboratories

Retlif Job Number R-8535-1