







# **TEST REPORT**

Test report no.: 1-7682/14-01-12-A



# **Testing laboratory**

#### **CETECOM ICT Services GmbH**

Untertuerkheimer Strasse 6 – 10 66117 Saarbruecken / Germany Phone: + 49 681 5 98 - 0 Fax: + 49 681 5 98 - 9075 Internet: <a href="http://www.cetecom.com">http://www.cetecom.com</a> e-mail: ict@cetecom.com

# **Accredited Testing Laboratory:**

The testing laboratory (area of testing) is accredited according to DIN EN ISO/IEC 17025 (2005) by the Deutsche Akkreditierungsstelle GmbH (DAkkS)

The accreditation is valid for the scope of testing procedures as stated in the accreditation certificate with

the registration number: D-PL-12076-01-01

Area of Testing:

Radio Communications & EMC (RCE)

# **Applicant**

# Echostar Technologies

90 Inverness Circle East Englewood CO 80112 / USA

Phone: -/-Fax: -/-

Contact: Ian Schroeder

Regulatory Compliance Engineer e-mail: <a href="mailto:lan.schroeder@echostar.com">lan.schroeder@echostar.com</a>

Phone: +1 303 706-5234

# **Manufacturer**

# **Echostar Technologies**

90 Inverness Circle East Englewood CO 80112 / USA

# Test standard/s

47 CFR Part 15 Title 47 of the Code of Federal Regulations; Chapter I; Part 15 - Radio frequency

devices

For further applied test standards please refer to section 3 of this test report.

**Test Item** 

Kind of test item: TV streaming media device

Model name: M1

FCC ID: DKN-L37 IC: 1707A-L37

Frequency: 5150 – 5350 MHz; 5470 – 5725 MHz

Technology tested: WLAN

Antenna: Integrated antenna

Power supply: 5.3 V DC by Power Supply

Temperature range: -20°C to +55°C



This test report is electronically signed and valid without handwriting signature. For verification of the electronic signatures, the public keys can be requested at the testing laboratory.

Test report authorised:	Test performed:
	p.o.
Marco Bertolino Testing Manager	Rene Oelmann Testing Manager

2014-05-27 Page 1 of 17



# Table of contents

1	Table	of contents	2
2	Genera	al information	3
	2.1	Notes and disclaimerApplication details	3
3	Test st	andard/s	3
4		nvironment	
5	Test it	em	
•		Additional information	
6		boratories sub-contracted	
7		ary of measurement results	
8	KF me	asurements	(
	8.1	Description of test setup	6
	8.		
	8.	1.2 Parameters of DFS test signals	7
	8.2	DFS test results	
	8.2		
	8.2	2.2 Non-Occupancy Period	12
9	Test e	quipment and ancillaries used for tests	15
10	Ol	oservations	15
Anr	nex A	Document history	16
Anr	nex B	Further information	
۸n-	nex C	Accreditation Certificate	
AIII	ICX C	ACCI ECITATION CERTIFICATE	1 /



# 2 General information

# 2.1 Notes and disclaimer

The test results of this test report relate exclusively to the test item specified in this test report. CETECOM ICT Services GmbH does not assume responsibility for any conclusions and generalizations drawn from the test results with regard to other specimens or samples of the type of the equipment represented by the test item.

The test report may only be reproduced or published in full. Reproduction or publication of extracts from the report requires the prior written approval of CETECOM ICT Services GmbH.

The testing service provided by CETECOM ICT Services GmbH has been rendered under the current "General Terms and Conditions for CETECOM ICT Services GmbH".

CETECOM ICT Services GmbH will not be liable for any loss or damage resulting from false, inaccurate, inappropriate or incomplete product information provided by the customer.

Under no circumstances does the CETECOM ICT Services GmbH test report include any endorsement or warranty regarding the functionality, quality or performance of any other product or service provided.

Under no circumstances does the CETECOM ICT Services GmbH test report include or imply any product or service warranties from CETECOM ICT Services GmbH, including, without limitation, any implied warranties of merchantability, fitness for purpose, or non-infringement, all of which are expressly disclaimed by CETECOM ICT Services GmbH.

All rights and remedies regarding vendor's products and services for which CETECOM ICT Services GmbH has prepared this test report shall be provided by the party offering such products or services and not by CETECOM ICT Services GmbH.

In no case this test report can be considered as a Letter of Approval.

This test report is electronically signed and valid without handwritten signature. For verification of the electronic signatures, the public keys can be requested at the testing laboratory.

# 2.2 Application details

Date of receipt of order: 2014-03-24
Date of receipt of test item: 2014-05-12
Start of test: 2014-05-19
End of test: 2014-05-19

Person(s) present during the test: -/-

# 3 Test standard/s

Test standard	Date	Test standard description
47 CFR Part 15	-/-	Title 47 of the Code of Federal Regulations; Chapter I; Part 15 - Radio frequency devices

2014-05-27 Page 3 of 17



# **Test environment**

+22 °C during room temperature tests  $T_{nom}$ 

Temperature: +55 °C during high temperature tests  $\mathsf{T}_{\mathsf{max}}$ 

 $\mathsf{T}_{\mathsf{min}}$ -20 °C during low temperature tests

Relative humidity content: 48 %

Barometric pressure: not relevant for this kind of testing

Power supply:  $V_{nom}$ DC by Power Supply 5.3 V

#### 5 **Test item**

Kind of toot itom	_	TV streeming modic device
Kind of test item	•	TV streaming media device
Type identification	:	M1
S/N serial number	:	U40140400257
HW hardware status	:	No information available
SW software status	:	No information available
Frequency band [MHz]	:	5150 – 5350 MHz; 5470 – 5725 MHz
Type of radio transmission	:	OFDM
Use of frequency spectrum	:	OFDM
Type of modulation	:	BPSK, QPSK, 16-QAM, 64-QAM
Number of channels	:	9
Antenna	:	Integrated antenna
Power supply	:	5.3 V DC by Power Supply
Temperature range	:	-20°C to +55 °C

#### 5.1 **Additional information**

Test setup- and EUT-photos are included in test reports: 1-7682\_14-01-01\_AnnexA

1-7682\_14-01-01\_AnnexB

1-7682\_14-01-01\_AnnexH

#### 6 **Test laboratories sub-contracted**

None

2014-05-27 Page 4 of 17



# 7 Summary of measurement results No deviations from the technical specifications were ascertained There were deviations from the technical specifications ascertained

TC Identifier	Description	Verdict	Date	Remark
DFS-Testing	CFR Part 15	Pass	2014-05-27	DFS client tests only

Test Report Clause	Test Case	Temperature / Voltage	Pass	Fail	NA	NP	Remark
§15.407 (h)(2) (iii)	Channel move time and channel closing transmission time	nominal / nominal	$\boxtimes$				complies
§15.407 (h)(2) (iv)	Non-Occupancy Period	nominal / nominal	$\boxtimes$				complies

Note: NA = Not Applicable; NP = Not Performed

2014-05-27 Page 5 of 17



# 8 RF measurements


# 8.1 Description of test setup

# 8.1.1 Conducted measurements

# <u>Setup</u>

Figure 1 shows a setup whereby the UUT is a RLAN device operating in slave mode, without Radar Interference Detection function. This setup also contains a RLAN device operating in master mode. The radar test signals are injected into the master device. The UUT (slave device) is associated with the master device.

Figure 1 shows an example



2014-05-27 Page 6 of 17



# 8.1.2 Parameters of DFS test signals

1. Interference Threshold values, Master or Client incorporating In-Service Monitoring

Maximum Transmit Power	Value (see note)
≥ 200 mW	-64 dBm
< 200 mW	-62 dBm

Note 1: This is the level at the input of the receiver assuming a 0 dBi receive antenna Note 2: Throughout these test procedures an additional 1 dB has been added to the amplitude of the test transmission waveforms to account for variations in measurement equipment. This will ensure that the test signal is at or above the detection threshold level to trigger a DFS response.

# 2. DFS Response requirement values

Parameter	Value
Non-occupancy period	minimum 30 minutes
Channel Availability Check Time	60 seconds
Channel Move Time	10 seconds See Note 1.
Channel Closing Transmission Time	200 milliseconds + an aggregate of 60 milliseconds over remaining 10 second period.  See Notes 1 and 2.
U-NII Detection Bandwidth	Minimum 80% of the 99% transmission power bandwidth See Note 3.

Note 1: The instant that the Channel Move Time and the Channel Closing Transmission Time begins is as follows:

- For the Short pulse radar Test Signals this instant is the end of the Burst.
- For the Frequency Hopping radar Test Signal, this instant is the end of the last radar Burst generated.
- For the Long Pulse radar Test Signal this instant is the end of the 12 second period defining the radar transmission.

Note 2: The Channel Closing Transmission Time is comprised of 200 milliseconds starting at the beginning of the Channel Move Time plus any additional intermittent control signals required to facilitate Channel changes (an aggregate of 60 milliseconds) during the remainder of the 10 second period. The aggregate duration of control signals will not count quiet periods in between transmissions.

Note 3: During the U-NII Detection Bandwidth detection test, radar type 1 is used and for each frequency step the minimum percentage of detection is 90%. Measurements are performed with no data traffic.

2014-05-27 Page 7 of 17



# 8.2 DFS test results

# 8.2.1 Channel move time / channel closing transmission time

# **Description:**


Channel Move Time. After a radar's presence is detected, all transmissions shall cease on the operating channel within 10 seconds. Transmissions during this period shall consist of normal traffic for a maximum of 200 ms after detection of the radar signal. In addition, intermittent management and control signals can be sent during the remaining time to facilitate vacating the operating channel.

# **Test Procedure:**

Perform the test with one of the type 1 to type 4 short pulse radar waveforms.

# **Result: Channel 60**

# Plot 1: Channel Move Time




Date: 19.MAY.2014 08:35:15

2014-05-27 Page 8 of 17



# Plot 2: Channel Closing Transmission Time



Date: 19.MAY.2014 08:24:29

The arrow shows the time of the radar pulse. On the plot you can see that no transmissions occur from the AP after 10s after sending the radar burst. The time difference between the recognition of the radar burst by the AP and its last transmission is called as Channel Move Time (Limit: 10 s). The accumulated transmission time of the AP and for the slave device after detection of a radar signal is called channel closing transmission time (Limit: in total 200 ms + 60 ms).


The accumulated channel closing transmission time after 200ms of the slave device is less than 60 ms.

2014-05-27 Page 9 of 17




# Result:

Plot 1: Channel Move Time, Channel 104



Date: 19.MAY.2014 08:32:25

Plot 2: Channel Closing Transmission Time, Channel 100



Date: 19.MAY.2014 08:25:50

2014-05-27 Page 10 of 17



The arrow shows the time of the radar pulse. On the plot you can see that no transmissions occur from the AP after 10s after sending the radar burst. The time difference between the recognition of the radar burst by the AP and its last transmission is called as Channel Move Time (Limit: 10 s). The accumulated transmission time of the AP and for the slave device after detection of a radar signal is called channel closing transmission time (Limit: in total 200 ms + 60 ms).

The accumulated channel closing transmission time after 200ms of the slave device is less than 60 ms.

Final verdict: Passed

2014-05-27 Page 11 of 17



# 8.2.2 Non-Occupancy Period

# **Description:**

Non-occupancy Period. A channel that has been flagged as containing a radar system, either by a channel availability check or in-service monitoring, is subject to a non-occupancy period of at least 30 minutes. The non occupancy period starts at the time when the radar system is detected.

# Test Procedure:

Client device is not permitted to transmit beacons on DFS frequencies.

# 1) Non-associated test:

The master has been off, monitor the analyzer on the test mode frequency that have been selected for testing, power up the client for 30 minutes to make sure no beacons have been transmitted.

# 2) Associated test:

Associate the master and client and stream the movie as specified for non- occupancy test. Transmit Radar type 1; monitor the test frequency to make sure no beacons have been transmitted for 30 minutes.


Mode	Results
Non-Associated	No Beacons transmit
Associated	No transmissions

Please refer to the following plots.

2014-05-27 Page 12 of 17



# Plot 1: Non-associated




Date: 19.MAY.2014 08:48:25

The plot shows no transmissions over a 30 minutes period over the whole frequency band  $5.15~\mathrm{GHz} - 5.85~\mathrm{GHz}$ .

2014-05-27 Page 13 of 17



# Plot 2: Associated



Date: 19.MAY.2014 11:24:39

In the plot above you can see, that the client does not transmit any emission within 30 minutes after having received the "stop transmit" order from the Access Point (DFS-Master).

Final verdict: Passed

2014-05-27 Page 14 of 17



# 9 Test equipment and ancillaries used for tests

Typically, the calibrations of the test apparatus are commissioned to and performed by an accredited calibration laboratory. The calibration intervals are determined in accordance with the DIN EN ISO/IEC 17025. In addition to the external calibrations, the laboratory executes comparison measurements with other calibrated test systems or effective verifications. Weekly chamber inspections and range calibrations are performed. Where possible, rf-generating and signalling equipment as well as measuring receivers and analyzers are connected to an external high-precision 10 MHz reference (GPS-based or rubidium frequency standard).

In order to simplify the identification of the equipment used at some special tests, some items of test equipment and ancillaries can be provided with an identifier or number in the equipment list below (Lab/Item).

No.	Lab / Item	Equipment	Туре	Manufact.	Serial No.	INV. No Cetecom	Kind of Calibration	Last Calibration	Next Calibration
1	n. a.	Spectrum Analyzer 9kHz - 30 GHz	FSP30	R&S	100623	300003464	Ve	15.01.2013	15.01.2015
2	n. a.	Vektor Signal Generator	SMU200A	R&S	101633	300003496	k	07.04.2014	07.04.2017
3	n. a.	DFS-test site	div. Splitter, Cables, Attenuators	Mini- Circuits	na	300004557	ev		
4	n. a.	Access Point	AP-800 US	Orinoco	12US4654000		ev		

# Agenda: Kind of Calibration

k	calibration / calibrated	EK	limited calibration
ne	not required (k, ev, izw, zw not required)	ZW	cyclical maintenance (external cyclical maintenance)
ev	periodic self verification	izw	internal cyclical maintenance
Ve	long-term stability recognized	g	blocked for accredited testing
vlkl!	Attention: extended calibration interval		
NK!	Attention: not calibrated	*)	next calibration ordered / currently in progress

# 10 Observations

No observations exceeding those reported with the single test cases have been made.

2014-05-27 Page 15 of 17



# Annex A Document history

Version	Applied changes	Date of release
	Initial release	2014-05-20
-A	Model name changed	2014-05-27

# Annex B Further information

# Glossary

AVG - Average

DUT - Device under test

EMC - Electromagnetic Compatibility

EN - European Standard
EUT - Equipment under test

ETSI - European Telecommunications Standard Institute

FCC - Federal Communication Commission

FCC ID - Company Identifier at FCC

HW - Hardware

IC - Industry Canada
Inv. No. - Inventory number
N/A - Not applicable
PP - Positive peak
QP - Quasi peak
S/N - Serial number
SW - Software

2014-05-27 Page 16 of 17



#### Annex C **Accreditation Certificate**

Front side of certificate

Back side of certificate

((DAkkS

Deutsche Akkreditierungsstelle GmbH

Bellehene gemäß § 8 Absatz 1 AkkStelleG i.V.m. § 1 Absatz 1 AkkStelleGBV Unterzeichnerin der Multilateralen Abkommen von EA, ILAC und IAF zur gegenseitigen Anerkennung

Akkreditierung



Die Deutsche Akkreditierungsstelle GmbH bestätigt hiermit, dass das Prüflaboratorium

Untertürkheimer Straße 6-10, 66117 Saarbrücken

die Kompetenz nach DIN EN ISO/IEC 17025:2005 besitzt, Prüfungen in folgenden Bereichen durchzuführen:

Drahtgebundene Kommunikation einschließlich xDSL VoIP und DECT

VoIP und DECT
Akustik
Funk einschließlich WLAN
Short Range Devices (SRD)
RFID
Wilmax und Richtfunk
Mobilitunk (OSN / DCS, Over the Air (OTA) Performance)
Elektromagnetische Verträglichkeit (EMV) einschließlich Automotive Elektromagnetische Verträglichkeit (EMV) Produktsicherheit SAR und Hearing Aid Compatibility (HAC) Umweltsimulation

Smart Card Terminals Bluetooth Wi-Fi- Services

Die Akkreditierungsurkunde gilt nur in Verbindung mit dem Bescheld vom 07.03.2014 mit der Akkreditierungsnummer D-Pt-17076-01 und ist gillig 17.01.2018. Sie besteht aus diesem Deckblatt, der Rückseite des Deckblatts und der fulgenden Anlage mit Insgesamt 77 Seiten.

Registrierungsnummer der Urkunde: D-PL-12076-01-00

Frankfurt om Main, 07.03.2014

Deutsche Akkreditierungsstelle GmbH

Standort Frankfurt am Main

Die auszugsweise Veröffentlichung der Akkreditierungsunkunde becamf der wurhenigen schrißlichen Zusämmung der Deutsche Akkreditierungsstelle Gribh (DANKS). Ausgenommen diesen ist die separate Weiterveroreitung des Deckliattes durch die umseitig genennte Kunformitätsbewertungsstelle in umeränderter Form.

Es darf nicht der Ansthein erweckt werden, dass sich die Akkreditierung auch auf Bereichs erstreed, die über den durch die DAkkS bestätigten Akkreditierungsbereich hinausgehen.

Die Akkreditierung erfolgte gemöß des Grachten über din Akkreditierungsstells (Akkstellect) vom 31 Juli 2009 (Boß). I. S. 2675) sowie der Verordrung (161) Nr. 7657/2008 des Europäischen Parlament und des Rates vom S. 1.11 2008 (Boß der Verordrung). In R. 7657/2008 des Europäischen Parlament im Zusammenhang mit der Vermanktung von Produkten (Abl. L. 218 vom S. 1.11 2008, S. 30). Die DAkk Sist Uterrer dessein der Wildlasstellen Akkstemmen uns gegenste Higen Areste enung der European ers operation für Ausreditätien (EA), des Hebraatienal Acceptation form (IAI) and der International Labestury Ausredition on Ecoporation (LIAC). Die Unterzeichner eleser Abkommen erkomeen ihre Akkreditierungen gegenstellig an.

Der aktue in Stund der Villiglindsmaß kom folgen den Websetten ertnommen werden: FSL: www.naropisch-accord tellon.org IIAC: www.lateur; IAS: www.lateur;

# Note:

The current certificate including annex is published on our website (see link below) or may be received from CETECOM ICT Services on request.

http://www.cetecom.com/eu/de/cetecom-group/europa/deutschland-saarbruecken/akkreditierungen.html

2014-05-27 Page 17 of 17