

**EMC Technologies Pty Ltd** 

ABN 82 057 105 549 176 Harrick Road Keilor Park Victoria Australia 3042

Ph: + 613 9365 1000 Fax: + 613 9331 7455 email: melb@emctech.com.au

### SAR Test Report

Report Number: M070616\_CERT\_4965AGN\_SAR\_2.4

Test Sample: Portable TABLET Computer

Radio Modules: WLAN 4965AGN & Bluetooth EYTF3CS FT

Model Number: T2010

Tested For: Fujitsu Australia Pty Ltd

FCC ID: EJE-WB0052

IC: 337J-WB0052

Date of Issue: 6th July 2007

EMC Technologies Pty Ltd reports apply only to the specific samples tested under stated test conditions. It is the manufacturer's responsibility to assure that additional production units of this model are manufactured with identical electrical and mechanical components. EMC Technologies Pty Ltd shall have no liability for any deductions, inferences or generalisations drawn by the client or others from EMC Technologies Pty Ltd issued reports. This report shall not be used to claim, constitute or imply product endorsement by EMC Technologies Pty Ltd.

#### **CONTENTS**

1.0	General Information	3
2.0	INTRODUCTION	4
3.0	Sample Technical INFORMATION	4
	3.1 EUT (WLAN) Details	4
	3.2 EUT (Bluetooth) Details	
	3.3 EUT (Notebook PC) Details	
	3.4 Test sample Accessories	
	3.4.1 Battery Types	
	4.0 Test Signal, Frequency and Output Power	
	4.1 Battery Status	
	5.0 Details of Test Laboratory	
	5.2 Accreditations	
	5.3 Environmental Factors	
6.0	DESCRIPTION OF SAR MEASUREMENT SYSTEM	
0.0	6.1 Probe Positioning System	
	6.2 E-Field Probe Type and Performance	
	6.3 Data Acquisition Electronics	
	6.4 Validation	
	6.4.1 Validation Results @ 2450MHz	
	6.4.2 Deviation from reference validation values	
	6.4.3 Liquid Depth 15cm	
	6.5 Phantom Properties (Size, Shape, Shell Thickness)	
	6.6 Tissue Material Properties	
	6.6.1 Liquid Temperature and Humidity	
	6.7 Simulated Tissue Composition Used for SAR Test	
	6.8 Device Holder for Laptops and P 10.1 Phantom	
7.0	SAR Measurement Procedure Using DASY4	
8.0	MEASUREMENT UNCERTAINTY	
9.0	Equipment List and Calibration Details	
10.0	OET Bulletin 65 – Supplement C Test Method	18
	10.1.1 "Tablet" Position Definition (0mm spacing)	
	10.1.2 "Edge On" Position	
	10.2 List of All Test Cases (Antenna In/Out, Test Frequencies, User Modes)	
	10.3 FCC RF Exposure Limits for Occupational/ Controlled Exposure	
44.0	SAR measurement RESULTS	
11.0	11.1.1 2450MHz SAR Results	
400		
	Compliance statement	
	ENDIX A1 Test Sample Photographs	
APP	ENDIX A2 Test Sample Photographs	24
APP	ENDIX A3 Test Sample Photographs	25
APP	ENDIX A4 Test Setup Photographs	26
APP	ENDIX A5 Test Sample Photographs	27
APP	ENDIX A6 Test Sample Photographs	28
APP	ENDIX A7 Test Sample Photographs	29
ΔΡΡ	FNDIX B Plots of the SAR Measurements	30

#### SAR TEST REPORT

Report Number: M070616\_CERT\_4965AGN \_SAR\_2.4

FCC ID: <u>EJE-WB0052</u> IC: 337J-WB0052

#### 1.0 GENERAL INFORMATION

**Test Sample:** Portable Tablet Computer

Model Name: T2010

Radio Modules: WLAN 4965AGN & Bluetooth EYTF3CS FT

Interface Type:Mini-PCI ModuleDevice Category:Portable TransmitterTest Device:Pre-Production UnitFCC ID:EJE-WB0052IC:337J-WB0052

RF exposure Category: General Population/Uncontrolled

Manufacturer: Fujitsu Limited

**Test Standard/s:**1. Evaluating Compliance with FCC Guidelines For Human Exposure to

Radiofrequency Electromagnetic Fields

Supplement C (Edition 01-01) to OET Bulletin 65 (Edition 97-01)

2. Evaluation Procedure for Mobile and Portable Radio Transmitters with respect to Health Canada's Safety Code 6 for Exposure of

Humans to Radio Frequency Fields.

RSS-102 Issue 1 (Provisional) September 25, 1999

Statement Of Compliance: The Fujitsu TABLET Computer T2010 with Wireless LAN model

4965AGN and Bluetooth module EYTF3CS FT complied\* with the FCC General public/uncontrolled RF exposure limits of 1.6mW/g per requirements of 47CFR2.1093(d). It also complied with IC RSS-102

requirements.

\*. Refer to compliance statement section 9.

Test Date: 25<sup>th</sup> June – 3<sup>rd</sup> July 2007

**Tested for:** Fujitsu Australia Pty Ltd

Address: 1230 Nepean Highway, Cheltenham VIC 3192

 Contact:
 Praveen Rao

 Phone:
 +61 3 9265 0210

 Fax:
 +61 3 9265 0656

E-mail: Praveen.rao@au.fujitsu.com

Peter Jakubiec

**Authorised Signature:** 

**Test Officer:** 

Peter Jakubiec

#### **SAR TEST REPORT**

# Portable TABLET Computer Model: T2010 Report Number: M070616\_CERT\_4965AGN\_SAR\_2.4

#### 2.0 INTRODUCTION

Testing was performed on the Fujitsu TABLET PC, Model: T2010 with INTEL Mini-PCI Wireless LAN Module (KEDRON 802.11a/b/g/n), Model: 4965AGN & TAIYO YUDEN Bluetooth Module, Model: EYTF3CS FT. The KEDRON module is an OEM product. The Mini-PCI Wireless LAN (WLAN) was tested in the dedicated host – LIFEBOOK T SERIES, Model T2010.

The measurement test results mentioned hereon only apply to the 2450MHz frequency band; an additional report titled "M070616\_CERT\_4965AGN \_SAR\_5.6" applies to the 5GHz range.

#### 3.0 SAMPLE TECHNICAL INFORMATION

(Information supplied by the client)

#### 3.1 EUT (WLAN) Details

**Transmitter:** Mini-Card Wireless LAN Module Wireless Module: KEDRON (802.11a/b/g/n)

Model Number: 4965AGN
Manufacturer: Intel Corporation

Modulation Type: Direct Sequence Spread Spectrum (DSSS for 802.11b)

Orthogonal Frequency Division Multiplexing (OFDM for 802.11g) Orthogonal Frequency Division Multiplexing (OFDM for 802.11a) Orthogonal Frequency Division Multiplexing (OFDM for 802.11n)

2.4 GHz (802.11b/g/n): DBPSK, DQPSK, CCK, 16QAM and 64QAM

**5 GHz (802.11a/n):** BPSK, QPSK, 16QAM and 64QAM

**Maximum Data Rate:** 802.11b = 11Mbps, 802.11g and 802.11a = 54Mbps

802.11n = 300 Mbps

Frequency Ranges: 2.412 –2.462 GHz for 11b/g/n

5.18 - 5.32 GHz and 5.745 - 5.825 GHz for 11a/n

Number of Channels: 11 channels for 11b/g/n

13 channels for 11a/n with 20 MHz bandwidth 6 channels for 11n with 40 MHz bandwidth

Antenna Types: Tx: Yokowo Monopole Antenna

Model: CP338043(T1:Right), CP338042(T2:Left)

Location: Top edge of LCD screen

**Power Supply:** 3.3 VDC from PCI bus

Channels and Output power setting:

Channel and Mode	Frequency MHz	Data Rates Mbps	Average Output Power dBm
802.11b/g/n mode			
Channels 1, 6 and 11	2412, 2437 and 2462	1 to 54 / HT0 – HT7	15.5
Channels 1, 6 and 11	2412, 2437 and 2462	HT8 – HT15	12.5/12.5 (ant. A and B)
802.11a/n mode with 20MHz Bandwidth			
Channels 36, 52, 64	5180, 5260 and 5320	6 to 54 / HT0 – HT7	16.5
Channels 36, 52, 64	5180, 5260 and 5320	HT8 – HT15	13.5/13.5 (ant. A and B)
Channels 149, 157 and 165	5745, 5785 and 5825	6 to 54 / HT0 – HT7	17.5
Channels 149, 157 and 165	5745, 5785 and 5825	HT8 – HT15	14.5/14.5 (ant. A and B)
802.11n mode with 40MHz Bandwidth			
Channels 38	5190	HT0 – HT7	14.5
Channels 46	5230	HT0 – HT7	16.5
Channels 62	5310	HT0 – HT7	15.5
Channels 38	5190	HT8 – HT15	11.5/11.5 (ant. A and B)
Channels 46	5230	HT8 – HT15	13.5/13.5 (ant. A and B)
Channels 62	5310	HT8 – HT15	12.5/12.5 (ant. A and B)
Channels 151 and 159	5755 and 5795	HT0 – HT7	17.5
Channels 151 and 159	5755 and 5795	HT8 – HT15	14.5/14.5 (ant. A and B)

NOTE: For 5GHz SAR results refer to report titled "M070616\_CERT\_4965AGN\_SAR\_5.6".

#### **EUT (Bluetooth) Details** 3.2

Transmitter: Bluetooth Model Number: EYTF3CS FT TAIYO YUDEN Manufacturer:

Network Standard:

Bluetooth<sup>TM</sup> RF Test Specification Frequency Hopping Spread Spectrum (FHSS) Modulation Type:

Frequency Range: 2402 MHz to 2480 MHz

Number of Channels: 79 Carrier Spacing: 1.0 MHz

Taiyo Yuden Monopole Antenna, Model: CP331590 Antenna Types:

Location: Right palm rest

Max. Output Power: 4 dBm

Reference Oscillator: 16 MHz (Built-in) 3.3 VDC from host. **Power Supply:** 

#### Frequency allocation:

Channel Number	Frequency (MHz)	Bluetooth Utility power setting
1	2402	
2	2403	
-	-	
39	2440	
40	2441	Power (Ext, Int) = 0, 96
41	2442	· · ·
-	-	
78	2479	
79	2480	

#### 3.3 EUT (Notebook PC) Details

**EUT:** LIFEBOOK T SERIES

Model Name: T2010

Serial Number: Pre-production Sample Manufacturer: FUJITSU LIMITED

CPU Type and Speed: Core2 Duo U7600 1.20GHz/U7500 1.06GHz

LCD 12.1"WXGA

Wired LAN: Marvell 88E8055 : 10 Base-T/100 Base-TX/1000Base-T

Modem: Agere MDC1.5 modem Model: D40 Port Replicator Model: FPCPR77 / FPCPR79 / FPCPR80

AC Adapter Model: 60W:SEC80N2-16.0(Sanken)

 Voltage:
 16 V

 Current Specs:
 3.75A

 Watts:
 60W

#### 3.4 Test sample Accessories

#### 3.4.1 Battery Types

One type of Fujitsu Lithium Ion Battery is used to power the Portable TABLET Computer Wireless LAN Model: 4965AGN. SAR measurements were performed with the battery as shown below.

#### **Standard Battery**

Model CP345809-01 V/mAh 10.8V/5800mAh

Cell No. 6

#### 4.0 Test Signal, Frequency and Output Power

INTEL's CRTU test tool was used to configure the WLAN for testing. The Portable Tablet Computer Wireless LAN had a total of 11 channels (USA model) within the 2412 to 2462 MHz frequency band and 17 channels within the frequency range 5180 – 5825 MHz. In The frequency range 2412 MHz to 2462 MHz the device operates in 2 modes, OFDM and DSSS. Within the 5180 – 5825 MHz frequency range the device operates in OFDM mode only. For the SAR measurements the device was operating in continuous transmit mode using programming codes supplied by Fujitsu. The fixed frequency channels used in the testing are shown in Table Below.

The Bluetooth module operates over 79 channels within the frequency range 2402 to 2480 MHz. It is possible for the Bluetooth module to operate simultaneously with the WLAN module (co-transmission). For the SAR measurements the device was operating in continuous transmit mode using programming codes supplied by Fujitsu. The tests were conducted with only the WLAN operating and also with the WLAN and Bluetooth module operating in co-transmission. The fixed frequency channels used in the testing are shown in the table below. The Bluetooth interface utilizes dedicated antenna, for the purpose of this report labelled antenna "D".

The test results mentioned in this report only apply to the 2450MHz frequency range. An additional report titled "M070616\_CERT\_4965AGN\_SAR\_5.6" is specific to the 5GHz range.

The WLAN modules can be configured in a number of different data rates. It was found that the highest source based time averaged power was measured when using the lowest data rates available in each mode. This lowest data rate corresponds to 6Mbps in OFDM mode and 1Mbps in DSSS mode.

The frequency span of the 2450 MHz range Band was more than 10MHz consequently; the SAR levels of the test sample were measured for lowest, centre and highest channels in the applicable modes. The EUT is capable of using two antennas transmitting simultaneously (HT8 DATA mode) the power level is 3dB lower (50%) than if a single antenna was transmitting. There were no wires or other connections to the Portable TABLET Computer during the SAR measurements.

At the beginning and at the completion of the SAR tests, the conducted power of the device was measured after temporary modification of antenna connector inside the device's TX RX compartment. Measurements were performed with a calibrated Power Meter. The results of this measurement are listed in table below.

**Table: Frequency and Conducted Power Results** 

Channel	Channel Frequency MHz	Data Rates	Maximum Conducted Output Power - Peak Measured (dBm)
Channel 01	2412	1 (DSSS)	16.5
Channel 06	2437	1 (DSSS)	16.9
Channel 11	2462	1 (DSSS)	17.0
Channel 01	2412	6	16.3
Channel 06	2437	6	16.5
Channel 11	2462	6	16.9
Channel 01	2412	HT0	16.7
Channel 06	2437	HT0	16.6
Channel 11	2462	HT0	16.8
Channel 01	2412	HT8	13.5
Channel 06	2437	HT8	14.2
Channel 11	2462	HT8	14.1

Frequency and Conducted Power Results Bluetooth

Channel	Channel Frequency MHz	*Data Rate (Mbps)	Maximum Conducted Output Power Measured (dBm)
Channel 40	2441	N/A	3.7

#### 4.1 Battery Status

The device battery was fully charged prior to commencement of measurement. Each SAR test was completed within 30 minutes. The battery condition was monitored by measuring the RF field at a defined position inside the phantom before the commencement of each test and again after the completion of the test. It was not possible to perform conducted power measurements at the output of the device, at the beginning and end of each scan due to lack of a suitable antenna port. The uncertainty associated with the power drift was less than 12% and was assessed in the uncertainty budget.

#### 5.0 Details of Test Laboratory

#### 5.1 Location

EMC Technologies Pty Ltd 176 Harrick Road Keilor Park, (Melbourne) Victoria Australia 3042

Telephone: +61 3 9365 1000 Facsimile: +61 3 9331 7455 email: melb@emctech.com.au website: www.emctech.com.au

#### 5.2 Accreditations

EMC Technologies Pty. Ltd. is accredited by the National Association of Testing Authorities, Australia (NATA). **NATA Accredited Laboratory Number: 5292** 

EMC Technologies Pty Ltd is NATA accredited for the following standards: **AS/NZS 2772.1:** RF and microwave radiation hazard measurement

ACA: Radio communications (Electromagnetic Radiation - Human Exposure) Standard 2003

FCC: Guidelines for Human Exposure to RF Electromagnetic Field OET65C 01/01

EN 50360: 2001 Product standard to demonstrate the compliance of mobile phones with the basic restrictions related to human exposure to electromagnetic fields (300 MHz – 3 GHz)

EN 50361: 2001 Basic standard for the measurement of Specific Absorption Rate related to human

exposure to electromagnetic fields from mobile phones (300MHz – 3GHz)

IEEE 1528: 2003 Recommended Practice for Determining the Peak Spatial-Average Specific Absorption

Rate (SAR) in the Human Head Due to Wireless Communications Devices: Measurement

Techniques.

Refer to NATA website www.nata.asn.au for the full scope of accreditation.

#### 5.3 Environmental Factors

The measurements were performed in a shielded room with no background RF signals. The temperature in the laboratory was controlled to within  $21\pm1^{\circ}$ C, the humidity was in the range 31% to 51%. The liquid parameters are measured daily prior to the commencement of each test. Tests were performed to check that reflections within the environment did not influence the SAR measurements. The noise floor of the DASY4 SAR measurement system using the SN1380 probe was less than  $5\mu V$  in both air and liquid mediums.

#### 6.0 DESCRIPTION OF SAR MEASUREMENT SYSTEM

Applicable Head Configurations	: None
Applicable Body Configurations	: Tablet Position
	: Edge On Position

#### 6.1 Probe Positioning System

The measurements were performed with the state-of-the-art automated near-field scanning system **DASY4 V4.7 Build 53** from Schmid & Partner Engineering AG (SPEAG). The system is based on a high precision 6-axis robot (working range greater that 1.1m), which positions the SAR measurement probes with a positional repeatability of better than  $\pm 0.02$  mm. The DASY4 fully complies with the OET65 C (01-01), IEEE 1528 and EN50361 SAR measurement requirements.

#### 6.2 E-Field Probe Type and Performance

The SAR measurements were conducted with SPEAG dosimetric probe ET3DV6 Serial: 1380 (2.45 GHz) designed in the classical triangular configuration and optimised for dosimetric evaluation. The probes have been calibrated and found to be accurate to better than  $\pm 0.25$  dB. The probe is suitable for measurements close to material discontinuity at the surface of the phantom. The sensors of the probe are directly loaded with Schottky diodes and connected via highly resistive lines (length = 300 mm) to the data acquisition unit.

#### 6.3 Data Acquisition Electronics

The data acquisition electronics (DAE3) consists of a highly sensitive electrometer-grade preamplifier with autozeroing, a channel and gain switching multiplexer, a fast 16 bit AD-converter and a command decoder and control logic unit. The input impedance of the DAE3 box is 200 M $\Omega$ ; the inputs are symmetrical and floating. Common mode rejection is above 80dB.Transmission to the PC-card is accomplished through an optical downlink for data and status information as well as an optical uplink for commands and the clock.

The mechanical probe-mounting device includes two different sensor systems for frontal and sideways probe contacts. They are used for mechanical surface detection and probe collision detection.

#### 6.4 Validation

#### 6.4.1 Validation Results @ 2450MHz

The following tables lists the dielectric properties of the tissue simulating liquid measured prior to SAR validation. The results of the validation are listed in columns 4 and 5. The forward power into the reference dipole for SAR validation was adjusted to 250 mW.

Table: Validation Results (Dipole: SPEAG D2450V2 SN: 724)

1. Validation Date	2. ∈r (measured)	3. σ (mho/m) (measured)	4. Measured SAR 1g (mW/g)	5. Measured SAR 10g (mW/g)
29 <sup>th</sup> June 2007	40.5227	1.76538	13.6	6.37
2 <sup>nd</sup> July 2007	40.7753	1.782	13.6	6.37
3 <sup>rd</sup> July 2007	40.3992	1.83646	13.8	6.4

#### 6.4.2 Deviation from reference validation values

The reference SAR values are derived using a reference dipole and flat section of the SAM phantom suitable for a centre frequency of 2450MHz. These reference SAR values are obtained from the IEEE Std 1528-2003 and are normalized to 1W.

The SPEAG calibration reference SAR value is the SAR validation result obtained in a specific dielectric liquid using the validation dipole (D2450V2) during calibration. The measured one-gram SAR should be within 10% of the expected target reference values shown in table below (2450MHz) below.

Table: Deviation from reference validation values @ 2450MHz

Frequency and Date	Measured SAR 1g (mW/g)	Measured SAR 1g (Normalized to 1W)	SPEAG Calibration reference SAR Value 1g (mW/g)	Deviation From SPEAG Reference (1g)	IEEE Std 1528 reference SAR value 1g (mW/g)	Deviation From IEEE (1g)
2450MHz 29 <sup>th</sup> June 2007	13.6	54.4	54	0.74	52.4	3.82\
2450MHz 2 <sup>nd</sup> July 2007	13.6	54.4	54	0.74	52.4	3.82
2450MHz 3 <sup>rd</sup> July 2007	13.8	55.2	54	2.22	52.4	5.34

NOTE: All reference validation values are referenced to 1W input power.

#### 6.4.3 Liquid Depth 15cm

During the SAR measurement process the liquid level was maintained to a level of 15cm with a tolerance of 0.5cm.




Photo of liquid Depth in Flat Phantom

#### 6.5 Phantom Properties (Size, Shape, Shell Thickness)

The phantom used during the validations was the SAM Phantom model: TP - 1260 from SPEAG. It is a phantom with a single thickness of 2 mm and was filled with the required tissue simulating liquid. The SAM phantom support structures were all non-metallic and spaced more than one device width away in transverse directions.

For SAR testing in the body worn positions an AndreT Flat phantom P 10.1 was used. The phantom thickness is 2.0mm+/-0.2 mm and was filled with the required tissue simulating liquid. Below table provides a summary of the measured phantom properties. Refer to Appendix C Part 4, for details of P 10.1 phantom dielectric properties and loss tangent.

Table: Phantom Properties (300MHz-2500MHz)

Phantom Properties	Required	Measured
Thickness of flat section	2.0mm ± 0.2mm (bottom section)	2.12-2.20mm
Dielectric Constant	<5.0	4.603 @ 300MHz (worst-case frequency)
Loss Tangent	<0.05	0.0379 @ 2500MHz (worst-case frequency)

Depth of Phantom 200mm
Length of Flat Section 620mm
Width of Flat Section 540mm

P 10.1 Flat Phantom



P 10.1 Flat Phantom



#### 6.6 Tissue Material Properties

The dielectric parameters of the brain simulating liquid were measured prior to SAR assessment using the HP85070A dielectric probe kit and HP8753ES Network Analyser. The actual dielectric parameters are shown in the following table.

**Table: Measured Brain Simulating Liquid Dielectric Values for Validations** 

Frequency Band	∈r (measured range)	∈r (target)	σ (mho/m) (measured range)	σ (target)	ρ <b>kg/m</b> ³
2450 MHz Brain	40.4 - 40.8	39.2 ±5% (37.2 to 41.2)	1.77 - 1.84	1.80 ±5% (1.71 to 1.89)	1000

NOTE: The brain liquid parameters were within the required tolerances of  $\pm 5\%$ .

**Table: Measured Body Simulating Liquid Dielectric Values** 

rabior indada Deay of indiating Enquire Profession Values						
Frequency Band	∈r (measured range)	∈r (target)	σ (mho/m) (measured range)	σ (target)	ρ <b>kg/m</b> ³	
2412 MHz Muscle	53.0	52.7 ±5% (50.1 to 55.3)	1.97	1.95 ±5% (1.85 to 2.05)	1000	
2437 MHz Muscle	52.9 – 53.1	52.7 ±5% (50.1 to 55.3)	1.91 – 1.92	1.95 ±5% (1.85 to 2.05)	1000	
2462 MHz Muscle	52.7	52.7 ±5% (50.1 to 55.3)	2.04	1.95 ±5% (1.85 to 2.05)	1000	

NOTE: The brain and muscle liquid parameters were within the required tolerances of  $\pm 5\%$ .

#### 6.6.1 Liquid Temperature and Humidity

The humidity and dielectric/ambient temperatures were recorded during the assessment of the tissue material dielectric parameters. The difference between the ambient temperature of the liquid during the dielectric measurement and the temperature during tests was less than |2|°C.

Table: Temperature and Humidity recorded for each day

Date	Ambient Temperature (°C)		Humidity (%)
29 <sup>th</sup> June 2007	21.9	21.7	50.0
2 <sup>nd</sup> July 2007	21.5	21.2	41.0
3 <sup>rd</sup> July 2007	20.5	20.2	48.0

#### 6.7 Simulated Tissue Composition Used for SAR Test

The tissue simulating liquids are created prior to the SAR evaluation and often require slight modification each day to obtain the correct dielectric parameters.

Table: Tissue Type: Brain @ 2450MHz
Volume of Liquid: 30 Litres

Table: Tissue Type: Muscle @ 2450MHz
Volume of Liquid: 60 Litres

Approximate Composition	% By Weight
Distilled Water	62.7
Salt	0.5
Triton X-100	36.8

	Approximate Composition	% By Weight
	Distilled Water	73.2
ſ	Salt	0.04
ſ	DGBE	26.7

<sup>\*</sup>Refer "OET Bulletin 65 97/01 P38"

#### Device Holder for Laptops and P 10.1 Phantom

A low loss clamp was used to position the TABLET underneath the phantom surface. Small pieces of foam were then used to press the TABLET flush against the phantom surface.

Refer to Appendix A for photographs of device positioning

FCC ID: EJE-WB0052 IC: 337J-WB0052

#### 7.0 SAR MEASUREMENT PROCEDURE USING DASY4

The SAR evaluation was performed with the SPEAG DASY4 system. A summary of the procedure follows:

- A measurement of the SAR value at a fixed location is used as a reference value for assessing the power drop of the EUT. The SAR at this point is measured at the start of the test, and then again at the end of the test.
- The SAR distribution at the exposed flat section of the flat phantom is measured at a distance of 3.9 mm from the inner surface of the shell. The area covers the entire dimension of the EUT and the horizontal grid spacing is 15 mm x 15 mm. The actual Area Scan has dimensions of 81mm x 101mm surrounding the test device. Based on this data, the area of the maximum absorption is determined by Spline interpolation. The first "pre-scans" covered an area of 141 mm x 171 mm to ensure that the hotspot was correctly identified.
- Around this point, a volume of 30 mm x 30 mm x 30 mm is assessed by measuring 7 x 7 x 7 points. On the basis of this data set, the spatial peak SAR value is evaluated with the following procedure:
  - The data at the surface are extrapolated, since the centre of the dipoles is 2.7 mm away from the tip of the probe and the distance between the surface and the lowest measuring point is 1.2 mm. The extrapolation is based on a least square algorithm. A polynomial of the fourth order is calculated through the points in z-axes. This polynomial is then used to evaluate the points between the surface and the probe tip.
  - (ii) The maximum interpolated value is searched with a straightforward algorithm. Around this maximum the SAR values averaged over the spatial volumes (1 g and 10 g) are computed using the 3D-Spline interpolation algorithm. The 3D-Spline is composed of three one-dimensional splines with the "Not a knot"- condition (in x, y and z-direction). The volume is integrated with the trapezoidal - algorithm. One thousand points (10 x 10 x 10) are interpolated to calculate the averages.
  - (iii) All neighbouring volumes are evaluated until no neighbouring volume with a higher average value is found.
  - (iv) The SAR value at the same location as in Step (a) is again measured to evaluate the actual power drift.

#### 8.0 MEASUREMENT UNCERTAINTY

The uncertainty analysis is based on the template listed in the IEEE Std 1528-2003 for both Handset SAR tests and Validation uncertainty. The measurement uncertainty of a specific device is evaluated independently and the total uncertainty for both evaluations (95% confidence level) must be less than 30%.

Table: Uncertainty Budget for DASY4 V4.7 Build 53 - EUT SAR test 2450MHz

a	b	С	d	e= f(d,k)	f	g	h=cxf/e	i=cxg/e	k
Uncertainty Component	Sec.	Tol. (%)	Prob. Dist.	Div.	C <sub>i</sub> (1g)	C <sub>i</sub> (10g)	1g u <sub>i</sub> (%)	10g u <sub>i</sub> (%)	Vi
Measurement System									
Probe Calibration (k=1) (numerical calibration)	7.2.1	4.8	N	1	1	1	4.8	4.8	8
Axial Isotropy	7.2.1	4.7	R	1.73	0.707	0.707	1.9	1.9	8
Hemispherical Isotropy	7.2.1	9.6	R	1.73	0.707	0.707	3.9	3.9	8
Boundary Effect	7.2.1	1	R	1.73	1	1	0.6	0.6	8
Linearity	7.2.1	4.7	R	1.73	1	1	2.7	2.7	8
System Detection Limits	7.2.1	1	R	1.73	1	1	0.6	0.6	8
Readout Electronics	7.2.1	1	N	1	1	1	1.0	1.0	8
Response Time	7.2.1	0.8	R	1.73	1	1	0.5	0.5	8
Integration Time	7.2.1	2.6	R	1.73	1	1	1.5	1.5	8
RF Ambient Conditions	7.2.3	0.05	R	1.73	1	1	0.0	0.0	$\infty$
Probe Positioner Mechanical Tolerance	7.2.2	0.4	R	1.73	1	1	0.2	0.2	∞
Probe Positioning with respect to Phantom Shell	7.2.2	2.9	R	1.73	1	1	1.7	1.7	8
Extrapolation, interpolation and Integration Algorithms for Max. SAR Evaluation	7.2.4	1	R	1.73	1	1	0.6	0.6	8
Test Sample Related									
Test Sample Positioning	7.2.2	1.61	N	1	1	1	1.6	1.6	11
Device Holder Uncertainty									7
Output Power Variation – SAR Drift Measurement	7.2.3	8.42	R	1.73	1	1	4.9	4.9	8
Phantom and Tissue Parameters									
Phantom Uncertainty (shape and thickness tolerances)	7.2.2	4	R	1.73	1	1	2.3	2.3	∞
Liquid Conductivity – Deviation from target values	7.2.3	5	R	1.73	0.64	0.43	1.8	1.2	8
Liquid Conductivity – Measurement uncertainty	7.2.3	4.3	N	1	0.64	0.43	2.8	1.8	5
Liquid Permittivity – Deviation from target values	7.2.3	5	R	1.73	0.6	0.49	1.7	1.4	8
Liquid Permittivity – Measurement uncertainty	7.2.3	4.3	N	1	0.6	0.49	2.6	2.1	5
Combined standard Uncertainty			RSS				11.0	10.5	154
Expanded Uncertainty (95% CONFIDENCE LEVEL)			k=2				21.9	21.06	

Estimated total measurement uncertainty for the DASY4 measurement system was  $\pm 11.0\%$ . The extended uncertainty (K = 2) was assessed to be  $\pm 21.9\%$  based on 95% confidence level. The uncertainty is not added to the measurement result.

Table: Uncertainty Budget for DASY4 V4.7 Build 53 - Validation 2450MHz

a	b	С	D	e= f(d,k)	f	g	h=cxf/e	i=cxg/e	k
Uncertainty Component	Sec.	Tol. (6%)	Prob. Dist.	Div.	C <sub>i</sub> (1g)	C <sub>i</sub> (10g)	1g u <sub>i</sub> (6%)	10g u <sub>i</sub> (6%)	Vi
Measurement System									
Probe Calibration (k=1) (standard calibration)	E.2.1	4.8	N	1	1	1	4.8	4.8	8
Axial Isotropy	E.2.2	4.7	R	1.73	1	1	2.7	2.7	8
Hemispherical Isotropy	E.2.2	0	R	1.73	1	1	0.0	0.0	8
Boundary Effect	E.2.3	1	R	1.73	1	1	0.6	0.6	8
Linearity	E.2.4	4.7	R	1.73	1	1	2.7	2.7	8
System Detection Limits	E.2.5	1	R	1.73	1	1	0.6	0.6	8
Readout Electronics	E.2.6	1	N	1	1	1	1.0	1.0	8
Response Time	E.2.7	0	R	1.73	1	1	0.0	0.0	8
Integration Time	E.2.8	0	R	1.73	1	1	0.0	0.0	8
RF Ambient Conditions	E.6.1	0.05	R	1.73	1	1	0.0	0.0	8
Probe Positioner Mechanical Tolerance	E.6.2	0.4	R	1.73	1	1	0.2	0.2	8
Probe Positioning with respect to Phantom Shell	E.6.3	2.9	R	1.73	1	1	1.7	1.7	8
Extrapolation, interpolation and Integration Algorithms for Max. SAR Evaluation	E.5	1	R	1.73	1	1	0.6	0.6	8
Test Sample Related									
Dipole Axis to Liquid Surface		2	R	1.73	1	1	1.2	1.2	8
Power Drift		4.7	R	1.73	1	1	2.7	2.7	8
Phantom and Tissue Parameters									
Phantom Uncertainty (shape and thickness tolerances)	E.3.1	4	R	1.73	1	1	2.3	2.3	8
Liquid Conductivity – Deviation from target values	E.3.2	5	R	1.73	0.6	0.43	1.7	1.2	8
Liquid Conductivity – Measurement uncertainty	E.3.3	2.5	N	1.73	0.6	0.43	0.9	0.6	5
Liquid Permittivity – Deviation from target values	E.3.2	5	R	1.73	0.6	0.49	1.7	1.4	8
Liquid Permittivity – Measurement uncertainty	E.3.3	2.5	N	1.73	0.6	0.49	0.9	0.7	5
Combined standard Uncertainty			RSS				8.0	7.8	154
Expanded Uncertainty (95% CONFIDENCE LEVEL)			k=2				16.0	15.63	

Estimated total measurement uncertainty for the DASY4 measurement system was  $\pm 8.0\%$ . The extended uncertainty (K = 2) was assessed to be  $\pm 16.0\%$  based on 95% confidence level. The uncertainty is not added to the Validation measurement result.

#### 9.0 EQUIPMENT LIST AND CALIBRATION DETAILS

Table: SPEAG DASY4 Version V4.7 Build 53

Equipment Type	Manufacturer	Model Number	Serial Number	Calibration Due	Used For this Test?	
Robot - Six Axes	Staubli	RX90BL	N/A	Not applicable	Yes	
Robot Remote Control	SPEAG	CS7MB	RX90B	Not applicable	Yes	
SAM Phantom	SPEAG	N/A	1260	Not applicable	Yes	
SAM Phantom	SPEAG	N/A	1060	Not applicable	No	
Flat Phantom	AndreT	10.1	P 10.1	Not Applicable	Yes	
Flat Phantom	AndreT	9.1	P 9.1	Not Applicable	No	
Flat Phantom	SPEAG	PO1A 6mm	1003	Not Applicable	No	
Data Acquisition Electronics	SPEAG	DAE3 V1	359	12-July-2007	No	
Data Acquisition Electronics	SPEAG	DAE3 V1	442	13-Oct-2007	Yes	
Probe E-Field - Dummy	SPEAG	DP1	N/A	Not applicable	No	
Probe E-Field	SPEAG	ET3DV6	1380	12-Dec-2007	Yes	
Probe E-Field	SPEAG	ET3DV6	1377	14-July-2007	No	
Probe E-Field	SPEAG	ES3DV6	3029	Not Used	No	
Probe E-Field	SPEAG	EX3DV4	3563	14-July-2007	No	
Antenna Dipole 300 MHz	SPEAG	D300V2	1005	26-Oct-2007	No	
Antenna Dipole 450 MHz	SPEAG	D450V2	1009	14-Dec-2008	No	
Antenna Dipole 900 MHz	SPEAG	D900V2	047	6-July-2008	No	
Antenna Dipole 1640 MHz	SPEAG	D1640V2	314	30-June-2008	No	
Antenna Dipole 1800 MHz	SPEAG	D1800V2	242	3-July-2008	No	
Antenna Dipole 1950 MHz	SPEAG	D1950V3	1113	5-March-2007	No	
Antenna Dipole 3500 MHz	SPEAG	D3500V2	1002	1-July-2007	No	
Antenna Dipole 2450 MHz	SPEAG	D2450V2	724	13-Dec-2008	Yes	
Antenna Dipole 5600 MHz	SPEAG	D5GHzV2	1008	27-Oct-2007	No	
RF Amplifier	EIN	603L	N/A	Not applicable	No	
RF Amplifier	Mini-Circuits	ZHL-42	N/A	Not applicable	Yes	
RF Amplifier	Mini-Circuits	ZVE-8G	N/A	Not applicable	Yes	
Synthesized signal generator	Hewlett Packard	ESG-D3000A	GB37420238	*In test	Yes	
RF Power Meter Dual	Hewlett Packard	437B	3125012786	30-May-008	Yes	
RF Power Sensor 0.01 - 18 GHz	Hewlett Packard	8481H	1545A01634	30-May-008	Yes	
RF Power Meter Dual	Gigatronics	8542B	1830125	11-May-2008	Yes	
RF Power Sensor	Gigatronics	80301A	1828805	11-May-2008	Yes	
RF Power Meter Dual	Hewlett Packard	435A	1733A05847	*In test	Yes	
RF Power Sensor	Hewlett Packard	8482A	2349A10114	*In test	Yes	
Network Analyser	Hewlett Packard	8714B	GB3510035	31-Aug-2007	No	
Network Analyser	Hewlett Packard	8753ES	JP39240130	30-Sept-2007	Yes	
Dual Directional Coupler	Hewlett Packard	778D	1144 04700	*In test	No	
Dual Directional Coupler	NARDA	3022	75453	*In test	Yes	

<sup>\*</sup> Calibrated during the test for the relevant parameters.

#### 10.0 OET BULLETIN 65 – SUPPLEMENT C TEST METHOD

Notebooks should be evaluated in normal use positions, typical for lap-held bottom-face only. However the number of positions will depend on the number of configurations the laptop can be operated in. The "LIFEBOOK T SERIES" can be used in either a conventional laptop position (see Appendix A1) or a Tablet configuration. The antenna location in the "LIFEBOOK T SERIES" is closest to the top of the screen when used in a conventional laptop configuration and due to the separation distances involved between the phantom and the laptop antenna, testing is not required in this position.

#### 10.1.1 "Tablet" Position Definition (0mm spacing)

The device was tested in the 2.00 mm flat section of the AndreT Flat phantom P 10.1 for the "Tablet" position. The Transceiver was placed at the bottom of the phantom and suspended in such way that the back of the device was touching the phantom. This device orientation simulates the PC's normal use – being held on the lap of the user. A spacing of 0mm ensures that the SAR results are conservative and represent a worst-case position.

#### 10.1.2 "Edge On" Position

The device was tested in the (2.00 mm) flat section of the AndreT phantom for the "Edge On" position. The Antenna edge of the Transceiver was placed underneath the flat section of the phantom and suspended until the edge touched the phantom. *Refer to Appendix A for photos of measurement positions.* 

#### 10.2 List of All Test Cases (Antenna In/Out, Test Frequencies, User Modes)

The device has a fixed antenna. Depending on the measured SAR level up to three test channels with the test sample operating at maximum power, as specified in section 4.0 were recorded. The following table represents the matrix used to determine what testing was required. The worst case result was verified with the Bluetooth transmitting at full power in co-transmission with the WLAN. The worst case result was also verified in the multiple antenna transmission mode, (HT8). In the HT8 mode the transmitter output power was 3dB lower than it was in single antenna mode.

Table:	Testing	configura	ations

Phantom	*Device Mode	Antenna	Tes	Test Configurations				
Configuration			CHANNEL (LOW)	Channel (Middle)	Channel (High)			
Tablet	OFDM 2.4GHz	Α		X				
		В		X				
	DSSS 2.4GHz	Α		X				
		В		X				
Edge On	OFDM 2.4GHz	Α		X				
		В		X				
	DSSS 2.4GHz	Α		X				
		В		X				

Legend X	Testing Required in this configuration
	Testing required in this configuration only if SAR of middle channel is more than 3dB below the SAR limit or it is the worst case

#### 10.3 FCC RF Exposure Limits for Occupational/ Controlled Exposure

Spatial Peak SAR Limits For:	
Partial-Body:	8.0 mW/g (averaged over any 1g cube of tissue)
Hands, Wrists, Feet and Ankles:	20.0 mW/g (averaged over 10g cube of tissue)

#### 10.4 FCC RF Exposure Limits for Un-controlled/Non-occupational

10.4 100 Ki Expectate Elittle 101 Gi	· controlled/item cocapational
Spatial Peak SAR Limits For:	
Partial-Body:	1.6 mW/g (averaged over any 1g cube of tissue)
Hands, Wrists, Feet and Ankles:	4.0 mW/g (averaged over 10g cube of tissue)

#### 11.0 SAR MEASUREMENT RESULTS

The SAR values averaged over 1g tissue masses were determined for the sample device for all test configurations listed in section 7.2.

#### 11.1.1 2450MHz SAR Results

There are two modes of operation within the 2450MHz band, they include OFDM and DSSS modulations. Refer to section 7.2 for selection of all device test configurations. Table below displays the SAR results.

Table: SAR MEASUREMENT RESULTS - DSSS Mode

Test Position	Plot No.	Ant A or B	Bit rate Mode (Mbps)	Channel Bandwidth (MHz)	Test Channel	Test Freq (MHz)	Measured 1g SAR Results (mW/g)	Measured Drift (dB)
*Tablet	1	В	1	-	06	2437	Pre-scan Only	0.519
*Edge On Top	2	Α	1	-	06	2437	Pre-scan Only	-0.137
*Edge On Top	3	В	1	-	06	2437	Pre-scan Only	-0.025
*Edge On Right	4	А	1	-	06	2437	Pre-scan Only	0.423
*Edge On Left	5	В	1	-	06	2437	Pre-scan Only	-0.499
Edge On Top	6	В	1	-	06	2437	0.666	-0.213
Edge On Right	7	А	1	-	06	2437	0.105	0.015
Edge On Left	8	В	1	-	06	2437	0.020	0.050
Edge On	9	Α	1	-	01	2412	1.31	0.27
Top	10	Α	1	-	06	2437	1.15	-0.151
	11	Α	1	-	11	2462	1.14	-0.01
Edge On Top with Bluetooth On	12	А	1	-	01	2412	1.21	0.098

NOTE: The measurement uncertainty of 21.9% for 2.45GHz was not added to the result.

Table: SAR MEASUREMENT RESULTS - OFDM Mode

Test Position	Plot No.	Ant A or B	Bit rate Mode (Mbps)	Channel Bandwidth (MHz)	Test Channel	Test Freq (MHz)	Measured 1g SAR Results (mW/g)	Measured Drift (dB)
Edge On Right	13	Α	6	•	06	2437	0.075	-0.135
Edge On Left	14	В	6	-	06	2437	0.024	-0.096
Edge On Top	15	Α	6	-	06	2437	0.805	0.138
Edge On Top	16	В	6	-	06	2437	0.533	-0.292
Edge On Top	17	Α	HT0	20	06	2437	0.871	-0.241
Edge On Top	18	A + B	HT8	20	01	2412	0.358	-0.351

NOTE: The measurement uncertainty of 21.9% for 2.45GHz was not added to the result.

The highest SAR level recorded in the 2450MHz band was 1.31 mW/g as evaluated in a 1g cube of averaging mass. This value was obtained in Edge On Top position in DSSS mode, utilizing channel 01 (2412 MHz) and antenna A. The Bluetooth was OFF.

#### FCC ID: $\underline{\mathsf{EJE}\text{-}WB0052}$ IC: $\underline{\mathsf{337J}\text{-}WB0052}$

#### 12.0 COMPLIANCE STATEMENT


The Fujitsu TABLET PC, Model: T2010 with INTEL Mini-PCI Wireless LAN Module (KEDRON 802.11a/b/g/n), Model: 4965AGN & TAIYO YUDEN Bluetooth Module, Model: EYTF3CS FT was found to comply with the FCC and RSS-102 SAR requirements.

The highest SAR level recorded was 1.31 mW/g for a 1g cube. This value was measured at 2412 MHz (channel 01) in the "Edge On Top" position in DSSS modulation mode at the antenna A. The Bluetooth was OFF. This was below the limit of 1.6 mW/g for uncontrolled exposure, even taking into account the measurement uncertainty of 21.9 %.

#### **APPENDIX A1 TEST SAMPLE PHOTOGRAPHS**

T2010 Host - Conventional Laptop Configuration







#### **APPENDIX A2 TEST SAMPLE PHOTOGRAPHS**

Model: 4965AGN - WLAN Module

Front



Back



#### **APPENDIX A3 TEST SAMPLE PHOTOGRAPHS**








4965AGN inside the Fujitsu LIFEBOOK T SERIES Computer



#### **APPENDIX A4 TEST SETUP PHOTOGRAPHS**

**Tablet Position** 





### **APPENDIX A5 TEST SAMPLE PHOTOGRAPHS**

Edge On Top Position





#### **APPENDIX A6 TEST SAMPLE PHOTOGRAPHS**

Edge On Left Position





#### **APPENDIX A7 TEST SAMPLE PHOTOGRAPHS**

Edge On Right Position





#### APPENDIX B PLOTS OF THE SAR MEASUREMENTS

Plots of the measured SAR distributions inside the phantom are given in this Appendix for all tested configurations. The spatial peak SAR values were assessed with the procedure described in this report.

Table: 2450 MHz DSSS Band SAR Measurement Plot Numbers

Test Position	Plot No.	Ant	Bit rate Mode (Mbps)	Channel Bandwidth (MHz)	Test Channel		
*Tablet	1	В	1	-	06		
*Edge On Top	2	A	1	_	06		
*Edge On Top	3	В	1	-	06		
*Edge On Right	4	Α	1	-	06		
*Edge On Left	5	В	1	-	06		
Edge On Top	6	В	1	-	06		
Edge On Right	7	Α	1	-	06		
Edge On Left	8	В	1	-	06		
Z-Axis graphs for Plots 6 to 8							
Edge On — Top —	9	Α	1	-	01		
	10	Α	1	-	06		
	11	Α	1	-	11		
Z-Axis graphs for Plots 9 to 11							
	<del> </del>						
Edge On Top with Bluetooth On	12	Α	1	-	01		
Z-Axis graph for Plot 12							

Table: 2450 MHz OFDM Band SAR Measurement Plot Numbers

Test Position	Plot No.	Ant	Bit rate Mode (Mbps)	Channel Bandwidth (MHz)	Test Channel
Edge On Right	13	Α	6	-	06
Edge On Left	14	В	6	-	06
Edge On Top	15	Α	6	-	06
Edge On Top	16	В	6	-	06
Z-Axis graphs for Plots 13 to 16					
Edge On Top	17	Α	HT0	20	06
Z-Axis graph for Plot 17					
Edge On Top	18	A + B	HT8	20	01
Z-Axis graph for Plot 18					

**Table: 2450MHz Validation Plot** 

Plot 19	Validation 2450 MHz 29 June 2007	
Plot 20	Validation 2450 MHz 02 June 2007	
Plot 21	Validation 2450 MHz 03 June 2007	
Z-Axis graphs for Plots 19 to 21		


Test Date: 29 June 2007

File Name: Tablet DSSS 2.45 Champlain Antenna B Bluetooth Off Prescan 29-06-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

# Channel 6 Test/Area Scan (141x171x1): Measurement grid: dx=20mm, dy=20mm Maximum value of SAR (interpolated) = 0.013 mW/g



SAR MEASUREMENT PLOT 1


Ambient Temperature Liquid Temperature Humidity 21.9 Degrees Celsius 21.7 Degrees Celsius 50.0 % Test Date: 02 July 2007

File Name: <u>Edge On Top DSSS 2.45 GHz Champlain Antenna A Bluetooth Off Prescan 02-07-07.da4</u> **DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F** 

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma$  = 1.92238 mho/m,  $\epsilon_r$  = 52.9393;  $\rho$  = 1000 kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (61x181x1): Measurement grid: dx=20mm, dy=20mm

Maximum value of SAR (interpolated) = 0.572 mW/g



SAR MEASUREMENT PLOT 2


Ambient Temperature Liquid Temperature Humidity 21.5 Degrees Celsius 21.2 Degrees Celsius 41.0 % Test Date: 02 July 2007

File Name: <u>Edge On Top DSSS 2.45 GHz Champlain Antenna B Bluetooth Off Prescan 02-07-07.da4</u> **DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F** 

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\varepsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

## Channel 6 Test/Area Scan (61x181x1): Measurement grid: dx=20mm, dy=20mm

Maximum value of SAR (interpolated) = 0.437 mW/g



0 dB = 0.532 mW/g


SAR MEASUREMENT PLOT 3

Ambient Temperature Liquid Temperature Humidity 21.5 Degrees Celsius 21.2 Degrees Celsius 41.0 % Test Date: 29 June 2007

File Name: Edge On Right DSSS 2.45 GHz Champlain Antenna A Bluetooth Off Prescan 29-06-07.da4 DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

# **Channel 6 Test/Area Scan (81x201x1):** Measurement grid: dx=15mm, dy=15mm Maximum value of SAR (interpolated) = 0.111 mW/g




SAR MEASUREMENT PLOT 4

Ambient Temperature Liquid Temperature Humidity 21.9 Degrees Celsius 21.7 Degrees Celsius 50.0 % Test Date: 29 June 2007

File Name: <u>Edge On Left DSSS 2.45 GHz Champlain Antenna B Bluetooth Off Prescan 29-06-07.da4</u> **DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F** 

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

# **Channel 6 Test/Area Scan (81x201x1):** Measurement grid: dx=15mm, dy=15mm Maximum value of SAR (interpolated) = 0.024 mW/g



SAR MEASUREMENT PLOT 5

Ambient Temperature Liquid Temperature Humidity 21.9 Degrees Celsius 21.7 Degrees Celsius 50.0 %

File Name: Edge On Top DSSS 2.45 GHz Champlain Antenna B Bluetooth Off 02-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\varepsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442: Probe: ET3DV6 SN1380: ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.651 mW/g

#### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 16.5 V/m; Power Drift = -0.213 dB

Peak SAR (extrapolated) = 1.85 W/kg

SAR(1 g) = 0.666 mW/g; SAR(10 g) = 0.281 mW/gMaximum value of SAR (measured) = 0.752 mW/g



SAR MEASUREMENT PLOT 6

**Ambient Temperature Liquid Temperature** Humidity

Test Date: 29 June 2007

File Name: Edge On Right DSSS 2.45 GHz Champlain Antenna A Bluetooth Off 29-06-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442: Probe: ET3DV6 SN1380: ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.109 mW/g

#### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 4.97 V/m; Power Drift = 0.015 dB

Peak SAR (extrapolated) = 0.262 W/kg

SAR(1 g) = 0.105 mW/g; SAR(10 g) = 0.047 mW/g Maximum value of SAR (measured) = 0.116 mW/g



SAR MEASUREMENT PLOT 7

Ambient Temperature Liquid Temperature Humidity

Test Date: 29 June 2007

File Name: Edge On Left DSSS 2.45 GHz Champlain Antenna B Bluetooth Off 29-06-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz: Frequency; 2437 MHz: Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442: Probe: ET3DV6 SN1380: ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm

Maximum value of SAR (interpolated) = 0.022 mW/g


#### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 1.94 V/m; Power Drift = 0.050 dB

Peak SAR (extrapolated) = 0.045 W/kg


SAR(1 g) = 0.020 mW/g; SAR(10 g) = 0.00814 mW/g

Maximum value of SAR (measured) = 0.025 mW/g



SAR MEASUREMENT PLOT 8

**Ambient Temperature Liquid Temperature** Humidity



File Name: Edge On Top DSSS 2.45 GHz Champlain Antenna A Bluetooth Off 03-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2412 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.96585$  mho/m,  $\varepsilon_r = 53.0275$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

# Channel 1 Test 3/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm Maximum value of SAR (interpolated) = 1.13 mW/g


### Channel 1 Test 3/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm,

dz=5mm

Reference Value = 19.2 V/m; Power Drift = 0.270 dB

Peak SAR (extrapolated) = 3.69 W/kg

SAR(1 g) = 1.31 mW/g; SAR(10 g) = 0.525 mW/g Maximum value of SAR (measured) = 1.50 mW/g



### SAR MEASUREMENT PLOT 9

Ambient Temperature Liquid Temperature Humidity

File Name: Edge On Top DSSS 2.45 GHz Champlain Antenna A Bluetooth Off 02-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\varepsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

#### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 1.23 mW/g

### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 26.7 V/m; Power Drift = -0.151 dB

Peak SAR (extrapolated) = 3.16 W/kg

SAR(1 g) = 1.15 mW/g; SAR(10 g) = 0.481 mW/g Maximum value of SAR (measured) = 1.33 mW/g



SAR MEASUREMENT PLOT 10

Ambient Temperature Liquid Temperature Humidity

File Name: Edge On Top DSSS 2.45 GHz Champlain Antenna A Bluetooth Off 03-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2462 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 2.03951$  mho/m,  $\varepsilon_r = 52.6917$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442: Probe: ET3DV6 SN1380: ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 11 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm

Maximum value of SAR (interpolated) = 1.09 mW/g


#### Channel 11 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm,

dz=5mm

Reference Value = 24.7 V/m; Power Drift = -0.01 dB


Peak SAR (extrapolated) = 3.30 W/kg

SAR(1 g) = 1.14 mW/g; SAR(10 g) = 0.460 mW/g Maximum value of SAR (measured) = 1.32 mW/g



SAR MEASUREMENT PLOT 11

Ambient Temperature Liquid Temperature Humidity



File Name: Edge On Top DSSS 2.45 GHz Champlain Antenna A Bluetooth On 03-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2412 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.96585$  mho/m,  $\varepsilon_r = 53.0275$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

#### Channel 1 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 1.03 mW/g

### Channel 1 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 18.7 V/m; Power Drift = 0.098 dB


Peak SAR (extrapolated) = 3.40 W/kg

SAR(1 g) = 1.21 mW/g; SAR(10 g) = 0.483 mW/g Maximum value of SAR (measured) = 1.39 mW/g



SAR MEASUREMENT PLOT 12

Ambient Temperature Liquid Temperature Humidity



File Name: Edge On Right OFDM 2.45 GHz Champlain Antenna A Bluetooth Off 02-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC:

0013E8175E6F

- \* Communication System: OFDM 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\epsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

#### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.078 mW/g

### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 4.20 V/m; Power Drift = -0.135 dB

Peak SAR (extrapolated) = 0.182 W/kg

SAR(1 g) = 0.075 mW/g; SAR(10 g) = 0.035 mW/g Maximum value of SAR (measured) = 0.083 mW/g



SAR MEASUREMENT PLOT 13

Ambient Temperature Liquid Temperature Humidity

Test Date: 29 June 2007

File Name: Edge On Left OFDM 2.45 GHz Champlain Antenna B Bluetooth Off 29-06-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: OFDM 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.90551$  mho/m,  $\varepsilon_r = 53.0696$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.027 mW/g

### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 1.60 V/m; Power Drift = -0.096 dB

Peak SAR (extrapolated) = 0.049 W/kg

SAR(1 g) = 0.024 mW/g; SAR(10 g) = 0.010 mW/g Maximum value of SAR (measured) = 0.029 mW/g



\_\_\_\_

SAR MEASUREMENT PLOT 14

Ambient Temperature Liquid Temperature Humidity

File Name: Edge On Top OFDM 2.45 GHz Champlain Antenna A Bluetooth Off 02-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: OFDM 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\epsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.858 mW/g

### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 21.5 V/m; Power Drift = 0.138 dB

Peak SAR (extrapolated) = 2.16 W/kg

SAR(1 g) = 0.805 mW/g; SAR(10 g) = 0.339 mW/g Maximum value of SAR (measured) = 0.928 mW/g



SAR MEASUREMENT PLOT 15

Ambient Temperature Liquid Temperature Humidity

File Name: Edge On Top OFDM 2.45 GHz Champlain Antenna B Bluetooth Off 02-07-07.da4

DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: OFDM 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.92238$  mho/m,  $\varepsilon_r = 52.9393$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 0.516 mW/g

#### Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 14.3 V/m; Power Drift = -0.292 dB


Peak SAR (extrapolated) = 1.42 W/kg


SAR(1 g) = 0.533 mW/g; SAR(10 g) = 0.224 mW/g Maximum value of SAR (measured) = 0.604 mW/g





SAR MEASUREMENT PLOT 16

Ambient Temperature Liquid Temperature Humidity









File Name: Edge On Top (HT0 Mbps 20 MHz) 2.45 GHz Champlain Antenna A Bluetooth Off 03-07-07.da4 DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2437 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 2.00134$  mho/m,  $\varepsilon_r = 52.8474$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 6 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm

Maximum value of SAR (interpolated) = 1.06 mW/g


Channel 6 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 23.1 V/m; Power Drift = -0.241 dB

Peak SAR (extrapolated) = 2.50 W/kg

SAR(1 g) = 0.871 mW/g; SAR(10 g) = 0.356 mW/g


Maximum value of SAR (measured) = 1.00 mW/g



0 dB = 1.00 mW/a

SAR MEASUREMENT PLOT 17

**Ambient Temperature Liquid Temperature** Humidity



File Name: Edge On Top (HT8 Mbps 20 MHz) 2.45 GHz Champlain Antenna A Bluetooth Off 03-07-07.da4 DUT: Fujitsu Tablet Champlain with Kedron 11abgn and Bluetooth; Type: 4965ABG; Serial: MAC: 0013E8175E6F

- \* Communication System: DSSS 2450 MHz; Frequency: 2412 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.96585$  mho/m,  $\varepsilon_r = 53.0275$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442: Probe: ET3DV6 SN1380: ConvF(4.21, 4.21, 4.21)
- Phantom: Flat Phantom 10.1; Serial: P 10.1; Phantom section: Flat 2.2 Section

### Channel 1 Test/Area Scan (81x101x1): Measurement grid: dx=15mm, dy=15mm

Maximum value of SAR (interpolated) = 0.329 mW/g


#### Channel 1 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 13.2 V/m; Power Drift = -0.351 dB

Peak SAR (extrapolated) = 0.981 W/kg


SAR(1 g) = 0.358 mW/g; SAR(10 g) = 0.145 mW/g

Maximum value of SAR (measured) = 0.414 mW/g



SAR MEASUREMENT PLOT 18

**Ambient Temperature Liquid Temperature** Humidity



Test Date: 29 June 2007

File Name: Validation 2450 MHz (DAE442 Probe1380) 29-06-07.da4

DUT: Dipole 2450 MHz; Type: DV2450V2; Serial: 724

- \* Communication System: CW 2450 MHz; Frequency: 2450 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.76538$  mho/m,  $\varepsilon_r = 40.5227$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.32, 4.32, 4.32)
- Phantom: SAM 22; Serial: 1260; Phantom section: Flat Section

#### Channel 1 Test/Area Scan (51x51x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 18.5 mW/g

#### Channel 1 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 95.9 V/m; Power Drift = -0.01 dB

Peak SAR (extrapolated) = 30.2 W/kg

SAR(1 g) = 13.6 mW/g; SAR(10 g) = 6.37 mW/g Maximum value of SAR (measured) = 15.3 mW/g



SAR MEASUREMENT PLOT 19

Ambient Temperature Liquid Temperature Humidity

File Name: Validation 2450 MHz (DAE442 Probe1380) 02-07-07.da4

DUT: Dipole 2450 MHz; Type: DV2450V2; Serial: 724

- \* Communication System: CW 2450 MHz; Frequency: 2450 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.782$  mho/m,  $\varepsilon_r = 40.7753$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.32, 4.32, 4.32)
- Phantom: SAM 22; Serial: 1260; Phantom section: Flat Section

#### Channel 1 Test/Area Scan (51x51x1): Measurement grid: dx=15mm, dy=15mm


Maximum value of SAR (interpolated) = 18.4 mW/g

#### Channel 1 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 94.8 V/m; Power Drift = -0.061 dB

Peak SAR (extrapolated) = 29.8 W/kg

SAR(1 g) = 13.6 mW/g; SAR(10 g) = 6.37 mW/gMaximum value of SAR (measured) = 15.3 mW/g



0 dB = 15.3 mW/g

SAR MEASUREMENT PLOT 20

**Ambient Temperature Liquid Temperature** Humidity

File Name: Validation 2450 MHz (DAE442 Probe1380) 03-07-07.da4

DUT: Dipole 2450 MHz; Type: DV2450V2; Serial: 724

- \* Communication System: CW 2450 MHz; Frequency: 2450 MHz; Duty Cycle: 1:1
- \* Medium parameters used:  $\sigma = 1.83646$  mho/m,  $\varepsilon_r = 40.3992$ ;  $\rho = 1000$  kg/m<sup>3</sup>
- Electronics: DAE3 Sn442; Probe: ET3DV6 SN1380; ConvF(4.32, 4.32, 4.32)
- Phantom: SAM 22; Serial: 1260; Phantom section: Flat Section

#### Channel 1 Test/Area Scan (51x51x1): Measurement grid: dx=15mm, dy=15mm

Maximum value of SAR (interpolated) = 18.4 mW/g


#### Channel 1 Test/Zoom Scan (7x7x7)/Cube 0: Measurement grid: dx=5mm, dy=5mm, dz=5mm

Reference Value = 93.2 V/m; Power Drift = 0.050 dB

Peak SAR (extrapolated) = 30.8 W/kg


SAR(1 g) = 13.8 mW/g; SAR(10 g) = 6.4 mW/g

Maximum value of SAR (measured) = 15.5 mW/g



SAR MEASUREMENT PLOT 21

**Ambient Temperature Liquid Temperature** Humidity



Calibration Laboratory of Schmid & Partner Engineering AG Zeughausstrasse 43, 8004 Zurich, Switzerland





S Schweizerischer Kalibrierdiens
C Service suisse d'étalonnage
Servizio svizzero di taratura
S Swiss Calibration Service

Accredited by the Swiss Federal Office of Metrology and Accreditation The Swiss Accreditation Service is one of the signatories to the EA Multilateral Agreement for the recognition of calibration certificates Accreditation No.: SCS 108

Client EMC Technologies

FCC ID: EJE-WB0052 IC: 337J-WB0052

Certificate No: ET3-1380 Dec06

#### CALIBRATION CERTIFICATE Object ET3DV6 - SN:1380 QA CAL-01.v5 and QA CAL-12.v4 Calibration procedure(s) Calibration procedure for dosimetric E-field probes Calibration date: December 12, 2006 Condition of the calibrated item In Tolerance This calibration certificate documents the traceability to national standards, which realize the physical units of measurements (SI), The measurements and the uncertainties with confidence probability are given on the following pages and are part of the certificate. All calibrations have been conducted in the closed laboratory facility: environment temperature (22 ± 3)°C and humidity < 70%. Calibration Equipment used (M&TE critical for calibration) Primary Standards ID# Cal Date (Calibrated by, Certificate No.) Scheduled Calibration Power meter E4419B GB41293874 5-Apr-06 (METAS, No. 251-00557) Apr-07 Power sensor E4412A MY41495277 5-Apr-06 (METAS, No. 251-00557) Apr-07 Power sensor F4412A MY41498087 5-Apr-06 (METAS, No. 251-00557) Apr-07 Reference 3 dB Attenuator SN: S5054 (3c) 10-Aug-06 (METAS, No. 217-00592) Aug-07 Reference 20 dB Attenuator SN: S5086 (20b) 4-Apr-06 (METAS, No. 251-00558) Apr-07 Reference 30 dB Attenuator SN: S5129 (30b) 10-Aug-06 (METAS, No. 217-00593) Aug-07 Reference Probe ES3DV2 SN: 3013 2-Jan-06 (SPEAG, No. ES3-3013\_Jan06) Jan-07 DAE4 SN: 654 21-Jun-06 (SPEAG, No. DAE4-654\_Jun06) Jun-07 Secondary Standards ID# Check Date (in house) Scheduled Check RF generator HP 8648C US3642U01700 4-Aug-99 (SPEAG, in house check Nov-05) In house check: Nov-07 Network Analyzer HP 8753E US37390585 18-Oct-01 (SPEAG, in house check Oct-06) In house check: Oct-07 Name Function Signature Calibrated by: Katja Pokovic Technical Manager Approved by: Niels Kuster Quality Manager Issued: December 13, 2006 This calibration certificate shall not be reproduced except in full without written approval of the laboratory.

Certificate No: ET3-1380\_Dec06

Page 1 of 9

FCC ID: <u>EJE-WB0052</u> IC: <u>337J-WB0052</u>

ET3DV6 SN:1380

December 12, 2006

#### DASY - Parameters of Probe: ET3DV6 SN:1380

Sensitivity in Fr	Sensitivity in Free Space <sup>A</sup>			ompression <sup>B</sup>
NormX	<b>1.79</b> ± 10.1%	$\mu V/(V/m)^2$	DCP X	<b>91</b> mV
NormY	<b>1.62</b> ± 10.1%	$\mu V/(V/m)^2$	DCP Y	<b>90</b> mV
NormZ	1.75 ± 10.1%	$\mu V/(V/m)^2$	DCP Z	89 mV

Sensitivity in Tissue Simulating Liquid (Conversion Factors)

Please see Page 8.

### **Boundary Effect**

TSL

900 MHz

Typical SAR gradient: 5 % per mm

Sensor Center to Phantom Surface Distance		3.7 mm	4.7 mm
SAR <sub>be</sub> [%]	Without Correction Algorithm	5.5	2.2
SAR <sub>be</sub> [%]	With Correction Algorithm	0.0	0.0

TSL

1810 MHz

Typical SAR gradient: 10 % per mm

Sensor Center to Phantom Surface Distance		3.7 mm	4.7 mm
SAR <sub>be</sub> [%]	Without Correction Algorithm	13.3	8.5
SAR <sub>be</sub> [%]	With Correction Algorithm	0.4	0.3

#### Sensor Offset

Probe Tip to Sensor Center

2.7 mm

The reported uncertainty of measurement is stated as the standard uncertainty of measurement multiplied by the coverage factor k=2, which for a normal distribution corresponds to a coverage probability of approximately 95%.

Certificate No: ET3-1380\_Dec06

Page 4 of 9

<sup>&</sup>lt;sup>A</sup> The uncertainties of NormX,Y,Z do not affect the E<sup>2</sup>-field uncertainty inside TSL (see Page 8).

<sup>&</sup>lt;sup>8</sup> Numerical linearization parameter: uncertainty not required.


FCC ID:  $\underline{\text{EJE-WB0052}}$  IC:  $\underline{337\text{J-WB0052}}$ 

ET3DV6 SN:1380

December 12, 200

## Frequency Response of E-Field

(TEM-Cell:ifi110 EXX, Waveguide: R22)



Uncertainty of Frequency Response of E-field: ± 6.3% (k=2)


Certificate No: ET3-1380\_Dec06


Page 5 of 9


FCC ID: <u>EJE-WB0052</u> IC: <u>337J-WB0052</u>

December 12, 2006

## Receiving Pattern ( $\phi$ ), $\vartheta = 0^{\circ}$







Uncertainty of Axial Isotropy Assessment: ± 0.5% (k=2)


Certificate No: ET3-1380\_Dec06

Page 6 of 9

December 12, 2006

## Dynamic Range f(SAR<sub>head</sub>)

(Waveguide R22, f = 1800 MHz)




Uncertainty of Linearity Assessment: ± 0.6% (k=2)


Certificate No: ET3-1380\_Dec06

Page 7 of 9

December 12, 2006

#### **Conversion Factor Assessment**





f [MHz]	Validity [MHz] <sup>C</sup>	TSL	Permittivity	Conductivity	Alpha	Depth	ConvF	Uncertainty
450	± 50 / ± 100	Head	43.5 ± 5%	0.87 ± 5%	0.39	1.95	7.04	± 13.3% (k=2)
900	± 50 / ± 100	Head	41.5 ± 5%	$0.97 \pm 5\%$	0.41	2.29	6.21	± 11.0% (k=2)
1640	± 50 / ± 100	Head	40.3 ± 5%	1.29 ± 5%	0.54	2.57	5.39	± 11.0% (k=2)
1810	± 50 / ± 100	Head	40.0 ± 5%	1.40 ± 5%	0.61	2.42	5.19	± 11.0% (k=2)
2450	± 50 / ± 100	Head	39.2 ± 5%	1.80 ± 5%	0.85	1.68	4.32	± 11.8% (k=2)
450	± 50 / ± 100	Body	56.7 ± 5%	0.94 ± 5%	0.32	2.01	7.57	± 13.3% (k=2)
900	± 50 / ± 100	Body	55.0 ± 5%	1.05 ± 5%	0.34	2.76	6.07	± 11.0% (k=2)
1810	± 50 / ± 100	Body	53.3 ± 5%	1.52 ± 5%	0.65	2.60	4.52	± 11.0% (k=2)
2450	± 50 / ± 100	Body	52.7 ± 5%	1.95 ± 5%	0.80	1.72	4.21	± 11.8% (k=2)

Certificate No: ET3-1380\_Dec06


Page 8 of 9

 $<sup>^{\</sup>rm C}$  The validity of  $\pm$  100 MHz only applies for DASY v4.4 and higher (see Page 2). The uncertainty is the RSS of the ConvF uncertainty at calibration frequency and the uncertainty for the indicated frequency band.

December 12, 2006

### **Deviation from Isotropy in HSL**

Error  $(\phi, \vartheta)$ , f = 900 MHz



Uncertainty of Spherical Isotropy Assessment: ± 2.6% (k=2)

Certificate No: ET3-1380\_Dec06

Page 9 of 9

FCC ID: <u>EJE-WB0052</u> IC: <u>337J-WB0052</u>

Calibration Laboratory of Schmid & Partner Engineering AG Zeughausstrasse 43, 8004 Zurich, Switzerland





Schweizerischer Kalibrierdienst Service suisse d'étalonnage C Servizio svizzero di taratura Swiss Calibration Service

Accredited by the Swiss Federal Office of Metrology and Accreditation The Swiss Accreditation Service is one of the signatories to the EA Multilateral Agreement for the recognition of calibration certificates

Accreditation No.: SCS 108

S

S

Client

**EMC Technologies** 

Certificate No: D2450V2-724\_Dec06

Object	D2450V2 - SN: 724				
Calibration procedure(s)	QA CAL-05.v6				
	Calibration proc	edure for dipole validation kits			
4					
Calibration date:	December 13, 2	2006			
Condition of the calibrated item	In Tolerance		337.00775232770970107		
ne measurements and the unc	ertainties with confidence p	tional standards, which realize the physical units o probability are given on the following pages and ar	re part of the certificate.		
calibrations have been condu	ucted in the closed laborate	ov facility: environment temperature (22 + 2390			
Calibration Equipment used (M8		by facility: environment temperature $(22\pm3)^{\circ}$ C an	d humidity < 70%.		
alibration Equipment used (M8					
alibration Equipment used (M8 rimary Standards ower meter EPM-442A	TE critical for calibration)	Cal Date (Calibrated by, Certificate No.)	Scheduled Calibration		
alibration Equipment used (M8 imary Standards ower meter EPM-442A ower sensor HP 8481A	TE critical for calibration)	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608)	Scheduled Calibration Oct-07		
imary Standards ower meter EPM-442A ower sensor HP 8481A oference 20 dB Attenuator	ID # GB37480704	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608)	Scheduled Calibration Oct-07 Oct-07		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A aference 20 dB Attenuator aference 10 dB Attenuator	ID # GB37480704 US37292783	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608)	Scheduled Calibration Oct-07 Oct-07 Aug-07		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A oference 20 dB Attenuator oference 10 dB Attenuator oference Probe ES3DV2	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591)	Scheduled Calibration Oct-07 Oct-07		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A eference 20 dB Attenuator eference 10 dB Attenuator eference Probe ES3DV2	ID # GB37480704 US37292783 SN: 5086 (20g) SN: 5047.2 (10r)	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No 217-00591)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07		
alibration Equipment used (M8 simary Standards ower meter EPM-442A ower sensor HP 8481A ofference 20 dB Attenuator eference 10 dB Attenuator eference Probe ES3DV2	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A afference 20 dB Attenuator afference 10 dB Attenuator afference Probe ES3DV2 AE4	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05) Check Date (in house)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check		
rimary Standards ower meter EPM-442A ower sensor HP 8481A eference 20 dB Attenuator eference Probe ES3DV2 AE4 econdary Standards ower sensor HP 8481A	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #  MY41092317	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No. 217-00591) 10-Aug-06 (METAS, No. 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05) Check Date (in house)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check In house check: Oct-07		
	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00608) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05) Check Date (in house)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A eference 20 dB Attenuator eference 10 dB Attenuator eference Probe ES3DV2 AE4 econdary Standards ower sensor HP 8481A E generator Agilent E4421B	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #  MY41092317  MY41000675	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00508) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05)  Check Date (in house)  18-Oct-02 (SPEAG, in house check Oct-05) 11-May-05 (SPEAG, in house check Nov-05) 18-Oct-01 (SPEAG, in house check Oct-06)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check In house check: Oct-07 In house check: Oct-07		
alibration Equipment used (M8 rimary Standards over meter EPM-442A over sensor HP 8481A afference 20 dB Attenuator afference 10 dB Attenuator afference Probe ES3DV2 AE4 condary Standards wer sensor HP 8481A igenerator Agilent E4421B twork Analyzer HP 8753E	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #  MY41092317  MY41000675  US37390585 S4206	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00508) 10-Aug-06 (METAS, No. 217-00591) 10-Aug-06 (METAS, No. 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05)  Check Date (in house)  18-Oct-02 (SPEAG, in house check Oct-05) 11-May-05 (SPEAG, in house check Nov-05) 18-Oct-01 (SPEAG, in house check Oct-06)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check In house check: Oct-07 In house check: Nov-07		
alibration Equipment used (M8 rimary Standards ower meter EPM-442A ower sensor HP 8481A eference 20 dB Attenuator eference 10 dB Attenuator eference Probe ES3DV2 AE4 econdary Standards ower sensor HP 8481A E generator Agilent E4421B	ID #  GB37480704  US37292783  SN: 5086 (20g)  SN: 5047.2 (10r)  SN 3025  SN 601  ID #  MY41092317  MY4100675  US37390585 S4206  Name	Cal Date (Calibrated by, Certificate No.) 03-Oct-06 (METAS, No. 217-00608) 03-Oct-06 (METAS, No. 217-00508) 10-Aug-06 (METAS, No 217-00591) 10-Aug-06 (METAS, No 217-00591) 19-Oct-06 (SPEAG, No. ES3-3025_Oct06) 15-Dec-05 (SPEAG, No. DAE4-601_Dec05)  Check Date (in house)  18-Oct-02 (SPEAG, in house check Oct-05) 11-May-05 (SPEAG, in house check Nov-05) 18-Oct-01 (SPEAG, in house check Oct-06)	Scheduled Calibration Oct-07 Oct-07 Aug-07 Aug-07 Oct-07 Dec-06 Scheduled Check In house check: Oct-07 In house check: Oct-07		

Certificate No: D2450V2-724\_Dec06

Page 1 of 6

#### FCC ID: <u>EJE-WB0052</u> IC: <u>337J-WB0052</u>

Measurement Conditions

DASY system configuration, as far as not given on page 1.

DASY Version	DASY4	V4.7
Extrapolation	Advanced Extrapolation	
Phantom	Modular Flat Phantom V5.0	
Distance Dipole Center - TSL	10 mm	with Spacer
Zoom Scan Resolution	dx, $dy$ , $dz = 5 mm$	
Frequency	2450 MHz ± 1 MHz	

#### Head TSL parameters

The following parameters and calculations were applied.

	Temperature	Permittivity	Conductivity
Nominal Head TSL parameters	22.0 °C	39.2	1.80 mho/m
Measured Head TSL parameters	(22.0 ± 0.2) °C	37.7 ± 6 %	1.77 mho/m ± 6 %
Head TSL temperature during test	(21.8 ± 0.2) °C	- <del> </del>	

#### SAR result with Head TSL

SAR averaged over 1 cm <sup>3</sup> (1 g) of Head TSL	condition	
SAR measured	250 mW input power	13.5 mW / g
SAR normalized	normalized to 1W	54.0 mW / g
SAR for nominal Head TSL parameters 1	normalized to 1W	53.3 mW / g ± 17.0 % (k=2)

SAR averaged over 10 cm3 (10 g) of Head TSL	condition	***************************************
SAR measured	250 mW input power	6.24 mW / g
SAR normalized	normalized to 1W	25.0 mW / g
SAR for nominal Head TSL parameters <sup>1</sup>	normalized to 1W	24.7 mW / g ± 16.5 % (k=2)

Certificate No: D2450V2-724\_Dec06

Page 3 of 6

Correction to nominal TSL parameters according to d), chapter "SAR Sensitivities"

#### DASY4 Validation Report for Head TSL

Date/Time: 13.12.2006 12:39:25

Test Laboratory: SPEAG, Zurich, Switzerland

DUT: Dipole 2450 MHz; Type: D2450V2; Serial: D2450V2 - SN724

Communication System: CW-2450; Frequency: 2450 MHz; Duty Cycle: 1:1

Medium: HSL U10 BB\_060425;

Medium parameters used: f = 2450 MHz;  $\sigma$  = 1.77 mho/m;  $\epsilon_r$  = 37.7;  $\rho$  = 1000 kg/m<sup>3</sup>

Phantom section: Flat Section

Measurement Standard: DASY4 (High Precision Assessment)


#### DASY4 Configuration:

- Probe: ES3DV2 SN3025 (HF); ConvF(4.5, 4.5, 4.5); Calibrated: 19.10.2006
- Sensor-Surface: 4mm (Mechanical Surface Detection)
- Electronics: DAE4 Sn601; Calibrated: 15.12.2005
- Phantom: Flat Phantom 5.0 (front); Type: QD000P50AA;;
- Measurement SW: DASY4, V4.7 Build 44; Postprocessing SW: SEMCAD, V1.8 Build 171

### Pin = 250 mW; d = 10 mm/Zoom Scan (7x7x7)/Cube 0:

Measurement grid: dx=5mm, dy=5mm, dz=5mm Reference Value = 89.2 V/m; Power Drift = 0.053 dB Peak SAR (extrapolated) = 28.4 W/kg

SAR(1 g) = 13.5 mW/g; SAR(10 g) = 6.24 mW/g Maximum value of SAR (measured) = 15.0 mW/g



0 dB = 15.0 mW/g

Certificate No: D2450V2-724\_Dec06

Page 5 of 6