

September 30, 2004

DASY - Parameters of Probe: ET3DV6 SN:1788

Sensitivity in Free Space^A

Diode Compression^B

NormX	1.68 ± 9.9%	$\mu V/(V/m)^2$	DCP X	94 mV
NormY	1.70 ± 9.9%	$\mu V/(V/m)^2$	DCP Y	94 mV
NormZ	1.74 ± 9.9%	μ V/(V/m) ²	DCP Z	94 mV

Sensitivity in Tissue Simulating Liquid (Conversion Factors)

Please see Page 8.

Boundary Effect

TSL

900 MHz Typical SAR gradient: 5 % per mm

Sensor Cente	er to Phantom Surface Distance	3.7 mm	4.7 mm
SAR _{be} [%]	Without Correction Algorithm	8.1	4.4
SAR _{be} [%]	With Correction Algorithm	0.7	0.1

TSL 1810 MHz Typical SAR gradient: 10 % per mm

Sensor Cente	r to Phantom Surface Distance	3.7 mm	4.7 mm
SAR _{be} [%]	Without Correction Algorithm	12.0	8.2
SAR _{be} [%]	With Correction Algorithm	0.9	0.1

Sensor Offset

Probe Tip to Sensor Center 2.7 mm

The reported uncertainty of measurement is stated as the standard uncertainty of measurement multiplied by the coverage factor k=2, which for a normal distribution corresponds to a coverage probability of approximately 95%.

^A The uncertainties of NormX,Y,Z do not affect the E²-field uncertainty inside TSL (see Page 8).

^B Numerical linearization parameter: uncertainty not required.

Certificate No: ET3-1788_Sep04


Page 4 of 9



September 30, 2004

Frequency Response of E-Field

(TEM-Cell:ifi110 EXX, Waveguide: R22)




Uncertainty of Frequency Response of E-field: ± 6.3% (k=2)

Certificate No: ET3-1788_Sep04


Page 5 of 9



September 30, 2004



Receiving Pattern (ϕ), $\vartheta = 0^{\circ}$




Uncertainty of Axial Isotropy Assessment: ± 0.5% (k=2)

Certificate No: ET3-1788_Sep04

Page 6 of 9



September 30, 2004




Uncertainty of Linearity Assessment: ± 0.6% (k=2)

Certificate No: ET3-1788_Sep04

Page 7 of 9



September 30, 2004



Conversion Factor Assessment

f [MHz]	Validity [MHz] ^C	TSL	Permittivity	Conductivity	Alpha	Depth	ConvF Uncertainty
835	± 50 / ± 100	Head	41.5 ± 5%	0.90 ± 5%	1.12	1.42	6.74 ± 11.0% (k=2)
900	± 50 / ± 100	Head	41.5 ± 5%	0.97 ± 5%	1.07	1.44	6.63 ± 11.0% (k=2)
1750	± 50 / ± 100	Head	40.0 ± 5%	1.40 ± 5%	0.56	2.31	5.37 ± 11.0% (k=2)
1900	± 50 / ± 100	Head	40.0 ± 5%	1.40 ± 5%	0.55	2.42	5.16 ± 11.0% (k=2)
2000	± 50 / ± 100	Head	40.0 ± 5%	1.40 ± 5%	0.54	2.59	4.88 ± 11.0% (k=2)
2450	± 50 / ± 100	Head	39.2 ± 5%	1.80 ± 5%	0.65	2.22	4.56 ± 11.8% (k=2)
835	± 50 / ± 100	Body	55.2 ± 5%	0.97 ± 5%	1.04	1.52	6.53 ± 11.0% (k=2)
900	± 50 / ± 100	Body	55.0 ± 5%	1.05 ± 5%	0.99	1.56	6.17 ± 11.0% (k=2)
1750	± 50 / ± 100	Body	53.3 ± 5%	1.52 ± 5%	0.53	2.74	4.73 ± 11.0% (k=2)
1900	± 50 / ± 100	Body	53.3 ± 5%	1.52 ± 5%	0.55	2.82	4.56 ± 11.0% (k=2)
2000	± 50 / ± 100	Body	53.3 ± 5%	1.52 ± 5%	0.54	2.98	4.43 ± 11.0% (k=2)
2450	± 50 / ± 100	Body	52.7 ± 5%	1.95 ± 5%	0.72	2.00	4.26 ± 11.8% (k=2)

^C The validity of ± 100 MHz only applies for DASY 4.3 B17 and higher (see Page 2). The uncertainty is the RSS of the ConvF uncertainty at calibration frequency and the uncertainty for the indicated frequency band.

Certificate No: ET3-1788_Sep04

Page 8 of 9






September 30, 2004

Deviation from Isotropy in HSL

Error (\, \,), f = 900 MHz



Uncertainty of Spherical Isotropy Assessment: ± 2.6% (k=2)

Certificate No: ET3-1788 Sep04

Page 9 of 9



Test Report No : FA521801-1-2-01

Engineering AG ughausstrasse 43, 8004 Zurich,	Switzerland	CRUBRATO S	Servizio svizzero di taratura
credited by the Swiss Federal Off e Swiss Accreditation Service i Itiliateral Agreement for the rec	s one of the signatories	to the EA	n No.: SCS 108
ent Sporton (Auden)			lo: DAE3-577_Nov04
ALIBRATION CI	ERTIFICATE		
bject	DAE3 - SD 000 D	03 AA - SN: 577	
alibration procedure(s)	QA CAL-06.v10 Calibration proceed	dure for the data acquisition uni	t (DAE)
alibration date:	November 17, 200	04	
ondition of the calibrated item	In Tolerance		
ne measurements and the uncerta	ainties with confidence pro	anal standards, which realize the physical u obability are given on the following pages a	and are part of the certificate.
e measurements and the uncerta I calibrations have been conducte	ainties with confidence pro		and are part of the certificate.
he measurements and the uncerta I calibrations have been conducte alibration Equipment used (M&TE	ainties with confidence pro	obability are given on the following pages a	and are part of the certificate.
he measurements and the uncerta Il calibrations have been conducte alibration Equipment used (M&TE rimary Standards	ainties with confidence produce of the closed laboratory oritical for calibration)	obability are given on the following pages a facility: environment temperature (22 ± 3)	ind are part of the certificate. °C and humidity < 70%.
he measurements and the uncerta Il calibrations have been conducte alibration Equipment used (M&TE rimary Standards uke Process Calibrator Type 702	inties with confidence produce of the closed laboratory ortical for calibration)	obability are given on the following pages a facility: environment temperature (22 ± 3) Cal Date (Calibrated by, Certificate No.)	ind are part of the certificate. °C and humidity < 70%. Scheduled Calibration
te measurements and the uncerta I calibrations have been conducte alibration Equipment used (M&TE imary Standards uke Process Calibrator Type 702 acondary Standards	inties with confidence provide the closed laboratory ortical for calibration)	Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintrel, No.E-040073)	ind are part of the certificate. *C and humidity < 70%. Scheduled Calibration Sep-05
he measurements and the uncerta Il calibrations have been conducte alibration Equipment used (M&TE rimary Standards uke Process Calibrator Type 702 econdary Standards	inties with confidence provide the closed laboratory ortical for calibration)	bability are given on the following pages a facility: environment temperature (22 ± 3) Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintral, No.E-040073) Check Date (in house)	ind are part of the certificate. *C and humidity < 70%. Scheduled Calibration Sep-05 Scheduled Check
te measurements and the uncerta I calibrations have been conducte alibration Equipment used (M&TE imary Standards uke Process Calibrator Type 702 acondary Standards	inties with confidence provide the closed laboratory ortical for calibration)	bability are given on the following pages a facility: environment temperature (22 ± 3) Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintral, No.E-040073) Check Date (in house)	ind are part of the certificate. *C and humidity < 70%. Scheduled Calibration Sep-05 Scheduled Check
te measurements and the uncerta I calibrations have been conducte alibration Equipment used (M&TE imary Standards uke Process Calibrator Type 702 acondary Standards alibrator Box V1.1	inties with confidence production of the closed laboratory ortical for calibration) ID # SN: 6295803 ID # SE UMS 006 AB 1002	Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintrel, No.E-040073) Check Date (in house) 16-Jul-04 (SPEAG, in house check)	ind are part of the certificate. *C and humidity < 70%. <u>Scheduled Calibration</u> Sep-05 <u>Scheduled Check</u> In house check Jul-05
he measurements and the uncerta Il calibrations have been conducte alibration Equipment used (M&TE rimary Standards uke Process Calibrator Type 702 acondary Standards alibrator Box V1.1	inties with confidence provide the closed laboratory ortical for calibration) ID # SN: 6295803 ID # SE UMS 006 AB 1002 Name	Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintrel, No.E-040073) Check Date (in house) 16-Jul-04 (SPEAG, in house check)	ind are part of the certificate. *C and humidity < 70%. <u>Scheduled Calibration</u> Sep-05 <u>Scheduled Check</u> In house check Jul-05
he measurements and the uncerta	Anne Eric Hainfeld	Cal Date (Calibrated by, Certificate No.) 7-Sep-04 (Sintrel, No.E-040073) Check Date (in house) 16-Jul-04 (SPEAG, in house check) Function Technician	Ind are part of the certificate. C and humidity < 70%. Scheduled Calibration Sep-05 Scheduled Check In house check Jul-05 Signature



Calibration Laboratory of Schmid & Partner Engineering AG Zeughausstrasse 43, 8004 Zurich, Switzerland



S

С

s

Schweizerischer Kalibrierdienst Service suisse d'étalonnage Servizio svizzero di taratura Swiss Calibration Service

Accreditation No.: SCS 108

Accredited by the Swiss Federal Office of Metrology and Accreditation The Swiss Accreditation Service is one of the signatories to the EA Multilateral Agreement for the recognition of calibration certificates

Glossary

DAE digital acquisition electronics Connector angle information used in DASY system to align probe sensor X to the robot coordinate system.

Methods Applied and Interpretation of Parameters

- DC Voltage Measurement: Calibration Factor assessed for use in DASY system by comparison with a calibrated instrument traceable to national standards. The figure given corresponds to the full scale range of the voltmeter in the respective range.
- Connector angle: The angle of the connector is assessed measuring the angle mechanically by a tool inserted. Uncertainty is not required.
- The following parameters contain technical information as a result from the performance test and require no uncertainty.
- DC Voltage Measurement Linearity: Verification of the Linearity at +10% and -10% of the nominal calibration voltage. Influence of offset voltage is included in this measurement.
- Common mode sensitivity: Influence of a positive or negative common mode voltage on the differential measurement.
- Channel separation: Influence of a voltage on the neighbor channels not subject to an input voltage.
- AD Converter Values with inputs shorted: Values on the internal AD converter corresponding to zero input voltage
- Input Offset Measurement: Output voltage and statistical results over a large number of zero voltage measurements.
- Input Offset Current: Typical value for information; Maximum channel input offset current, not considering the input resistance.
- Input resistance: DAE input resistance at the connector, during internal auto-zeroing and during measurement.
- Low Battery Alarm Voltage: Typical value for information. Below this voltage, a battery alarm signal is generated.
- Power consumption: Typical value for information. Supply currents in various operating modes.

Certificate No: DAE3-577_Nov04

Page 2 of 5



DC Voltage Measurement

High Range:	1LSB =	6.1µV,	full range =	-100+300 mV
Low Range:	1LSB =	61nV,	full range =	-1+3mV
DASY measurement	parameters: Au	to Zero Time: 3 s	sec; Measuring	time: 3 sec

and the second se	and the second se	-		

Calibration Factors	X	Y	Z
High Range	404.437 ± 0.1% (k=2)	$403.891 \pm 0.1\%$ (k=2)	$404.359 \pm 0.1\%$ (k=2)
Low Range	3.94121 ± 0.7% (k=2)	3.89867 ± 0.7% (k=2)	3.95408 ± 0.7% (k=2)

Connector Angle

Connector Angle to be used in DASY system	127 ° ± 1 °
---	-------------

Certificate No: DAE3-577_Nov04

Page 3 of 5



Appendix

1. DC Voltage Linearity

High Range		Input (µV)	Reading (µV)	Error (%)
Channel X	+ Input	200000	200000.6	0.00
Channel X	+ Input	20000	20001.77	0.01
Channel X	- Input	20000	-19991.81	-0.04
Channel Y	+ Input	200000	199999.7	0.00
Channel Y	+ Input	20000	19999.20	0.00
Channel Y	- Input	20000	-19994.82	-0.03
Channel Z	+ Input	200000	200000.2	0.00
Channel Z	+ Input	20000	19996.22	-0.02
Channel Z	- Input	20000	-19996.74	-0.02

Low Range	Input (µV)	Reading (µV)	Error (%)
Channel X + Input	2000	2000	0.00
Channel X + Input	200	200.05	0.03
Channel X - Input	200	-200.88	0.44
Channel Y + Input	2000	1999.9	0.00
Channel Y + Input	200	199.73	-0.13
Channel Y - Input	200	-200.53	0.27
Channel Z + Input	2000	2000.1	0.00
Channel Z + Input	200	199.25	-0.38
Channel Z - Input	200	-201.42	0.71

2. Common mode sensitivity

DASY measurement parameters: Auto Zero Time: 3 sec; Measuring time: 3 sec

	Common mode Input Voltage (mV)	High Range Average Reading (μV)	Low Range Average Reading (µV)
Channel X	200	13.15	12.30
	- 200	-12.61	-12.86
Channel Y	200	-7.43	-7.53
	- 200	6.30	6.52
Channel Z	200	-0.16	0.31
	- 200	-1.51	-1.48

3. Channel separation

DASY measurement parameters: Auto Zero Time: 3 sec; Measuring time: 3 sec

	Input Voltage (mV)	Channel X (µV)	Channel Y (µV)	Channel Z (µV)
Channel X	200	-	1.90	-0.22
Channel Y	200	1.47	-	4.60
Channel Z	200	-1.40	-0.08	-

Certificate No: DAE3-577_Nov04

Page 4 of 5



4. AD-Converter Values with inputs shorted

DASY measurement parameters: Auto Zero Time: 3 sec; Measuring time: 3 sec

	High Range (LSB)	Low Range (LSB)
Channel X	15948	15814
Channel Y	15960	16073
Channel Z	16236	16172

5. Input Offset Measurement

DASY measurement parameters: Auto Zero Time: 3 sec; Measuring time: 3 sec Input 10M Ω

	Average (μV)	min. Offset (μV)	max. Offset (μV)	Std. Deviation (µV)
Channel X	0.03	-3.07	1.24	0.58
Channel Y	-0.66	-2.19	1.96	0.55
Channel Z	-0.91	-2.82	0.42	0.39

6. Input Offset Current

Nominal Input circuitry offset current on all channels: <25fA

7. Input Resistance

	Zeroing (MOhm)	Measuring (MOhm)
Channel X	0.2000	199.3
Channel Y	0.2000	200.4
Channel Z	0.2001	199.5

8. Low Battery Alarm Voltage (verified during pre test)

Typical values	Alarm Level (VDC)	
Supply (+ Vcc)	+7.9	
Supply (- Vcc)	-7.6	

9. Power Consumption (verified during pre test)

Typical values	Switched off (mA)	Stand by (mA)	Transmitting (mA)
Supply (+ Vcc)	+0.0	+6	+14
Supply (- Vcc)	-0.01	-8	-9

10. Common Mode Bit Generation (verified during pre test)

Typical values	Bit set to High at Common Mode Error (V _{DC})
Channel X, Y, Z	+1.25

Certificate No: DAE3-577_Nov04

Page 5 of 5