# **EXHIBIT 3**

Report Of Measurement Includes sample calculations, block diagrams, photographs of test configurations and properly signed and dated report.



# **TEST RESULT SUMMARY**

# **FCC PART 15 SUBPART C Section 15.231**

MANUFACTURER'S NAME

Denso Corp

NAME OF EQUIPMENT

Transmitter for Keyless Entry System

MODEL NUMBER

12BAN

MANUFACTURER'S ADDRESS

1-1 Showa-cho, Kariya-shi Aichi-ken, 448-8661 Japan

TEST REPORT NUMBER

W8541.2

**TEST DATE** 

23 November 1998

According to testing performed at TÜV Product Service Inc, the above-mentioned unit is in compliance with the electromagnetic compatibility requirements defined in FCC Part 15.

It is the manufacturer's responsibility to assure that additional production units of this model are manufactured with identical electrical and mechanical characteristics. Any modifications necessary for compliance made during testing on the above mentioned date(s) must be implemented in all production units for compliance to be maintained.

TÜV Product Service Inc, as an independent testing laboratory, declares that the equipment tested as specified above conforms to the requirements of FCC Part 15.

Date:

02 December 1998

Location: Taylors Falls MN

**USA** 

Test Technician

**NVLAP Signatory** 

五年。 如此一個一個一個

Not Transferable





# **EMC EMISSION - TEST REPORT**

Test Report File No.	: <b>W011854101.2</b> Date of issue: <u>02 December 1998</u>	_
Model / Serial No.	: 12BAN /	
Product Type	: Transmitter for Keyless Entry System	_
Applicant	: Denso Corp	
Manufacturer	: Denso Corp	
License holder	: Denso Corp	
Address	: 1-1 Showa-cho, Kariya-shi	
	: Aichi-ken, 448-8661 Japan	_
Test Result	: ■ Positive □ Negative	
Test Project Number Reference(s)	: _ <del>W8541.2</del>	
Total pages including Appendices		

TÜV Product Service Inc is a subcontractor to TÜV Product Service, GmbH according to the principles outlined in ISO/IEC Guide 25 and EN 45001.

TÜV Product Service Inc reports apply only to the specific samples tested under stated test conditions. It is the manufacturer's responsibility to assure that additional production units of this model are manufactured with identical electrical and mechanical components. TÜV Product Service Inc shall have no liability for any deductions, inferences or generalizations drawn by the client or others from TÜV Product Service Inc issued reports.

This report is the confidential property of the client. As a mutual protection to our clients, the public and ourselves, extracts from the test report shall not be reproduced except in full without our written approval. This report shall not be used by the client to claim product endorsement by NVLAP or any agency of the US government.

> TÜV Product Service Inc and its professional staff hold government and professional organization certifications and are members of AAMI, ACIL, AEA, ANSI, IEEE, NVLAP, and VCCI



# DIRECTORY - EMISSIONS

A)	Documentation		Page(s)
	Test report		1 - 10
	Directory		2
	Test Regulations		3
	Deviation from standard / Sumr	nary	10
	Test-setups (Photos)		11 - 12
	Test-setup (drawing)		Appendix A
B)	Test data		
	Conducted emissions	10/150 kHz - 30 MHz	5, 9
	Radiated emissions	10 kHz - 30 MHz	5, 9
	Radiated emissions	30 MHz - 1000 MHz	6, 9
	Interference power	30 MHz - 300 MHz	6, 9
	Equivalent Radiated emissions	1 GHz - 18 GHz	7, 9
C)	Appendix A		
	Test Data Sheets and Test Setup D	rawing(s)	A2 - A6
D)	Appendix B		
	Constructional Data Form		B2
	Product Information Form(s)		B3
E)	Appendix C		
	Measurement Protocol		C1 - C2





### **EMISSIONS TEST REGULATIONS:**

The emissions tests were performed according to following regulations: □ - EN 50081-1 / 1991 □ - Group 2 □ - EN 55011 / 1991 □ - Group 1 ☐ - Class A □ - Class B □ - EN 55013 / 1990 - EN 55014 / 1987 □ - Household appliances and similar □ - Portable tools Semiconductor devices □ - EN 55014 / A2:1990 □ - EN 55014 / 1993 □ - Household appliances and similar □ - Portable tools □ - Semiconductor devices □ - EN 55015 / 1987 ☐ - EN 55015 / A1:1990 - EN 55015 / 1993 ☐ - Class A ☐ - Class B ☐ - EN 55022 / 1987 □ - EN 55022 / 1994 □ - Class A □ - Class B □ - BS □ - Class B □ - Class A □ - VCCI ■ - FCC Part 15 Subpart C Section 15.231 ☐ - Class A - Class B □ - AS 3548 (1992) □ - Group 1 □ - Group 2 □ - CISPR 11 (1990) ☐ - Class B □ - Class A ☐ - Class B ☐ - Class A □ - CISPR 22 (1993)





## Environmental conditions in the lab:

Actual

Temperature : 22 °C Relative Humidity : 39 % : 98.6 kPa Atmospheric pressure : 12 VDC Power supply system

# Sign Explanations:

□ - not applicable ■ - applicable



# **Emissions Test Conditions: CONDUCTED EMISSIONS (Interference Voltage)**

The CONDUCTED EMISSIONS	(INTERFERENCE VOLTAG	E) measurements were per	ormed at the following te	st location:
□ - Test not applicable				
<ul> <li>□ - Wild River Lab Large Te</li> <li>□ - Wild River Lab Small Te</li> <li>□ - Oakwood Lab (Open Ar</li> <li>□ - Wild River Lab Screen F</li> <li>□ - New Brighton Lab Shield</li> </ul>	est Site (Open Area Tes rea Test Site) Room	*		
Test equipment used : Model Number	Manufacturer	Description	Serial Number	Cal Date
Use of the calibrated equipment	nent on this list ensures	traceability to national and int	ternational standards.	
<b>Emissions Test Cond</b>	itions: RADIATED	EMISSIONS (Magnetic F	Field)	
The RADIATED EMISSIONS (N	AGNETIC FIELD) measu	rements were performed at	the following test location	n:
☐ - Wild River Lab Large Te ☐ - Wild River Lab Small Te ☐ - Oakwood Lab (Open Ar	est Site (Open Area Tes	-		
at a test distance of :				
☐ - 3 meters ☐ - 30 meters				
■ - Test not applicable				
Test equipment used : Model Number	Manufacturer	Description	Serial Number	Cal Date





## **Emissions Test Conditions: RADIATED EMISSIONS (Electric Field)**

The RADIATED EMISSIONS (ELECTRIC FIELD) measurements, in the frequency range of 30 MHz-1000 MHz, were tested in a horizontal and vertical polarization at the following test location:

- Wild River Lab Large Test Site (Open Area Test Site)
- ☐ Wild River Lab Small Test Site (Open Area Test Site)
- ☐ Oakwood Lab (Open Area Test Site)

#### at a test distance of:

- 3 meters
- ☐ 10 meters
- ☐ 30 meters

#### Test equipment used:

	Model Number	Manufacturer	Description	Serial Number	Cal Date
■ -	3146	Electro-Mechanics (EMCO)	Log Periodic Antenna	9103-3075	7-97
■ -	3108	Electro-Mechanics (EMCO)	Biconical Antenna	2118	7-97
<b>-</b>	8566B	Hewlett-Packard	Spectrum Analyzer	2221A01596	4-98
■ -	85662A	Hewlett-Packard	Analyzer Display	2152A03640	4-98
■ -	85650A	Hewlett-Packard	Quasi-Peak Adapter	2811A01127	4-98
■ -	ZHL-1042J	Mini-Circuits	Preamplifier	H072294-11	4-98

Use of the calibrated equipment on this list ensures traceability to national and international standards.

#### **Emissions Test Conditions: INTERFERENCE POWER**

The INTERFERENCE POWER measurements were performed by using the absorbing clamp on the mains and interface cables in the frequency range 30 MHz - 300 MHz at the following test location:

#### ■ - Test not applicable

- □ Wild River Lab Large Test Site (Open Area Test Site)
- ☐ Wild River Lab Small Test Site (Open Area Test Site)
- □ Oakwood Lab (Open Area Test Site)
- □ Wild River Lab Screen Room
- □ New Brighton Lab Shielded Room

#### Test equipment used:

Model Number	Manufacturer	Description	Serial Number	Cai Date

The control of the co





# **Emissions Test Conditions: RADIATED EMISSIONS (Electric Field)**

The Equivalent Radiated Emissions measurements in the frequency range 1 GHz - 100 GHz were performed in a horizontal and vertical polarization at the following test location:

- - Wild River Lab Large Test Site (Open Area Test Site)
- ☐ Wild River Lab Small Test Site (Open Area Test Site)
- ☐ Oakwood Lab (Open Area Test Site)
- □ Wild River Lab Screen Room

#### at a test distance of:

- ☐ 1 meters
- 3 meters
- □ 10 meters

<b>□</b> -	Test	not	app	lica	ble
------------	------	-----	-----	------	-----

#### Test equipment used:

	Model Number	Manufacturer	Description	Serial Number	Cal Date
<b>-</b>	3115	Electro-Mechanics (EMCO)	Horn Antenna	9001-3275	8-97
<b>-</b>	8566B	Hewlett-Packard	Spectrum Analyzer	2221A01596	4-98
■ -	85662A	Hewlett-Packard	Analyzer Display	2152A03640	4-98
<b>-</b>	85650A	Hewlett-Packard	Quasi-Peak Adapter	2811A01127	4-98
■ -	ZHL-1042J	Mini-Circuits	Preamplifier	H072294-11	4-98
■ -	AFT-8434	Avantek	Preamplifier Preamplifier	9112 Z221	4-98

Use of the calibrated equipment on this list ensures traceability to national and international standards.

例是**被**政治,所以所以,但是一种的人的,但是一种的人的人的。

A CONTROL OF THE STREET OF THE





# Equipment Under Test (EUT) Test Operation Mode - Emission tests :

The device under test was operated	under the following conditi	ions during emissions testing:
□ - Standby		
☐ - Test program (H - Pattern)		
☐ - Test program (color bar)		
☐ - Test program (customer specific)		
☐ - Practice operation		
☐ - Normal Operating Mode		
■ - Transmitter on.		
Configuration of the device under to  ☐ - See Constructional Data Form in A  ■ - See Product Information Form in A	Appendix B - Page B2	ge B3
The following peripheral devices an		
D	Туре :	
D -	Tunn	
0-	Type:	
	Type:	
O-	Type:	
D	Type:	
□ -	Type :	
O	Type :	
☐ - unshielded power cable	. <del></del>	
☐ - unshielded cables		
☐ - shielded cables	MPS.No.:	
☐ - customer specific cables		
- customer specific capies		
□		





## **Emission Test Results:**

Conducted	d emissions 10/150 kHz - 30 MHz			
The require	ements are	□ - MET	☐ - NOT MET	
Minimum lir	mit margin	dB	at MHz	
Maximum li	imit exceeding	dB	at MHz	
Remarks:				
	the state of the s	20 MU-		
	emissions (magnetic field) 10 kHz	□ - MET	□ - NOT MET	<u></u>
The require		dB	at MHz	
Minimum lii	_			
Maximum li	imit exceeding	dB	at MHz	
Remarks:				<del></del>
Radiated e	emissions (electric field) 30 MHz -			
The require	ements are	■ - MET	☐ - NOT MET	
Minimum li	mit margin for fundamental	0.3 dB	at <u>314.3</u> MHz	
Minimum li	mit margin for spurious	<u>&gt;10</u> dB	at <u>628.7</u> MHz	
Remarks:	The fundamental was measured to cycle) to get average measuremer (5956 uV/m). The second harmon compared to an average limit of 55	nt, or 75.2 dBuV/m (5754 uV/n lic was measured to be 42.4 d	n) compared to a limit of /5.5 i	aBn n/w
Interferen	ce Power at the mains and interfa	ce cables 30 MHz - 300 MHz		
The require	ements are	□ - MET	☐ - NOT MET	
Minimum li	imit margin	dB	at MHz	
Maximum	limit exceeding	dB	at MHz	
Remarks:				
	nt Radiated emissions 1 GHz - 3.14	I GHz		
		■ - MET	☐ - NOT MET	
•	rements are	10 dB	at 1571 MHz	
	imit margin	dB	at MHz	
	limit exceeding	<del></del>	<u></u>	m (501
Remarks:	Peak analyzer reading of 44 dBu\uV/m).	//m (158.4 uv/m), compared to	o all average little of on abuvi	



	100 151 111 4 1257	PRODUCT SERVICE
DEVIATIONS FROM STANDARD:		The second secon
None.		
GENERAL REMARKS:		
the bandwidth to be less than 70 kHz. The	transmitter is on for 44.6 msed	frequency, or 785 kHz. Page A5 of A6 shows c/100 msec, so a duty cycle relaxation factor of lings. Page A6 of A6 shows the on/off times.
SUMMARY:		
The requirements according to the tech	nical regulations are	
■ - met		
☐ - <b>not</b> met.		
The device under test does		
■ - fulfill the general approval requirement	ents mentioned on page 3.	
☐ - <b>not</b> fulfill the general approval requ	irements mentioned on pag	ge 3.
Testing Start Date:	23 November 1998	
Testing End Date:	23 November 1998	
- TÜV PRODUCT SERVICE INC -		
		۸ ۸

J. T. Schneider **NVLAP Signatory**  Tested By: T. K. Swanson

· 松松·總特別國際的一部一灣語音等。1984年19月1日 1月1日書刊的第二十四日 1月





Test-setup photo(s): Conducted emission 10/150 kHz - 30 MHz

Not Applicable

(特殊)(特別な経済を持ち、発力に強力を対して、1000年の一名の「本政」では、1000年

TUV PRODUCT SERVICE

Appendix A

**Test Data Sheets** 

and

Test Setup Drawing(s)




# TEST SETUP FOR EMISSIONS TESTING

# WILD RIVER LAB Large Test Site

### Notes:

- Items shown in dotted lines are located on the floor below the test area. It is 5 meters vertically from the ground floor to the test area.
- 2. 50 Hz, 60 Hz, and 400 Hz are power panels for alternating current.
- 3. The antenna may be positioned horizontally 3, 10 or 30 meters from the center of the turntable.
- 4. The circle is a 6.7 meter diameter turntable.
- 5. A ground plane is in the plane of this sheet.
- 6. The test sample is shown in the azimuthal position representing zero degrees.



さいこと こうしょう かいしょう かいこうかい かんしゅう かいしょう しゅうしゅう しゅうしゅう はんしゅう はんしゅう はんしゅう かいしょう かいしょう しょうしょう しょうしょう しょうしょう しょうしょう しょうしょう しょうしょう しょうしょう しょうしょう しょうしょう しゅうしゅう しゅうしゅう しゅうしゅう しゅうしゅう しゅうしゅう



#### TUV PRODUCT SERVICE

#### RADIATED EMISSIONS

Large Test Site

3 Meter Antenna Distance

Equipment Under Test:

DENSO

12 BAN TRANSMITTER

Notes: WITH AUTO POWEROFF

Report W8541 Run 3 Date 11-23-98 Page 1

Engineer

Tech: TKS

Requester

Frequency MHz	Level :	Factor dB	Cable dB	Peak dBuV/m	Ave dBuV/m	Pol Hei	ar\ ght	Limit dBuV/m	Delta
7 dB duty		correc	tion fa	actor (2)	0 log 44	.6/	100)		
		14.2 14.2	1.6 1.6	62.8 82.2	 75.2	V H		75.5 75.5	
WITHOUT 3		14.2	1.6	82.2	75.2	Н		75.5	
WITH PREA 628.67 628.67	20.1		2.3	42.4 34.3	 	V V		55.5 55.5	
	.68 4.2	23.5 23.5		27 30.5					
1257.4 1257.4	2.7 5.15	25.6 25.6	3.4 3.4	31.6 34.1					
1571.7 1571.7	13.1 11.7	27.1 27.1	3.8 3.8	44 42.6	 	N N		54 54	
1886.1 1886.1	1.4 1.95	28.8 28.8	4.8 4.8	35 35.5	<del></del> 	H V		55.5 55.5	
NOISE FLO 2200.4 - 2200.4 -	OOR 4 -1.1	29.7 29.7	11.8	41 40.3	 	V H	<b></b>	54 54	
2514.7 - 2514.7 -				36 36.3				55.5 55.5	
2829.0 - 2829.0 -	95 4	30.8 30.8	5.5 5.5	35.4 35.9		V H	_ <del>_</del>	54 54	
3143.3 3143.3	.5 55	31.9 31.9	5.3 5.3	37.8 36.7		H V		55.5 55.5	

END OF SCAN



#### TUV PRODUCT SERVICE

#### RADIATED EMISSIONS

Large Test Site

3 Meter Antenna Distance

Equipment Under Test:

DENSO

12 BAN TRANSMITTER

Notes: WITH AUTO POWEROFF

Figure\_\_\_\_

Report W8541 Run 3 Date 11-23-98 Page 2

Engineer


Tech: TKS


Requester\_

Measurement Summary

Frequency MHz	Final dBuV/m	uV/m	Azimuth deg	Polar\ Height	Delta FCC 15.231	Delta
314.3	75.2	5754.4		Н	-0.3	
628.67	42.4	131.82		V	<b>-</b> 13.1	
943.07	30.5	33.496		V	-25	
1257.4	34.1	50.699		Н	-21.4	
1571.7	44	158.48		Н	-10	
1886.1	35.5	59.566		V	-20	
2200.4	41	112.20		V	-13	
2514.7	36.3	65.313		H	-19.2	
2829.0	35.9	62.373		H	-18.1	
3143.3	37.8	77.624		H	-17.7	

File W8541 Run 3







# Appendix B

Constructional Data Form and

Product Information Form(s)



**Constructional Data Form** 

Not Applicable



### Technical Description of the system

#### Type number

- Transmitter

:12BAN

Specifications of receiver

- Nominal frequency

:314.35 MHz

- Local oscillator frequency

:314.35 MHz SAW resonator circuit

:1 MHz CR oscillator circuit

- Radio frequency output power

:75.6 dBuW/m or less

- Type of modulation

:A1D

- Power supply

- Nominal supply voltage

:3 VDC

- Type of battery

:One lithium battery

- Antenna

:Built-in type (fixed)

## Description of the system operation

This system is mainly used for locking or unlocking the doors of the vehicle. The transmitter sends a radio wave signal while the button is pushed. The receiver becomes active in response to the signal from the transmitter.

#### Installation in vehicle

The receiver is installed inside the vehicle.





## **Appendix C**

## MEASUREMENT PROTOCOL

#### **GENERAL INFORMATION**

### **Measurement Uncertainty**

The test system for conducted emissions is defined as the LISN, tuned receiver or spectrum analyzer, and coaxial cable. The test system for radiated emissions is defined as the antenna, the pre-amplifier, the spectrum analyzer and the coaxial cable. These test systems have a measurement uncertainty of ±4.5 dB. The equipment comprising the test systems are calibrated on an annual basis.

## **Justification**

The Equipment Under Test (EUT) is configured in a typical user arrangement in accordance with the manufacturer's instructions. A cable is connected to each available port and either terminated with a peripheral into it's characteristic impedance or left unterminated. When appropriate, the cables are manually manipulated with respect to each other to obtain maximum emissions from the unit.

#### **CONDUCTED EMISSIONS**

The final level, expressed in  $dB\mu V$ , is arrived at by taking the reading directly from the EMI receiver. This level is compared directly to the FCC limit.

To convert between dB $\mu$ V and  $\mu$ V, the following conversions apply:

 $dB\mu V = 20(log \mu V)$  $\mu V = log(dB\mu V/20)$ 

#### RADIATED EMISSIONS

The final level, expressed in  $dB\mu V/m$ , is arrived at by taking the reading from the spectrum analyzer (Level  $dB\mu V$ ) and adding the antenna correction factor and cable loss factor (Factor dB) to it. This result then has the FCC limit subtracted from it to provide the Delta which gives the tabular data as shown in the data sheets in Attachment B. The amplifier gain is automatically accounted for by using an analyzer offset.

Example	: Frequency (MHz)	Level (dΒμV)	+	Factor & = Cable (dB)	Final (dBμV/m)	FCC B - Limit (dBμV/m)	=	Delta FCC B (dB)
	32.21	13.9	+	16.3 =	30.2	- 40.0	=	-0.8





#### **DETAILS OF TEST PROCEDURES**

#### **General Standard Information**

The test methods used comply with ANSI C63.4-1992 - "Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9 kHz to 40 GHz."

#### **Conducted Emissions**

Conducted emissions on the 60 Hz power interface of the EUT are measured in the frequency range of 450 kHz to 30 MHz. The measurements are performed using a receiver, which has CISPR characteristic bandwidth and quasi-peak detection, and a Line Impedance Stabilization Network (LISN), with  $50 \Omega/50 \mu H$  (CISPR 16) characteristics. Table top equipment is placed on a non-conducting table 80 centimeters above the floor and is positioned 40 centimeters from the vertical ground plane (wall) of the screen room. In some cases, a pre-scan using a spectrum analyzer is initially performed on the units comprising the system under test to locate the highest emissions. If the minimum passing margin appears to be less than 20 dB with a peak mode measurement, the emissions are re-measured using a tuned receiver or spectrum analyzer with quasi-peak and average detection and recorded on the data sheets.

#### Radiated Emissions

Radiated emissions from the EUT are measured in the frequency range of 30 to 1000 MHz using a spectrum analyzer and appropriate broadband linearly polarized antennas. Measurements between 30 MHz and 1000 MHz are made with 120 kHz/6 dB bandwidth and quasi-peak detection and measurements above 1000 MHz are made with a 1 MHz/6 dB bandwidth and peak detection. Table top equipment is placed on a 1.0 X 1.5 meter non-conducting table 80 centimeters above the ground plane. Floor standing equipment is placed directly on the turntable/ground plane. Interface cables that are closer than 40 centimeters to the ground plane are bundled in the center in a serpentine fashion so they are at least 40 centimeters from the ground plane. Cables to simulators/testers (if used in this test) are routed through the center of the table and to a screen room located outside the test area. The antenna is positioned 3 meters horizontally from the EUT. To locate maximum emissions from the test sample the antenna is varied in height from 1 to 4 meters, measurement scans are made with both horizontal and vertical antenna polarizations and the EUT are rotated 360 degrees. Intentional radiators are rotated through three orthogonal axes to determine the attitude that maximizes the emissions.

# 6. Component listing

# 6.1. Transmitter

Part Name	Description	Number of Units
IC	-	1
IC	-	1
Resonator	314.35 MHz	1
Transistor	-	1
Inductor	15 - 47nH	1
Capacitor	0.5 - 1.5pF	1
Capacitor	1.5 - 7pF	1
Capacitor	3 - 9pF	1
Capacitor	9 - 16pF	2
Capacitor	24pF	1
Capacitor	1000pF	1
Capacitor	0.1µF	1
Capacitor	1μF	1
Resistor	180 - 330Ω	1
Resistor	1kΩ	1
Resistor	4.7 - 8.2kΩ	1
Resistor	6.8 - 12kΩ	1
Resistor	7.5kΩ	1
Resistor	22kΩ	1
Resistor	47kΩ	2
Switch	-	4
Battery	3V	1