# TEST REPORT NO. RSI-2084E ELECTROMAGNETIC INTERFERENCE (EMI) OF THE

INVISIBLE FENCE CO.

MODEL INVISIBLE SENTRY

FCC PART 15, SUBPART C, PARAGRAPH 249

18 JULY 2000

PREPARED FOR:

Invisible Fence Co. 355 Phoenixville Pike Malvern, PA 19355

**SUBMITTED BY:** 

Radiation Sciences Inc. 3131 Detwiler Road Harleysville, PA 19438

PREPARED BY:

Daniel/J. Signore

President

**Radiation Sciences Inc.** 

**REVIEWED BY:** 

Chester B. Kosiorek EMC Engineer

**Radiation Sciences Inc.** 

# RADIATION SCIENCES INC.

# **TABLE OF CONTENTS**

<b>SECTION</b>	TITLE	<b>PAGE</b>
	Table of Contents List of Figures Administrative Data Summary of Test Results	i i ii iii
1.0	INTRODUCTION	1
2.0	DESCRIPTION OF THE TEST SAMPLE	2
3.0	TEST INSTRUMENTATION	3
4.0 4.1 4.2 4.3 5.0	TEST RESULTS Conducted Power Line Measurements, Paragraph 15.209 Radiated Emission Measurements, Paragraph 15.249 Emission Bandwidth, FCC Part 15, Paragraph 15.231c CONCLUSIONS	4 4 8 11 14
APPENDIX A	RSI's Open Area Test Site RSI-4963E	
APPENDIX B	RSI's CERTIFICATIONS	
	LIST OF FIGURES	
FIGURE 1	Power Line Conducted Emissions Test Setup	5
FIGURE 2	Power Line Emissions Test Results - Phase	6
FIGURE 3	Power Line Emissions Test Results - Neutral	7
FIGURE 4	Radiated Emissions Test Results for Intentional Radiators	9
FIGURE 5	Radiated Emissions Test Setup Photograph	10
FIGURE 6	Bandwidth Plot	12
FIGURE 7	Bandwidth of Fundamental Frequency	13

RSI-2084E -i-

#### **ADMINISTRATIVE DATA**

# **TEST PERFORMED:**

Measurements of radiated RF and conducted emissions.

## **PURPOSE OF TEST:**

To evaluate the ElectroMagnetic Interference (EMI) characteristics of the Equipment Under Test with respect to Subpart C of Part 15 of the Federal Communications Commission (FCC) Rules for intentional radiators.

## **EQUIPMENT UNDER TEST (EUT):**

Model: Invisible Sentry

# **CONTRACT:**

Purchase Order Number: 790338

## **TEST PERIOD:**

17 July 2000

#### **TEST FACILITY:**

Radiation Sciences Incorporated (RSI), EMI/EMC Test Laboratory, located at: 3131 Detwiler Road, Harleysville, Pennsylvania 19438.

## **TEST PERSONNEL AND COORDINATORS:**

#### **Radiation Sciences Inc.**

**Tactical Technologies, Inc.** 

Chet Kosiorek

Jim Deery

# **SUMMARY OF TEST RESULTS**

The Model Invisible Sentry, configured as described herein, COMPLIES WITH THE REQUIREMENTS SET FORTH IN SUBPART C OF PART 15, (Para. 249) OF THE FEDERAL COMMUNICATIONS COMMISSION (FCC) RULES FOR INTENTIONAL RADIATORS.

RSI-2084E -iii-



# 1.0 INTRODUCTION

This document is a report of tests to determine the ElectroMagnetic Interference (EMI) characteristics of the **Model Invisible Sentry**, presented by **Invisible Fence Co.** of Malvern, Pennsylvania.

The purpose of the testing was to evaluate the EMI characteristics of the test sample with respect to Subpart C, Para. 249 of Part 15 of the FCC Rules for intentional radiators.

Test setups and procedures are described in RSI's Test Procedures 4963E (see Appendix A) and test results are summarized herein on graphs.

All test procedures used meet the requirements of the American National Standards Institute Procedure C63.4: "Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9kHz to 40GHz", dated 17 July 1992.

RSI-2084E

HADIATION SOILNOLD INC.

# 3.0 TEST INSTRUMENTATION

					LACT	CAL	ċ	<b>↓</b>
RSI INV #	DESCRIPTION	MANUFACTURER	MODEL#	SERIAL#	LAST CAL DATE	CAL DUE DATE	Ē	Y P E
31	SPEC ANALYZER	ADVANTEST	R3271	J003583	2/23/2000	2/23/2001	12	С
32	SPEC. ANALY.	H.P.	8568B	2841A04457	4/27/2000	4/27/2001	12	С
33	SPEC. ANALY.	H.P.	85662A	2848A17406	4/27/2000	4/27/2001	12	С
77	ANTENNA	TENSOR	4108	2011	5/25/1999	5/25/2000	12	UC
83	ANTENNA	EMCO	3146	1554	12/1/1999	12/1/2000	12	٧
91	ANTENNA	EMCO	3115	2023	5/22/2000	5/22/2001	12	С
391	RECEIVER	R&S	ESVP	861744/015	4/18/2000	4/18/2001	12	С

-3-

RSI-2084E

# 4.0 TEST RESULTS


# 4.1 Conducted Power Line Measurements, Paragraph 15.209

The Invisible Sentry was tested to the FCC Part 15 requirements of Para. 209.

Figure 1 is a photograph of the Power Line Emissions Test Setup. Figure 2 and 3 are the test results for the phase and neutral power line emission tests.

The Power Line Emissions were within the 15.209 conducted limits.






Name: DCP01655.JPG Dimensions: 1152 x 864 pixels

# POWER LINE CONDUCTED EMISSIONS TEST SETUP

# FIGURE 1

		1					4.04444444444444444		OF 0	
	COND. EMIS.	S/N: 1		LIMIT			and the second of the second s		10	
) \I	FCC CLASS B	INVISIBLE FENCE OF INVISIBLE SENTRY MODEL: N/A S/N: AC POWERLINE: PHA					And the state of t			[41.14]
INC.  -							APANALUTAN MANAMANAN MANAMANAN			
SCIENCES INC. EVEL [dBuV]	-						Marketon Marketon Company of the Company of the State of the Company of the Compa		and the second s	
RADIATION SCIENCES FMISSION LEVEL [ dB							And they de they have been been been been been been been be		2	
	100		80	entile control entitle point of lands	09	0		O N	. 45	



# 4.2 Radiated Emission Measurements, Paragraph 15.249

Radiated emission measurements were recorded for the test sample at a distance of 3 meters. The results of field strength measurements are illustrated on Figure 4 for Intentional radiators. Figure 5 is a photograph of the test setup. Radiated emissions were measured with the antenna in both the horizontal and vertical polarizations. The antenna was raised 1 to 4 meters in height and the equipment under test (EUT) was rotated 360° to maximize the mission.

During radiated emissions testing the EUT was scanned from 30MHz to 9.165GHz (10 times the fundamental).

ALL LEVELS COMPLY WITH APPLICABLE LIMITS.

RSI-2084E -8-

FIGURE 4

Company: Invisible Fence Model #: Invisible Sentry

Radiated Emission for Intentional Radiators

Test Personnel: CBK Date: 7/17/00

Date:

_				T				Т	Т	Т	Т			Τ	Т	_	Γ	T		Γ	Τ	Т		Τ	T	T		
		Margin	116.00	(an)	-3.8	-1.5			2 2	5.5	0.7-																	
	Limits	@ E		(UN/NII)	50k	200			102	308	200																	
Field	Strongth	Sucrigin		(m//m)	32360	422				27230	224																	
			@ 3m	(dBuV/m)	94.0	54.0	2		1	94.0	54.0																	
71711	Lield .	Strength		(dBuV/m)	200	30.5	0.70	1		88.7	47.0				oi.	1	MDZ.											
		Averaging	Factor	(dB)		ING.	n/a			n/a	e/u				corded above	1000	MHz to 9165											
-		Cable A	Loss	(dB)	(an)	1:0	1:0			1.0	0	2	1		stacted are re		med from 30											
	Distance	Factor	1m to 3m	(ap)	(gp)	n/a	n/a	_		e/u	5 0	17.0			All Filt sizes detected are recorded above.	UI SIGIIGIS O	All testing was performed from 30MHz to 9165MHz.											
	_	Antenna		_	(gp)	23.0	25.0			23.0	23.0	25.0				T T	All testi											
		Indicated	_	1000	(dBuV)	66.2	26.5			7.70	04.7	21.0																
				Azımıdını	(Degrees)	355	0			,	0	0			1													
		carota		_	(Meters) (	1.46	1.00				1.55	1.00																
					Polarity	HORIZ	HORIZ				VERT	VERT												4				
				requency	(MHz)	916.548	1833.000				916.548	1833.000												100				

-9-

# RADIATED EMISSIONS TEST RESULTS





Name:

DCP01651.JPG Dimensions: 1152 x 864 pixels

# RADIATED EMISSIONS TEST SETUP

FIGURE 5

# 4.3 Emission Bandwidth, FCC Part 15, Paragraph 15.231c


The bandwidth requirement for intentional transmitters operating above 900MHz is that the bandwidth of the emission shall be no wider than 0.5% of the center frequency of the device measured at the 20dB points.

The center frequency of the Model Invisible Sentry is 916.546MHz.

The measured bandwidth of the **Invisible Sentry** is 225kHz as shown on the bandwidth data sheet, Figures 6 and 7.

RSI-2084E -11-





# RADIATION SCIENCES INC.

Company: Invisible Fence Co.

Test Personnel: Chester Kosiorek

**Model Invisible Sentry** 

Date: 07/19/00

# BANDWIDTH OF FUNDAMENTAL FREQUENCY

	Frequency (MHz)	Measurement (dBuV/m)
Center Frequency	916.550	66
20dB Down	916.442	46
20dB Down	916.667	46

# 20dB BANDWIDTH IS 225kHz

# FIGURE 7