



12/11/06

BreezeMAX 2500 system
FCC ID: LKT-BMAX-B-B25

Frequency and power determination before shipment:

Before product shipment from the factory, the units pass automatic calibration sequence test where the unit is calibrated (including power out) and frequency is tested.

Base station installation.

The user configures the unit according to licensed frequencies(user may have several frequencies)

Subscriber station transmits only when Base station is detected and adjusts the frequency to the Base station transmission.