

**Nemko Test Report No.:**

2L0311RUS1

**Applicant:**

Decade Transmitters  
3232 Richard St. Unit 04  
Sherbrooke, QC J1L 1Y2

**Equipment Under Test:**

FM-800 Mono Transmitter  
FM-850 Stereo Transmitter

**In Accordance With:**

**FCC Part 73, Subpart G**  
FM Broadcast Transmitters

**Tested By:**

Nemko Dallas Inc.  
802 N. Kealy  
Lewisville, Texas 75057-3136



**Authorized By:**

Tom Tidwell, RF Group Manager

**Date:**

6/19/02

**Total Number of Pages:**

35

**Table of Contents**

Section 1. Summary of Test Results ..... 3

Section 2. General Equipment Specification..... 5

Section 3. RF Power Output..... 7

Section 4. Occupied Bandwidth..... 10

Section 5. Spurious Emissions at Antenna Terminals ..... 14

Section 6. Field Strength of Spurious..... 18

Section 7. Powerline Conducted Emissions..... 21

Section 8. Test Equipment List..... 27

ANNEX A - TEST DETAILS..... 28

ANNEX B - TEST DIAGRAMS ..... 33

**Section 1. Summary of Test Results**

Manufacturer: Decade Transmitters

Model No.: FM-800 and FM-850

Serial No.: 647 & S677

General: **All measurements are traceable to national standards.**

These tests were conducted on a sample of the equipment for the purpose of demonstrating compliance with FCC Part 73, Subpart G.



New Submission



Production Unit



Class II Permissive Change



Pre-Production Unit

THIS TEST REPORT RELATES ONLY TO THE ITEM(S) TESTED.

THE FOLLOWING DEVIATIONS FROM, ADDITIONS TO, OR EXCLUSIONS FROM THE TEST SPECIFICATIONS HAVE BEEN MADE. NONE  
See " Summary of Test Data".

Nemko Dallas, Inc. authorizes the above named company to reproduce this report provided it is reproduced in its entirety and for use by the company's employees only.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Nemko Dallas, Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

This report applies only to the items tested.

**Summary Of Test Data**

<b>NAME OF TEST</b>	<b>PARA. NO.</b>	<b>SPEC.</b>	<b>RESULT</b>
RF Power Output	73.811	1 watt min.	Complies
Occupied Bandwidth	73.317	Mask	Complies
Spurious Emissions at Antenna Terminals	73.317	-13 dBm	Complies
Field Strength of Spurious Emissions	73.317	-13 dBm	Complies

**Footnotes:**

**Measurement uncertainty is expressed to a confidence level of 95%.**


**Section 2. General Equipment Specification**

<b>Supply Voltage Input:</b>	115 Vac
<b>Operating Frequency:</b>	87.9 to 107.9 MHz
<b>Channel Spacing:</b>	200 kHz
<b>Number of Channels:</b>	100
<b>Type of Modulation and Designator:</b>	180KF3E Frequency Modulation
<b>Output Impedance:</b>	50 ohms
<b>RF Output (Rated):</b>	1.8 Watts at antenna terminals.
<b>Frequency Selection:</b>	<b>Software</b> <input type="checkbox"/> <b>Manual</b> <input checked="" type="checkbox"/>

**System Description**

The DecadeFM-800 Mono transmitter and the FM-850 Stereo transmitter are transmitters designed to operate in commercial FM broadcast band, LP10 Services.

**System Diagram**



**Section 3. RF Power Output**

NAME OF TEST: RF Power Output	PARA. NO.: 73.267(b)(2)
TESTED BY: David Light	DATE: 6/6/2002

**Test Results:** Complies.

**Measurement Data:**

EUT	Measured Output Power (dBm)	Measured Output Power (W)	Measured/Rated Output Power (dB)
FM-800	32.32	1.706	0.948
FM-850	32.55	1.799	0.999

**Equipment Used:** 1036-1064-1065-1045

**Measurement Uncertainty:** +/- 1.6 dB

Test Plots – RF Power Output



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot		RF Power Output															
Page <u>1</u> of 2				Complete <u>X</u>													
Job No.:	2L0311	Date:	6/6/2002	Preliminary: _____													
Specification:	73.267(b)(2)	Temperature(°C):	24														
Tested By:	David Light	Relative Humidity(%):	40														
E.U.T.:	Decade transmitters																
Configuration:	Tx FULL POWER																
Sample Number:	1 & 2																
Location:	Lab 1	RBW:	2 kHz	Measurement													
Detector Type:	Peak	VBW:	2 kHz	Distance: <u>NA</u> m													
<b>Test Equipment Used</b>																	
Antenna:	_____	Directional Coupler:	_____														
Pre-Amp:	_____	Cable #1:	1045														
Filter:	_____	Cable #2:	_____														
Receiver:	1036	Cable #3:	_____														
Attenuator #1:	1064	Cable #4:	_____														
Attenuator #2:	1065	Mixer:	_____														
Additional equipment used:	_____																
Measurement Uncertainty:	+/-1.7 dB																
<table border="1" style="width:100%; border-collapse: collapse; font-size: small;"> <tr> <td style="text-align: center;">Ref Lvl</td> <td style="text-align: center;">32.55 dBm</td> <td style="text-align: center;">VBW</td> <td style="text-align: center;">2 kHz</td> <td style="text-align: center;">RF Att</td> <td style="text-align: center;">40 dB</td> </tr> <tr> <td style="text-align: center;">42.6 dBm</td> <td style="text-align: center;">98.50012525 MHz</td> <td style="text-align: center;">SWT</td> <td style="text-align: center;">80 ms</td> <td style="text-align: center;">Unit</td> <td style="text-align: center;">dBm</td> </tr> </table>						Ref Lvl	32.55 dBm	VBW	2 kHz	RF Att	40 dB	42.6 dBm	98.50012525 MHz	SWT	80 ms	Unit	dBm
Ref Lvl	32.55 dBm	VBW	2 kHz	RF Att	40 dB												
42.6 dBm	98.50012525 MHz	SWT	80 ms	Unit	dBm												
<p>Center 98.5 MHz      12.5 kHz/      Span 125 kHz</p>																	
Date: 06.JUN.2002 09:14:17																	
Notes: <u>FM-850</u>																	




Test Plots – RF Power Output



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.



**Section 4. Occupied Bandwidth**

NAME OF TEST: Occupied Bandwidth	PARA. NO.: 73.317
TESTED BY: David Light	DATE: 6/6/2002

**Test Results:** Complies.

**Test Data:** See attached plot(s).

All occupied bandwidth measurements were made with the transmitter deviation set to +/- 75 kHz.

**Measurement Uncertainty:** +/- 1.6 dB


**Test Plots –Occupied Bandwidth**



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot		Occupied Bandwidth			
Page 1 of 6				Complete	X
Job No.:	2L0311	Date:	6/6/2002	Preliminary:	
Specification:	73.317	Temperature(°C):	24		
Tested By:	David Light	Relative Humidity(%)	40		
E.U.T.:	DECADE FM TRANSMITTERS				
Configuration:	TX AUDIO SIGNAL FULL POWER				
Sample Number:	1 & 2				
Location:	Lab 1	RBW:	5 kHz	Measurement	
Detector Type:	Peak	VBW:	5 kHz	Distance:	m
<b>Test Equipment Used</b>					
Antenna:		Directional Coupler:			
Pre-Amp:		Cable #1:	1045		
Filter:		Cable #2:			
Receiver:	1036	Cable #3:			
Attenuator #1:	1064	Cable #4:			
Attenuator #2:	1065	Mixer:			
Additional equipment used:					
Measurement Uncertainty:	+/-1.7 dB				



Date: 06.JUN.2002 09:01:20


Notes: **FM-850 STEREO TRANSMITTER**  
**STEREO OPERATION**

Test Plots –Occupied Bandwidth



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.




**Test Plots –Occupied Bandwidth**



Nemko Dallas, Inc.

Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667



**Section 5. Spurious Emissions at Antenna Terminals**

NAME OF TEST: Spurious Emissions @ Antenna Terminals	PARA. NO.: 73.371
TESTED BY: David Light	DATE: 6/6/2002

**Test Results:** Complies.

**Test Data:**

**Equipment Used:** 1036-1064-1065-1042


**Measurement Uncertainty:** +/- 1.6 dB

**Test Plots – Spurious Emissions at Antenna Terminals**



Nemko Dallas, Inc.

Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667




**Test Plots – Spurious Emissions at Antenna Terminals**



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.






**Test Plots – Spurious Emissions at Antenna Terminals**



Nemko Dallas, Inc.

Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667



**Section 6. Field Strength of Spurious**

NAME OF TEST: Field Strength of Spurious Emissions	PARA. NO.: 2.1051
TESTED BY: David Light	DATE: 6/6/2002

**Test Results:** Complies.

**Test Data:** See attached table.

**Equipment Used:** 1464-791-1485-1484-1304-1480

**Measurement Uncertainty:** +/- 1.6 dB

**Test Data - Radiated Emissions**



Nemko Dallas, Inc.

**Dallas Headquarters:**

802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

**ERP Substitution Method**

Page 1 of 1

Job No.: 210311 Date: 6/7/2002 Complete X  
Preliminary \_\_\_\_\_

Specification: Pt 73 Temperature(°C): 24

Tested By: Tom Tidwell Relative Humidity(%) 40

E.U.T.: FM-800 & FM-850

Configuration: Tx at 98.5 MHz full power into load

Sample No: 1&2

Location: AC 3 RBW: 100 kHz Measurement  
Detector Type: Peak VBW: 30 kHz Distance: 3m m

**Test Equipment Used**

Antenna: 1304 Directional Coupler: \_\_\_\_\_

Pre-Amp: 791 Cable #1: 1484

Filter: \_\_\_\_\_ Cable #2: 1485

Receiver: 1036 Cable #3: \_\_\_\_\_

Attenuator #1: \_\_\_\_\_ Cable #4: \_\_\_\_\_

Attenuator #2: \_\_\_\_\_ Mixer: \_\_\_\_\_

Additional equipment used: 1480

Measurement Uncertainty: +/-3.6 dB

Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)	Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)	Limit (dBm)	ERP (dBm)	ERP (mW)	Polarity	Comments
197	-43.0	-2.5	0	0.0	-13	-45.5	0.0000	V	
295.5	-52.0	3.0	0	0.0	-13	-49.0	0.0000	V	
394	-44.2	4.7	0	0.0	-13	-39.5	0.0001	V	
492.5	-53.7	6.2	0	0.0	-13	-47.5	0.0000	V	
591	-48.0	2.0	0	0.0	-13	-46.0	0.0000	V	
689.5	-53.2	9.7	0	0.0	-13	-43.5	0.0000	V	
788	-47.5	36.0	24.6	-0.7	-13	-36.8	0.0002	V	
886.5	-54.8	32.2	24.8	4.9	-13	-42.6	0.0001	V	
985	-51.0	29.3	24.7	5.0	-13	-41.4	0.0001	V	
197	-48.2	-0.3	0	0.0	-13	-48.5	0.0000	H	
295.5	-56.2	3.2	0	0.0	-13	-53.0	0.0000	H	
394	-53.2	2.7	0	0.0	-13	-50.5	0.0000	H	
492.5	-60.5	3.0	0	0.0	-13	-57.5	0.0000	H	
591	-55.7	8.7	0	0.0	-13	-47.0	0.0000	H	
689.5	-57.8	8.8	0	0.0	-13	-49.0	0.0000	H	
788	-54.8	39.2	24.6	-0.7	-13	-40.9	0.0001	H	
886.5	-57.0	30.3	24.8	4.9	-13	-46.6	0.0000	H	
985	-55.2	31.0	24.7	5.0	-13	-43.9	0.0000	H	

Notes: Scanned spectrum to the 10th harmonic

**Photographs of Test Setup**

FRONT VIEW



REAR VIEW



**Section 7. Powerline Conducted Emissions**

NAME OF TEST: Powerline Conducted Emissions	PARA. NO.: 15.207
TESTED BY: David Light	DATE:6/6/2002

**Test Results:** Complies

**Limit:**

Frequency	Limit μV/m	Limit dBμV/m
0.450 to 30 MHz	250	48

**Results:**

**FM-800**

The worst case emission was 23.4 dBμV/m on Neutral line. This is 24.6 dB below the quasi-peak limit of 48 dBμV/m.

**FM-850**

The worst case emission was 22.23 dBμV/m on Neutral line. This is 25.77 dB below the quasi-peak limit of 48 dBμV/m.


**Test Plots – Powerline Conducted Emissions**



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot		Powerline Conducted Emissions	
Page 1 of 4		Complete _____	
Job No.:	2L0311	Date:	6/8/2002
Specification:	PT15	Temperature(°C):	25
Tested By:	David Light	Relative Humidity(%)	40
E.U.T.:	FM-800 & FM-850 TRANSMITTERS		
Configuration:	TX FULL POWER		
Sample Number:	1 & 2		
Location:	Lab 4	RBW:	10 kHz
Detector Type:	Peak	VBW:	10 kHz
		Measurement Distance:	_____ m
<b>Test Equipment Used</b>			
Antenna:		L.I.S.N.:	1258
Limiter:	674	Cable #1:	1526
Filter:	1555	Cable #2:	1114
Receiver:	1036	Cable #3:	
Attenuator #1:		Cable #4:	
Attenuator #2:		Mixer:	
Additional equipment used:			
Measurement Uncertainty:	+/-1.7 dB		




Notes: L1  
FM-800 TRANSMITTER

Test Plots – Powerline Conducted Emissions



Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.




**Test Plots – Powerline Conducted Emissions**



Nemko Dallas, Inc.

Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667






**Test Plots – Powerline Conducted Emissions**




Dallas Headquarters:  
802 N. Kealy  
Lewisville, TX 75057  
Tel: (972) 436-9600  
Fax: (972) 436-2667

Nemko Dallas, Inc.



**Test Setup – Powerline Conducted Emissions**



**Section 8. Test Equipment List**

Nemko ID	Description	Manufacturer Model Number	Serial Number	Calibration Date
1036	SPECTRUM ANALYZER	ROHDE & SCHWARZ FSEK30	830844/006	12/18/01
1042	CABLE, 4M	STORM PR90-010-144	N/A	06/14/02
674	LIMITER	HP 11947A	3107A02200	11/04/00
1555	Filter high pass 5KHz	Solar Electronics 7930-5.0	933125	06/06/02
1258	LISN .15mhz-30mhz	EMCO 0	1305	04/04/01
1526	Cable, .6m	KTL RG223	NA	08/06/01
1114	CABLE, 7m	KTL RG223	N/A	06/06/02
1304	HORN ANTENNA	ELECTRO METRICS RGA-60	6151	07/30/01
791	PREAMP, 25dB	ICC LNA25	398	08/16/01
1484	Cable 2.0-18.0 Ghz	Storm PR90-010-072	N/A	06/01/01
1485	Cable 2.0-18.0 Ghz	Storm PR90-010-216	N/A	06/01/01
1064	ATTENUATOR	NARDA 776B-20	NONE	09/13/01
1065	ATTENUATOR	NARDA 776B-10	NONE	09/13/01

**ANNEX A - TEST DETAILS**

**NAME OF TEST: RF Power Output****PARA. NO.: 73.267**

Determining operating power.

(a) The operating power of each FM station is to be determined by either the direct or indirect method.

(b) Direct method. The direct method of power determination for an FM station uses the indications of a calibrated transmission line meter (responsive to relative voltage, current, or power) located at the RF output terminals of the transmitter. This meter must be calibrated whenever there is any indication that the calibration is inaccurate or whenever any component of the metering circuit is repaired or replaced. The calibration must cover, as a minimum, the range from 90% to 105% of authorized power. The meter calibration may be checked by measuring the power at the transmitter terminals while either:

(1) operating the transmitter into the transmitting antenna, and determining actual operating power by the indirect method described in §73.267(c); or

(2) operating the transmitter into a load (of substantially zero reactance and a resistance equal to the transmission line characteristic impedance) and using an electrical device (within  $\pm 5\%$  accuracy) or temperature and coolant flow indicator (within  $\pm 4\%$  accuracy) to determine the power.

(c) Indirect method. The operating power is determined by the indirect method by applying an appropriate factor to the input power to the last radio-frequency power amplifier stage of the transmitter, using the following formula:

$$\text{Transmitter output power} = E_p \times I_p \times F$$

Where:

$E_p$  = DC input voltage of final radio stage.

$I_p$  = Total DC input current of final radio stage.

$F$  = Efficiency factor.

(1) If the above formula is not appropriate for the design of the transmitter final amplifier, use a formula specified by the transmitter manufacturer with other appropriate operating parameters.

(2) The value of the efficiency factor, F, established for the authorized transmitter output power is to be used for maintaining the operating power, even though there may be some variation in F over the power operating range of the transmitter.

(3) The value of F is to be determined and a record kept thereof by one of the following procedures listed in order of preference:

(i) Using the most recent measurement data for calibration of the transmission line meter according to the procedures described in paragraph (b) of this section or the most recent measurements made by the licensee establishing the value of F. In the case of composite transmitters or those in which the final amplifier stages have been modified pursuant to FCC approval, the licensee must furnish the FCC and also retain with the station records the measurement data used as a basis for determining the value of F.

(ii) Using measurement data shown on the transmitter manufacturer's test data supplied to the licensee; provided that measurements were made at the authorized frequency and transmitter output power.

(iii) Using the transmitter manufacturer's measurement data submitted to the FCC for type acceptance and as shown in the instruction book supplied to the licensee.

<b>NAME OF TEST: Occupied Bandwidth</b>	<b>PARA. NO.: 73.317</b>
---	--------------------------

FM transmission system requirements.

(a) FM broadcast stations employing transmitters authorized after January 1, 1960, must maintain the bandwidth occupied by their emissions in accordance with the specification detailed below. FM broadcast stations employing transmitters installed or type accepted before January 1, 1960, must achieve the highest degree of compliance with these specifications practicable with their existing equipment. In either case, should harmful interference to other authorized stations occur, the licensee shall correct the problem promptly or cease operation.

(b) Any emission appearing on a frequency removed from the carrier by between 120 kHz and 240 kHz inclusive must be attenuated at least 25 dB below the level of the unmodulated carrier. Compliance with this requirement will be deemed to show the occupied bandwidth to be 240 kHz or less.

(c) Any emission appearing on a frequency removed from the carrier by more than 240 kHz and up to and including 600 kHz must be attenuated at least 35 dB below the level of the unmodulated carrier.

(d) Any emission appearing on a frequency removed from the carrier by more than 600 kHz must be attenuated at least  $43 + 10 \text{ Log}_{10}(\text{Power, in watts})$  dB below the level of the unmodulated carrier, or 80 dB, whichever is the lesser attenuation.

(e) Preemphasis shall not be greater than the impedance-frequency characteristics of a series inductance resistance network having a time constant of 75 microseconds. (See upper curve of Figure 2 of §73.333.)

<b>NAME OF TEST: Field Strength of Spurious Radiation</b>	<b>PARA. NO.: 2.1053</b>
---	--------------------------

**Minimum Standard:** Para. No.73.317(d). Any emission appearing on a frequency removed from the carrier by more than 600 kHz must be attenuated at least  $43 + 10 \text{ Log}_{10}$  (Power, in watts) dB below the level of the unmodulated carrier, or 80 dB, whichever is the lesser attenuation.


**Test Method:** TIA/EIA-603-1992, Section 2.2.12

The antenna substitution method was used to determine the equivalent radiated power at spurious frequencies. The spurious emissions were measured at a distance of 3 meters. The EUT was then replaced with a reference substitution antenna with a known gain referenced to a dipole. This antenna was fed with a signal at the spurious frequency. The level of the signal was adjusted to repeat the previously measured level. The resulting erp is the signal level fed to the reference antenna corrected for gain referenced to a dipole.




**ANNEX B - TEST DIAGRAMS**


**Para. No. 2.985 - R.F. Power Output**



**Para. No. 2.989 - Occupied Bandwidth**



**Para. No. 2.991 Spurious Emissions at Antenna Terminals**



**Para. No. 2.993 - Field Strength of Spurious Radiation**

