

Post Installation Checklist

The following table lists the tasks that should be performed upon completing installation.

TABLE 4: POST INSTALLATION CHECKLIST		
NO.	CHECKLIST ITEM	☑
1	Scope out the entire area setup to locate any obvious problem areas.	<input type="checkbox"/>
2	Check antenna routing for safety concerns and near-field boundary setup.	<input type="checkbox"/>
3	Use tie wraps, where possible to ensure that all cables routed in parallel are bundled together.	<input type="checkbox"/>
4	Perform appropriate testing to ensure base station works properly.	<input type="checkbox"/>



Once installation is complete, make sure the area is clear of debris that would prevent proper airflow and ventilation.



No transmitter tuning or adjustments are to be performed in the field. The base station is factory set to meet all FCC requirements as required by the base station certification.