

849 NW State Road 45 Newberry, Fl 32669 USA

Phone: 888.472.2424 or 352.472.5500

Fax: 352.472.2030

Email: <u>info@timcoengr.com</u>
Website: <u>www.timcoengr.com</u>

FCC PART 15 SUB PART B

| Applicant | AUTOSTART | | | |
|----------------------|------------------------------------|--|--|--|
| Address | 5764 PARE | | | |
| | MONTREAL, QUEBEC CANADA H4P 2M2 | | | |
| FCC ID: | NAHSHL101 | | | |
| Product Description | SECURITY RECEIVER | | | |
| Date Sample Received | 12/14/2006 | | | |
| Date Tested | 1/5/2007 | | | |
| Tested By | JOSEPH SCOGLIO | | | |
| Approved By | MARIO DE ARANZETA | | | |
| Report Number | 3386AUT6TestReport.doc | | | |
| Total Pages | 9 | | | |
| Test Results | | | | |

THE ATTACHED REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL WITHOUT THE WRITTEN APPROVAL OF TIMCO ENGINEERING, INC.





TABLE OF CONTENTS

| | Δ |
|-------------------------------------|-----|
| GENERAL INFORMATION | . 7 |
| TEST EQUIPMENT LIST | |
| TEST PROCEDURE | |
| RADIATED SPURIOUS EMISSIONS | |
| POWER LINE CONDUCTED INTERFERENCE | |
| RADIATED EMISSIONS TEST SETUP PHOTO | |

APPLICANT: AUTOSTART FCC ID: NAHSHL101





STATEMENT OF COMPLIANCE

This equipment has been tested in accordance with the standards identified in the referenced test report. To the best of my knowledge and belief, these tests were performed using the measurement procedures described in this report and demonstrate that the equipment complies with the appropriate standards.

I attest that the necessary measurements were made by me or under my supervision, at TIMCO ENGINEERING, INC. located at 849 N.W. State Road 45, Newberry, Florida 32669 USA.

Authorized by: Mario de Aranzeta

Signature: < Mario de Aranzeta>

Function: Engineer

Date: 1/30/2007

APPLICANT: AUTOSTART FCC ID: NAHSHL101

REPORT: 3386AUT6TestReport.doc

Page 3 of 9





GENERAL INFORMATION

| The test results relate only to the items tested. | | | | | |
|---|---|--|--|--|--|
| DUT Description | SECURITY RECEIVER | | | | |
| FCC ID | NAHSHL101 | | | | |
| DUT Power Source | ☐ 110-120Vac/50- 60Hz | | | | |
| | ☐ DC Power | | | | |
| | ☐ Battery Operated Exclusively | | | | |
| Test Item | tem Prototype | | | | |
| | ☐ Pre-Production | | | | |
| | ☐ Production | | | | |
| Modifications to DUT | None | | | | |
| Test Standards | FCC Part 15, Subpart B, ANSI C63.4-2003 | | | | |

APPLICANT: AUTOSTART FCC ID: NAHSHL101





TEST EQUIPMENT LIST

| Device | Manufacturer | Model | Serial Number | Cal/Char Date | Due Date |
|-----------------|-----------------|--------------------------|---------------|----------------|-----------------|
| 3-Meter OATS | TEI | N/A N/A | | Listed 1/11/06 | 1/10/09 |
| 3/10-Meter | TEI | N/A N/A | | Listed 3/27/04 | 3/26/07 |
| OATS | | | | | |
| Analyzer Tan | HP | 8566B Opt 462 3138A07786 | | CAL 12/7/05 | 12/7/07 |
| Tower | | • | 3144A20661 | | |
| Spectrum | | | | | |
| Analyzer | | | | | |
| Analyzer Tan | HP | 85685A | 3221A01400 | CAL 12/7/05 | 12/7/07 |
| Tower RF | | | | | |
| Preselector | | | | | |
| Analyzer Tan | HP | 85650A | 3303A01690 | CAL 12/8/05 | 12/8/07 |
| Tower Quasi- | | | | | |
| Peak Adapter | | | | | |
| Analyzer Tan | HP | 8449B-H02 | 3008A00372 | CAL 12/8/05 | 12/8/07 |
| Tower | | | | | |
| Preamplifier | | | | | |
| Analyzer Blue | HP | 8568B | 2928A04729 | CAL 4/13/05 | 4/13/07 |
| Tower | | | 2848A18049 | | |
| Spectrum | | | | | |
| Analyzer | | | | | |
| Analyzer Blue | HP | 85685A | 2926A00983 | CAL 9/5/05 | 9/5/07 |
| Tower RF | | | | | |
| Preselector | | | | | |
| Analyzer Blue | HP | 85650A | 2811A01279 | CAL 4/13/05 | 4/13/07 |
| Tower Quasi- | | | | | |
| Peak Adapter | | | | | |
| Analyzer Silver | HP | 8566B Opt 462 | 3552A22064 | CAL 10/30/06 | 10/30/08 |
| Tower | | | 3638A08608 | | |
| Spectrum | | | | | |
| Analyzer | | | | | |
| Analyzer Silver | HP | 85685A | 2620A00294 | CAL 10/30/06 | 10/30/08 |
| Tower RF | | | | | |
| Preselector | | | | | |
| Analyzer Silver | HP | 85650A | 3303A01844 | CAL 10/30/06 | 10/30/08 |
| Tower Quasi- | | | | | |
| Peak Adapter | | | | | |
| Analyzer Open- | HP | 8449B | 3008A01075 | CAL 8/8/05 | 8/8/07 |
| Frame Tower | | | | | |
| Preamplifier | | | | | |
| Antenna: | Electro-Metrics | BIA-25 | 1171 | CAL 4/29/05 | 4/29/07 |
| Biconnical | | | | | |
| Antenna: | Eaton | 94455-1 | 1096 | CAL 10/11/06 | 10/11/08 |
| Biconnical | | | | | |
| Antenna: | Eaton | 94455-1 | 1057 | CAL 12/12/05 | 12/12/07 |
| Biconnical | | | | | |

APPLICANT: AUTOSTART FCC ID: NAHSHL101



Page 6 of 9



TEST PROCEDURE

General: This report shall NOT be reproduced except in full without the written approval of TIMCO ENGINEERING, INC.

Radiation Interference: The test procedure used was ANSI Standard C63.4-2003 using a spectrum analyzer with a pre-selector. The bandwidth of the spectrum analyzer was 100 kHz with an appropriate sweep speed. The analyzer was calibrated in dB above a microvolt at the output of the antenna. The video bandwidth was always greater than or equal to the RBW.

Formula Of Conversion Factors: The Field Strength at 3m was established by adding the meter reading of the spectrum analyzer (which is set to read in units of dBuV) to the antenna correction factor supplied by the antenna manufacturer. The antenna correction factors are stated in terms of dB. The gain of the Preselector was accounted for in the Spectrum Analyzer Meter Reading.

Example:

Freq (MHz) Meter Reading + ACF + CL = FS

33 20 dBuV + 10.36 dB/m +0.40 dB = 30.36 dBuV/m @ 3m

ANSI C63.4-2003 Section 10.1.7 Measurement Procedures: The unit under test was placed on a table 80 cm high and with dimensions of 1mby 1.5m. The table used for radiated measurements is capable of continuous rotation. When an emission was found, the table was rotated to produce the maximum signal strength. At this point, the antenna was raised and lowered from 1m to 4m. The antenna was placed in both the horizontal and verticals planes.

If powerline conducted testing was required for this device, the situation was similar for the conducted measurement except that the table did not rotate. The EUT was setup as described in ANSI C63.4-2003 with the EUT 40 cm from the vertical ground wall.

APPLICANT: AUTOSTART FCC ID: NAHSHL101





RADIATED SPURIOUS EMISSIONS

Rules Part No.: 15.109

Requirements:

| Frequency | Limits | | | |
|-----------|---------------------------------|--|--|--|
| 30 – 88 | 40.0 dBμV/m measured @ 3 meters | | | |
| 80 – 216 | 43.5 dBμV/m measured @ 3 meters | | | |
| 216 – 960 | 46.0 dBμV/m measured @ 3 meters | | | |
| Above 960 | 54.0 dBµV/m measured @ 3 meters | | | |

Test Procedure: The procedure used was ANSI C63.4-2003. The frequency was scanned from 30 MHz to 1.0 GHz. When an emission was found, the table was rotated to produce the maximum signal strength.

Test Data:

| Tuned | Emission | Meter | Ant | Coax | Correction | Field | Margin |
|-----------|-----------|---------|-----|------|------------|----------|--------|
| Frequency | Frequency | Reading | Po1 | Loss | Factor | Strength | dB |
| MHz | MHz | dBuV | | dB | dB | dBuV/m | |
| 433.9 | 433.50 | 24.7 | H | 1.23 | 16.61 | 42.54 | 3.46 |
| 433.9 | 433.50 | 25.0 | V | 1.23 | 16.17 | 42.40 | 3.60 |
| 433.9 | 867.10 | 3.5 | H | 1.93 | 22.94 | 28.37 | 17.63 |
| 433.9 | 867.10 | 4.8 | V | 1.93 | 22.40 | 29.13 | 16.87 |

APPLICANT: AUTOSTART FCC ID: NAHSHL101





POWER LINE CONDUCTED INTERFERENCE

Rules Part No.: Part 15.107

Requirements:

| Frequency (MHz) | Quasi Peak Limits (dBuv) | Average Limits (dBuV) |
|--------------------|-----------------------------|--------------------------|
| 0.15 - 0.5 | 66 – 56 | 56 – 46 |
| 0.5 - 5.0 | 56 | 46 |
| 5.0 – 30 | 60 | 50 |

Test Procedure: ANSI Standard C63.4-2003. The spectrum was scanned from 0.15 to

30 MHz.

Test Data: Not applicable.


APPLICANT: AUTOSTART FCC ID: NAHSHL101

REPORT: 3386AUT6TestReport.doc Page 8 of 9





RADIATED EMISSIONS TEST SETUP PHOTO



APPLICANT: AUTOSTART FCC ID: NAHSHL101