

Advanced  
Compliance Laboratory

6 Randolph Way  
Hillsborough, NJ 08844  
Tel: (908) 927 9288  
Fax: (908) 927 0728

## ELECTROMAGNETIC EMISSION COMPLIANCE REPORT

of

Proforce Debris Blower  
MODEL: 44538 & 07066

FCC ID: OF7PFB1

December 10, 2008

This report concerns (check one): Original grant <input checked="" type="checkbox"/> Class II change <input type="checkbox"/>	
Equipment type: <u>TRANSMITTER</u>	
Deferred grant requested per 47 CF 0.457(d)(1)(ii)?      yes <input type="checkbox"/> no <input checked="" type="checkbox"/>	
If yes, defer until: _____ (date)	
Company agrees to notify the Commission by _____ (date)	
of the intended date of announcement of the product so that the grant can be issued on that date.	
Transition Rules Request per 15.37?      yes <input type="checkbox"/> no <input checked="" type="checkbox"/>	
If no, assumed Part 15, Subpart B for unintentional radiators - the new 47 CFR [10-1-90 Edition] provision.	
Report prepared for:	THE TORO COMPANY
Report prepared by:	Advanced Compliance Lab
Report number:	0048-080206-02



The test result in this report IS supported and covered by the NVLAP accreditation

# Table of Contents

**Report Cover Page ..... 1**

**Table of Contents ..... 2**

**Figures ..... 3**

**1. GENERAL INFORMATION ..... 4**

**1.1 Verification of Compliance ..... 4**

**1.2 Equipment Modifications ..... 5**

**1.3 Product Information ..... 6**

**1.4 Test Methodology ..... 6**

**1.5 Test Facility ..... 6**

**1.6 Test Equipment ..... 6**

**1.7 Statement of the Document Use ..... 7**

**2. PRODUCT LABELING ..... 8**

**3. SYSTEM TEST CONFIGURATION ..... 9**

**3.1 Justification ..... 9**

**3.2 Special Accessories ..... 9**

**3.3 Configuration of Tested System ..... 9**

**4. SYSTEM SCHEMATICS ..... 12**

**5. RADIATED EMISSION DATA ..... 13**

**5.1 Field Strength Calculation ..... 13**

**5.2 Test Methods and Conditions ..... 13**

**5.3 Test Data ..... 13**

**5.4 Occupied Bandwidth ..... 15**

**6. PHOTOS OF TESTED EUT ..... 18**

## Figures

<b>Figure 2.1 FCC ID Label.....</b>	<b>8</b>
<b>Figure 2.2 Location of Label on Bottom of the EUT.....</b>	<b>8</b>
<b>Figure 3.1 Radiated Test Setup .....</b>	<b>10</b>
<b>Figure 3.2 Radiated Test Setup, X-Axis .....</b>	<b>10</b>
<b>Figure 3.3 Radiated Test Setup Y-Axis .....</b>	<b>11</b>
<b>Figure 3.4 Radiated Test Setup Z-Axis.....</b>	<b>11</b>
<b>Figure 4.1 EUT Schematics.....</b>	<b>12</b>
<b>Figure 5.1 Pulse Train Timing .....</b>	<b>17</b>
<b>Figure 5.2 Occupied Bandwidth .....</b>	<b>17</b>
<b>Figure 6.1 Front View .....</b>	<b>18</b>
<b>Figure 6.2 Open View.....</b>	<b>19</b>
<b>Figure 6.3 Component Side.....</b>	<b>20</b>
<b>Figure 6.4 Foil Side.....</b>	<b>21</b>

## 1. GENERAL INFORMATION

### 1.1 Verification of Compliance

EUT: TRANSMITTER

Model: 44538 & 07066 ( electronically identical)

Applicant: THE TORO COMPANY

Test Type: FCC Part 15C CERTIFICATION

Result: PASS

Tested by: ADVANCED COMPLIANCE LAB


Test Date: 02/19/2008 - 02/29/2008

Report Number: 0048-080206-02

The above equipment was tested by Advanced Compliance Laboratory for compliance with the requirement set forth in the FCC rules and regulations Part 15, subpart C. This said equipment in the configuration described in the report, shows the maximum emission levels emanating from equipment are within the compliance requirements.

The estimated uncertainty of the test result is given as following. The method of uncertainty calculation is provided in Advanced Compliance Lab. Doc. No. 0048-01-01.

	Prob. Dist.	Uncertainty(dB)	Uncertainty(dB)	Uncertainty(dB)
		30-1000MHz	1-6.5GHz	Conducted
Combined Std. Uncertainty $u_c$	norm.	$\pm 2.36$	$\pm 2.99$	$\pm 1.83$

  
 \_\_\_\_\_  
 Wei Li  
 Lab Manager  
 Advanced Compliance Lab

Date: December 10, 2008

## **1.2 Equipment Modifications**

N/A

### 1.3 Product Information

#### System Configuration

ITEM	DESCRIPTION	FCC ID	CABLE
Product	TRANSMITTER	OF7PFB1	
Housing	PLASTICS		
Power Supply	BATTERY 4.5VDC		
Clock/OSC Freq.	433.87 MHz		
Device Type	Periodic Operation		
RX	DoC		

(1) EUT submitted for grant.

### 1.4 Test Methodology

Radiated tests were performed according to the procedures in ANSI C63.4-2003 at an antenna to EUT distance of 3 meters.

### 1.5 Test Facility

The open area test site and conducted measurement facility used to collect the radiated and conducted data are located at Hillsborough, New Jersey. This site has been accepted by FCC to perform measurements under Part 15 or 18 in a letter dated May 19, 1997 (Refer to: 31040/PRV 1300F2). The NVLAP Lab code for accreditation of FCC EMC Test Method is: 200101-0.

### 1.6 Test Equipment

Manufacture	Model	Serial No.	Description	Last Cal dd/mm/yy	Cal Due dd/mm/yy
Hewlett-Packard	HP8546A	3448A00290	EMI Receiver	12/01/08	12/01/09
EMCO	3104C	9307-4396	20-300MHz Biconical Antenna	12/02/08	12/02/09
EMCO	3146	9008-2860	200-1000MHz Log-Periodic Antenna	09/02/08	09/02/09
Fischer Custom	LISN-2	900-4-0008	Line Impedance Stabilization Networks	23/08/08	23/08/09
Fischer Custom	LISN-2	900-4-0009	Line Impedance Stabilization Networks	23/08/08	23/08/09
EMCO	6502	2665	10KHz-30MHz Active Loop Antenna	27/02/08	27/02/09
EMCO	3115	4945	Double Ridge Guide Horn Antenna	11/08/08	11/08/09

All Test Equipment Used are Calibrated Traceable to NIST Standards.

### **1.7 Statement for the Document Use**

This report shall not be reproduced except in full, without the written approval of the laboratory. And this report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government.

## 2. PRODUCT LABELING

**FCC ID: OF7PFB1**

This device complies with part 15 of the FCC Rules. Operating is subject to the following two conditions:  
(1) This device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation.

**Fig 2.1 FCC Label ( Statement shown in user manual)**



**Fig 2.2 Location of the Label**



### **3. SYSTEM TEST CONFIGURATION**

#### **3.1 Justification**

The system was configured for testing in a typical fashion (as a customer would normally use it). Its antenna is integrated on PCB and the transmission will be deactivated with 5s (or immediately) after the operation button is released.

Testing was performed as EUT was operated continuously. Fresh batteries are used during the test in order to generate maximum emission from EUT.

#### **3.2 Special Accessories**

N/A

#### **3.3 Configuration of Tested System**

Figure 3.1 and Figure 3.3 illustrate this system, which is tested standing along.



**Figure 3.1 Radiated Test Setup**



**Figure 3.2 Radiated Test Setup – X axis**



**Figure 3.3 Radiated Test Setup – Y axis**



**Figure 3.4 Radiated Test Setup – Z axis**

## **4. SYSTEM SCHEMATICS**

**See attachment.**

**Figure 4.1 System Schematics**

## 5. RADIATED EMISSION DATA

### 5.1 Field Strength Calculation

The corrected field strength is automatically calculated by EMI Receiver using following:

$$FS = RA + AF + CF + AG$$

where FS: Corrected Field Strength in dB $\mu$ V/m

RA: Amplitude of EMI Receiver before correction in dB $\mu$ V

AF: Antenna Factor in dB/m

CF: Cable Attenuation Factor in dB

AG: Built-in Preamplifier Gain in dB (Stored in receiver as part of the calibration data)

The pulse train timing plots are showed in Figure 5.1.

The maximum average field strength should be 0.3146 of the peak field strength measured. So we use peak value minus 10dB as calculated maximum average field strength.

### 5.2 Test Methods and Conditions

The initial step in collecting radiated data is an EMI Receiver scan of the measurement range 30MHz - 5GHz using peak detector. IF bandwidth is 120KHz and video bandwidth is 300KHz for measuring 30MHz-1GHz. Both bandwidths are 1MHz for above 1GHz measurement.

### 5.3 Test Data

The following data lists the significant emission frequencies, polarity and position, peak reading of the EMI Receiver, calculated average reading, the FCC limit, and the difference between the peak reading and the limit. Explanation of the correction and calculation are given in section 5.1.

Test Personnel:

Tester Signature David Tu

Typed/Printed Name: David Tu

Date: December 10, 2008

**Radiated Test Data @3m**

Frequency (MHz)	Polarity [H or V], Position (X, Y, Z) (1)	Height (m)	Azimuth (Degree)	Peak Reading (dBmV/m)	Calculated Average Reading (dBmV/m)	FCC 3m Limit (dBmV/m)	Difference from Limit (dB)
433.87	H, X(1)	1.6	180	85.6	75.6	80.8(3)	-5.2
867.74	H, X	1.0	270	67.5	57.5	60.8(4)	-3.3
1301.61	H, X	1.2	280	57.2	47.2	54(2)	42.2
1735.48	H, X	1.2	280	43.3	33.3	60.8	-27.5
2169.35	H, X	1.2	330	48.9	38.9	60.8	-21.9
2603.22	H, X	1.2	000	46.1	36.1	60.8	-24.7
433.87	V, X	2.5	330	75.1	65.1	80.8	-15.7
867.74	V, X	1.0	040	64.2	54.2	60.8	-6.6
1301.61	V, X	1.2	350	56.3	46.3	54	-7.7
1735.48	V, X	1.1	000	43.8	33.8	60.8	-27
2169.35	V, X	1.1	000	50.2	40.2	60.8	-20.6
2603.22	V, X	1.0	000	45.8	35.8	60.8	-25
433.87	H, Y	2.1	000	85.2	75.2	80.8	-5.6
867.74	H, Y	1.0	180	66.2	56.2	60.8	-4.6
1301.61	H, Y	1.3	350	57.8	47.8	54	-6.2
1735.48	H, Y	1.3	000	47.9	37.9	60.8	-22.9
2169.35	H, Y	1.3	210	52.6	42.6	60.8	-18.2
2603.22	H, Y	1.3	200	48.2	38.2	60.8	-22.6
433.87	V, Y	2.6	060	81.6	71.6	80.8	-9.2
867.74	V, Y	1.9	120	66.3	56.3	60.8	-4.5
1301.61	V, Y	1.4	270	52.8	42.8	54	-11.2
1735.48	V, Y	1.4	130	45.5	35.5	60.8	-25.3
2169.35	V, Y	1.2	270	48.7	38.7	60.8	-22.1
2603.22	V, Y	1.0	260	46.5	36.5	60.8	-24.3
433.87	H, Z	2.7	000	83.5	73.5	80.8	-7.3
867.74	H, Z	1.1	220	59.1	49.1	60.8	-11.7
1301.61	H, Z	1.4	000	51.6	41.6	54	-12.4
1735.48	H, Z	1.3	010	43.5	33.5	60.8	-27.3
2169.35	H, Z	1.3	000	49.2	39.2	60.8	-21.6
2603.22	H, Z	1.2	190	48.7	38.7	60.8	-22.1
433.87	V, Z	1.2	200	82.9	72.9	80.8	-7.9
867.74	V, Z	1.2	040	69.5	59.5	60.8	-1.3
1301.61	V, Z	1.3	100	58	48	54	-6
1735.48	V, Z	1.1	100	44.5	34.5	60.8	-26.3
2169.35	V, Z	1.2	000	50.4	40.4	60.8	-20.4
2603.22	V, Z	1.2	160	46.1	36.1	60.8	-24.7

- (1) See Figure 3.1, 3.2 and 3.3 for definition of position X-1, Y-2, Z-3.
- (2) Restricted band.
- (3) Fundamental limit is 3750-12500 microvolts/meter linear interpolations (average reading). Per FCC 15.231(a).
- (4) Spurious limit is 375-1250 microvolts/meter linear interpolations (average reading). Per 15.231(a).

#### **5.4 Occupied Bandwidth**

The bandwidth of the emission shall be no wider than 0.25% of the center frequency, in this case, 1.08467MHz( $433.87 \times 0.25\%$ ). Bandwidth is determined at the points 20dB down from the modulated carrier. Figure 5.2 shows the occupied bandwidth plot.

### Commercial Equipment Remote Pulse Train and Duty Cycle Calculation over 100ms Worst Case Window

FCC: OF7PFB1 IC: 3575A-PFB1




Figure 5.1 Pulse Train Timing






Figure 5.2 Occupied Bandwidth