

FCC Radio Test Report

FCC ID: OL3AT10

Report No. : BTL-FCCP-2-2212G057A Equipment : True Wireless Earbuds (TWS)

Model Name : AT10

Brand Name : Alcatel-Lucent Enterprise

Applicant: ALE International

Address : 32, Avenue Kléber – 92700 Colombes – FRANCE

Manufacturer : ALE International

Address : 32, Avenue Kléber – 92700 Colombes – FRANCE

Radio Function : Bluetooth Low Energy

FCC Rule Part(s) : FCC CFR Title 47, Part 15, Subpart C (15.247)

Measurement : ANSI C63.10-2013

Procedure(s)

Date of Receipt : 2023/4/4

Date of Test : 2023/5/17 ~ 2023/5/23

Issued Date : 2023/8/14

The above equipment has been tested and found in compliance with the requirement of the above standards by BTL Inc.

Prepared by : delee

Eddie Lee, Engineer

Approved by : Jerry Chuang, Superviso

BTL Inc.

No.18, Ln. 171, Sec. 2, Jiuzong Rd., Neihu Dist., Taipei City 114, Taiwan

Tel: +886-2-2657-3299 Fax: +886-2-2657-3331 Web: www.newbtl.com Service mail: btl_qa@newbtl.com

Project No.: 2212G057A Page 1 of 63 Report Version: R02



Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **BTL** issued reports.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the **ISO/IEC 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

Project No.: 2212G057A Page 2 of 63 Report Version: R02





CONTENTS REVISION HISTORY 5 SUMMARY OF TEST RESULTS 6 1.1 REFERENCE TEST GUIDANCE 6 1.2 TEST FACILITY 7 1.3 MEASUREMENT UNCERTAINTY 7 1.4 **TEST ENVIRONMENT CONDITIONS** 8 1.5 **DUTY CYCLE** 8 2 **GENERAL INFORMATION** 9 **DESCRIPTION OF EUT** 9 2.1 2.2 **TEST MODES** 11 2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED 12 2.4 SUPPORT UNITS 13 3 AC POWER LINE CONDUCTED EMISSIONS TEST 14 3.1 LIMIT 14 **TEST PROCEDURE** 3.2 14 3.3 **DEVIATION FROM TEST STANDARD** 14 3.4 **TEST SETUP** 15 3.5 **TEST RESULT** 15 4 RADIATED EMISSIONS TEST 16 4.1 LIMIT 16 4.2 **TEST PROCEDURE** 17 4.3 **DEVIATION FROM TEST STANDARD** 17 4.4 **TEST SETUP** 17 **EUT OPERATING CONDITIONS** 4.5 19 4.6 TEST RESULT - BELOW 30 MHZ 19 4.7 TEST RESULT - 30 MHZ TO 1 GHZ 19 4.8 TEST RESULT – ABOVE 1 GHZ 19 5 **BANDWIDTH TEST** 20 APPLIED PROCEDURES / LIMIT 5.1 20 5.2 **TEST PROCEDURE** 20 5.3 **DEVIATION FROM STANDARD** 20 **TEST SETUP** 20 5.4 5.5 **EUT OPERATION CONDITIONS** 20 5.6 **TEST RESULTS** 20 6 **OUTPUT POWER TEST** 21 6.1 APPLIED PROCEDURES / LIMIT 21 **TEST PROCEDURE** 6.2 21 6.3 **DEVIATION FROM STANDARD** 21 6.4 **TEST SETUP** 21 **EUT OPERATION CONDITIONS** 6.5 21 **TEST RESULTS** 21 6.6 POWER SPECTRAL DENSITY TEST 22 7 APPLIED PROCEDURES / LIMIT 7.1 22 7.2 **TEST PROCEDURE** 22 **DEVIATION FROM STANDARD** 7.3 22 7.4 **TEST SETUP** 22 7.5 **EUT OPERATION CONDITIONS** 22



Report No.: BTL-FCCP-2-2212G057A

7.6	TEST	RESULTS	22
8	ANTENN	A CONDUCTED SPURIOUS EMISSION	23
8.1	APPLI	ED PROCEDURES / LIMIT	23
8.2	TEST	PROCEDURE	23
8.3	DEVIA	ATION FROM STANDARD	23
8.4	TEST	SETUP	23
8.5	EUT C	PERATION CONDITIONS	23
8.6	TEST	RESULTS	23
9	LIST OF	MEASURING EQUIPMENTS	24
10	EUT TES	ST PHOTO	26
11	EUT PHO	DTOS	26
A DDENID	13/ A	AC DOWED LINE CONDUCTED EMISSIONS	07
APPEND		AC POWER LINE CONDUCTED EMISSIONS	27
APPEND	IX B	RADIATED EMISSIONS - 30 MHZ TO 1 GHZ	32
APPEND	IX C	RADIATED EMISSIONS - ABOVE 1 GHZ	35
APPEND	IX D	BANDWIDTH	52
APPEND	IX E	OUTPUT POWER	55
APPEND	IX F	POWER SPECTRAL DENSITY TEST	57
APPEND	IX G	ANTENNA CONDUCTED SPURIOUS EMISSION	59

Project No.: 2212G057A Page 4 of 63 Report Version: R02



REVISION HISTORY

Report No.	Version	Description	Issued Date	Note
BTL-FCCP-2-2212G057A	R00	Original Report.	2023/6/19	Invalid
BTL-FCCP-2-2212G057A	R01	Revised report to address TCB's comments.	2023/8/1	Invalid
BTL-FCCP-2-2212G057A	R02	Revised report to address TCB's comments.	2023/8/14	Valid

Project No.: 2212G057A Page 5 of 63 Report Version: R02



1 SUMMARY OF TEST RESULTS

Test procedures according to the technical standards.

Standard(s) Section	Description	Test Result	Judgement	Remark
15.207	AC Power Line Conducted Emissions	APPENDIX A	Pass	
15.205 15.209 15.247(d)	Radiated Emissions	APPENDIX B APPENDIX C	Pass	
15.247(a)(2)	Bandwidth	APPENDIX D	Pass	
15.247(b)(3)	Output Power	APPENDIX E	Pass	
15.247(e)	Power Spectral Density	APPENDIX F	Pass	
15.247(d)	Antenna conducted Spurious Emission	APPENDIX G	Pass	
15.203	Antenna Requirement		Pass	NOTE (3)

NOTE

- (1) "N/A" denotes test is not applicable in this Test Report.
- (2) The report format version is TP.1.1.1.
- (3) The EUT has internal antenna, which was permanently attached, fulfill the requirement of this section. Please refer to the EUT photos.

1.1 REFERENCE TEST GUIDANCE

KDB 558074 D01 15.247 Meas Guidance v05r02

Project No.: 2212G057A Page 6 of 63 Report Version: R02





4	2	TFST		^…	171/
7	٠,		ı ⊢Δ:	('	1 I Y

The test locations state The test location(s) use No. 68-1, Ln. 169, Sec (FCC DN: TW0659)	ed to	collect the test da	ata in	this report are:			
` ⊠ C05		CB08		CB11	\boxtimes	SR10	SR11
No. 72, Ln. 169, Sec. 2 (FCC DN: TW0659)	2, Dat	ong Rd., Xizhi Di	st., N	ew Taipei City 22	1, Ta	iwan	
□ C06	\boxtimes	CB21		CB22			

1.3 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement $\mathbf{y} \pm \mathbf{U}$, where expanded uncertainty \mathbf{U} is based on a standard uncertainty multiplied by a coverage factor of $\mathbf{k} = \mathbf{2}$, providing a level of confidence of approximately 95 %. The measurement instrumentation uncertainty considerations contained in CISPR 16-4-2. The BTL measurement uncertainty is less than the CISPR 16-4-2 \mathbf{U}_{cispr} requirement.

A. AC power line conducted emissions test:

Test Site	Method	Measurement Frequency Range	U (dB)
Test Site	Method	Measurement Frequency Kange	U (ub)
C05	CISPR	150 kHz ~ 30MHz	3.44

B. Radiated emissions test:

THIS COLOT COLOT					
Test Site	Measurement Frequency Range	U (dB)			
	0.03 GHz ~ 0.2 GHz	4.17			
	0.2 GHz ~ 1 GHz	4.72			
CB21	1 GHz ~ 6 GHz	5.21			
CB21	6 GHz ~ 18 GHz	5.51			
	18 GHz ~ 26 GHz	3.69			
	26 GHz ~ 40 GHz	4.23			

C. Conducted test:

itest.					
Test Item	U (dB)				
Occupied Bandwidth	0.5334				
Output power	0.3669				
Power Spectral Density	0.6591				
Conducted Spurious emissions	0.5416				
Conducted Band edges	0.5348				

NOTE:

Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.

Project No.: 2212G057A Page 7 of 63 Report Version: R02




1.4 TEST ENVIRONMENT CONDITIONS

Test Item	Environment Condition	Test Voltage	Tested by
AC Power Line Conducted Emissions	21 °C, 58 %	AC 120V	Cora Lin
Radiated emissions below 1 GHz	Refer to data	AC 120V	Mark Wang
Radiated emissions above 1 GHz	Refer to data	AC 120V	Mark Wang
Bandwidth	22.1 °C, 58 %	DC 3.7V	Jay Tien
Output Power	22.1 °C, 58 %	DC 3.7V	Jay Tien
Power Spectral Density	22.1 °C, 58 %	DC 3.7V	Jay Tien
Antenna conducted Spurious Emission	22.1 °C, 58 %	DC 3.7V	Jay Tien

1.5 DUTY CYCLE

If duty cycle is \geq 98 %, duty factor is not required. If duty cycle is < 98 %, duty factor shall be considered.

	Remark	Delta 1			Delta 2	On Time/Period	10 log(1/Duty Cycle)
Г	Modo	ON	Numbers	On Time (B)	Period (ON+OFF)	Duty Cycle	Duty Factor
	Mode	(ms)	(ON)	(ms)	(ms)	(%)	(dB)
	BLE (1 Mbps)	0.390	1	0.390	0.620	62.90%	2.01
Г	BLE (2 Mbps)	0.210	1	0.210	0.620	33.87%	4.70





2 GENERAL INFORMATION

2.1 DESCRIPTION OF EUT

Equipment	True Wireless Earbuds (TWS)
Model Name	AT10
Brand Name	Alcatel-Lucent Enterprise
Model Difference	N/A
Power Source	DC voltage supplied from battery.
Power Rating	DC 3.7V
Products Covered	N/A
HVIN	PCB_EPA399A_V03
FVIN	V3.0.8
Operation Band	2400 MHz ~ 2483.5 MHz
Operation Frequency	2402 MHz ~ 2480 MHz
Modulation Technology	GFSK
Transfer Rate	1 Mbps, 2 Mbps
Output Power Max.	1 Mbps: 3.59 dBm (0.0023 W)
•	2 Mbps: 3.22 dBm (0.0021 W)
Operating Software	RTLBTAPP V5.2.3.60
Test Model	AT10
Sample Status	Engineering Sample
EUT Modification(s)	N/A

NOTE:

(1) The above EUT information is declared by manufacturer and for more detailed features description, please refers to the manufacturer's specifications or user's manual.

(2) Channel List:

Channel	Frequency (MHz)	Channel	Frequency (MHz)
00	2402	20	2442
01	2404	21	2444
02	2406	22	2446
03	2408	23	2448
04	2410	24	2450
05	2412	25	2452
06	2414	26	2454
07	2416	27	2456
08	2418	28	2458
09	2420	29	2460
10	2422	30	2462
11	2424	31	2464
12	2426	32	2466
13	2428	33	2468
14	2430	34	2470
15	2432	35	2472
16	2434	36	2474
17	2436	37	2476
18	2438	38	2478
19	2440	39	2480

Project No.: 2212G057A Page 9 of 63 Report Version: R02





(3) Table for Filed Antenna:

Antenna	Brand	Part number	Туре	Connector	Gain (dBi)
L	Shenzhen cape deep communication technology co., LTD	EPA399A-0015	FPC	N/A	-2.59
R	Shenzhen cape deep communication technology co., LTD	EPA399A-0016	FPC	N/A	-2.91

NOTE: Antenna gain higher is used for testing.

- (4) The above Antenna information are derived from the antenna data sheet provided by manufacturer and for more detailed features description, please refer to the manufacturer's specifications, the laboratory shall not be held responsible.
- (5) The left earphone and right earphone have the same circuit mechanism, PCB layout and placement. So we select high antenna gain for test.

Project No.: 2212G057A Page 10 of 63 Report Version: R02



2.2 TEST MODES

Test Items	Test mode	Channel	Note
AC power line conducted emissions	Normal/Idle	-	-
Transmitter Radiated Emissions (below 1GHz)	BLE 5.0 / 1 Mbps	19	-
Transmitter Radiated Emissions	BLE 5.0 / 1/2 Mbps	00/39	Bandedge
(above 1GHz)	BLE 5.0 / 1/2 Mbps	00/19/39	Harmonic
Bandwidth	BLE 5.0 / 1/2 Mbps	00/19/39	-
Output Power	BLE 5.0 / 1/2 Mbps	00/19/39	-
Power Spectral Density	BLE 5.0 / 1/2 Mbps	00/19/39	-
Antenna conducted Spurious Emission	BLE 5.0 / 1/2 Mbps	00/19/39	-

NOTE:

- (1) For radiated emission band edge test, both Vertical and Horizontal are evaluated, but only the worst case (Vertical) is recorded.
- (2) All X, Y and Z axes are evaluated, but only the worst case (X axis) is recorded.
- (3) The EUT supports both BLE 4.0 and 5.0, we will pick BLE 5.0 for testing.


Project No.: 2212G057A Page 11 of 63 Report Version: R02




2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED

Equipment letters and Cable numbers refer to item numbers described in the tables of clause 2.4.

AC power line conducted emissions



Radiated Emissions





2.4 SUPPORT UNITS

Item	Equipment	Brand	Model No.	Series No.	Remarks
Α	ADAPTER	SAMSUNG	EP-TA800	R37M8JV5R21HM3	Furnished by test lab.
В	ADAPTER	Xlaomi	AD652G	N/A	Furnished by test lab.

Item	Shielded	Ferrite Core	Length	Cable Type	Remarks
1	No	No	1.5m	USB type-C to type-C	Furnished by test lab.
2	No	No	1m	TYPE-C To USB	Furnished by test lab.

Project No.: 2212G057A Page 13 of 63 Report Version: R02



3 AC POWER LINE CONDUCTED EMISSIONS TEST

3.1 LIMIT

Frequency	Limit (dBμV)
(MHz)	Quasi-peak	Average
0.15 - 0.5	66 - 56 *	56 - 46 *
0.50 - 5.0	56	46
5.0 - 30.0	60	50

NOTE:

- (1) The tighter limit applies at the band edges.
- (2) The limit of " * " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.
- (3) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor (if use)

Margin Level = Measurement Value - Limit Value

Calculation example:

Reading Level		Correct Factor		Measurement Value
38.22	+	3.45	=	41.67

Measurement Value		Limit Value		Margin Level
41.67	-	60	=	-18.33

The following table is the setting of the receiver.

Receiver Parameter	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 KHz

3.2 TEST PROCEDURE

- a. The EUT was placed 0.8 m above the horizontal ground plane with the EUT being connected to the power mains through a line impedance stabilization network (LISN).
 - All other support equipment were powered from an additional LISN(s).
 - The LISN provides 50 Ohm/50uH of impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle to keep the cable above 40 cm.
- c. Excess I/O cables that are not connected to a peripheral shall be bundled in the center.
 - The end of the cable will be terminated, using the correct terminating impedance.
 - The overall length shall not exceed 1 m.
- d. The LISN is spaced at least 80 cm from the nearest part of the EUT chassis.
- e. For the actual test configuration, please refer to the related Item EUT TEST PHOTO.

NOTE:

- (1) In the results, each reading is marked as Peak, QP or AVG per the detector used. BW=9 kHz (6 dB Bandwidth)
- (2) All readings are Peak unless otherwise stated QP or AVG in column of Note. Both the QP and the AVG readings must be less than the limit for compliance.


3.3 DEVIATION FROM TEST STANDARD

No deviation.

Project No.: 2212G057A Page 14 of 63 Report Version: R02



3.4 TEST SETUP



3.5 TEST RESULT

Please refer to the APPENDIX A.





4 RADIATED EMISSIONS TEST

4.1 LIMIT

In case the emission fall within the restricted band specified on 15.205, then the 15.209 limit in the table below has to be followed.

LIMITS OF RADIATED EMISSIONS MEASUREMENT (9 kHz to 1000 MHz)

Frequency	Field Strength	Measurement Distance
(MHz)	(microvolts/meter)	(meters)
0.009~0.490	2400/F(KHz)	300
0.490~1.705	24000/F(KHz)	30
1.705~30.0	30	30
30~88	100	3
88~216	150	3
216~960	200	3
960~1000	500	3

LIMITS OF RADIATED EMISSIONS MEASUREMENT (Above 1000 MHz)

Frequency	Radiated (dBu	Measurement Distance	
(MHz)	Peak	Average	(meters)
Above 1000	74	54	3

NOTE:

- (1) The limit for radiated test was performed according to FCC CFR Title 47, Part 15, Subpart C.
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)

Margin Level = Measurement Value - Limit Value

Calculation example:

Reading Level		Correct Factor		Measurement Value
41.91	+	-8.36	=	33.55

Measurement Value		Limit Value		Margin Level
33.55	•	43.50	=	-9.95

Spectrum Parameter	Setting	
Attenuation	Auto	
Start Frequency	1000 MHz	
Stop Frequency	10th carrier harmonic	
RBW / VBW	1MHz / 3MHz for Peak,	
(Emission in restricted band)	1MHz / 1/T for Average	

Mode	VBW(Hz)
BLE (1M)	2700
BLE (2M)	2700

Spectrum Parameter	Setting
Attenuation	Auto
Start ~ Stop Frequency	9KHz~90KHz for PK/AVG detector
Start ~ Stop Frequency	90KHz~110KHz for QP detector
Start ~ Stop Frequency	110KHz~490KHz for PK/AVG detector
Start ~ Stop Frequency	490KHz~30MHz for QP detector
Start ~ Stop Frequency	30MHz~1000MHz for QP detector

Project No.: 2212G057A Page 16 of 63 Report Version: R02




4.2 TEST PROCEDURE

- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(below 1GHz)
- b. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 1.5 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(above 1GHz)
- c. The height of the equipment or of the substitution antenna shall be 0.8 m or 1.5 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- d. For each suspected emission, the EUT was arranged to its worst case and then the antenna was tuned to heights find the maximum reading (used Bore sight function).
- e. The receiver system was set to peak and average detect function and specified bandwidth with maximum hold mode when the test frequency is above 1GHz.
- f. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- g. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform. (below 1GHz)
- h. All readings are Peak Mode value unless otherwise stated AVG in column of Note. If the Peak Mode Measured value compliance with the Peak Limits and lower than AVG Limits, the EUT shall be deemed to meet both Peak & AVG Limits and then only Peak Mode was measured, but AVG Mode didn't perform. (above 1GHz)
- i. For the actual test configuration, please refer to the related Item EUT TEST PHOTO.
- j. In the Radiation bandedge test, the software was automatically obtained the maximum emission point in 2310-2390 MHz and 2483.5-2500 MHz.


4.3 DEVIATION FROM TEST STANDARD

No deviation.


4.4 TEST SETUP







Above 1 GHz







4.5 EUT OPERATING CONDITIONS

The EUT was programmed to be in continuously transmitting mode.

4.6 TEST RESULT - BELOW 30 MHZ

There were no emissions found below 30 MHz within 20 dB of the limit.

4.7 TEST RESULT - 30 MHZ TO 1 GHZ

Please refer to the APPENDIX B.

4.8 TEST RESULT - ABOVE 1 GHZ

Please refer to the APPENDIX C.

NOTE:

(1) No limit: This is fundamental signal, the judgment is not applicable. For fundamental signal judgment was referred to Peak output test.

Project No.: 2212G057A Page 19 of 63 Report Version: R02



5 BANDWIDTH TEST

5.1 APPLIED PROCEDURES / LIMIT

Section	Test Item	Limit	Frequency Range (MHz)	Result	
15.247(a)(2)	Bandwidth	>= 500KHz	2400-2483.5	PASS	
15.247 (a)(2)	Bandwidth	(6dB bandwidth)	2400-2463.5	PASS	

5.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting: RBW= 100KHz, VBW=300KHz, Sweep time = 2.5 ms.

5.3 DEVIATION FROM STANDARD

No deviation.

5.4 TEST SETUP



5.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 3.5 unless otherwise a special operating condition is specified in the follows during the testing.

5.6 TEST RESULTS

Please refer to the APPENDIX D.

Project No.: 2212G057A Page 20 of 63 Report Version: R02



6 OUTPUT POWER TEST

6.1 APPLIED PROCEDURES / LIMIT

Section	Test Item	Limit	Frequency Range (MHz)	Result
15.247(b)(3)	Maximum Output Power	1 1 watt or 30dBm 2400-2483 5		PASS


6.2 TEST PROCEDURE

- a. The EUT was directly connected to the power meter and antenna output port as show in the block diagram below,
- b. The maximum peak conducted output power was performed in accordance with FCC KDB 558074 D01 15.247 Meas Guidance.

6.3 DEVIATION FROM STANDARD

No deviation.

6.4 TEST SETUP



6.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 3.5 unless otherwise a special operating condition is specified in the follows during the testing.

6.6 TEST RESULTS

Please refer to the APPENDIX E.

Project No.: 2212G057A Page 21 of 63 Report Version: R02

Report No.: BTL-FCCP-2-2212G057A

7 POWER SPECTRAL DENSITY TEST

7.1 APPLIED PROCEDURES / LIMIT

Section	Test Item	Limit	Frequency Range (MHz)	Result
15.247(e)	Power Spectral Density	8 dBm (in any 3KHz)	2400-2483.5	PASS

7.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting: RBW=3KHz, VBW=10 KHz, Sweep time = auto.

7.3 DEVIATION FROM STANDARD

No deviation.

7.4 TEST SETUP



7.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 3.5 unless otherwise a special operating condition is specified in the follows during the testing.

7.6 TEST RESULTS

Please refer to the APPENDIX F.

Project No.: 2212G057A Page 22 of 63 Report Version: R02



8 ANTENNA CONDUCTED SPURIOUS EMISSION

8.1 APPLIED PROCEDURES / LIMIT

In any 100 kHz bandwidth outside the frequency band in which the spread spectrum or digitally modulated device is operating, the RF power that is produced shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of the desired power, based on either an RF conducted or a radiated measurement, provided that the transmitter demonstrates compliance with the peak conducted power limits.

8.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting: RBW= 100KHz, VBW=300KHz, Sweep time = 10 ms.

8.3 DEVIATION FROM STANDARD

No deviation.

8.4 TEST SETUP



8.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 3.5 unless otherwise a special operating condition is specified in the follows during the testing.

8.6 TEST RESULTS

Please refer to the APPENDIX G.

Project No.: 2212G057A Page 23 of 63 Report Version: R02



9 LIST OF MEASURING EQUIPMENTS

	AC Power Line Conducted Emissions						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until	
1	TWO-LINE V-NETWORK	R&S	ENV216	101521	2022/9/28	2023/9/27	
2	Test Cable	EMCI	EMCRG58-BM-B M-9000	220331	2023/3/30	2024/3/29	
3	EMI Test Receiver	R&S	ESR 7	101433	2022/11/16	2023/11/15	
4	Measurement Software	EZ	EZ_EMC (Version NB-03A1-01)	N/A	N/A	N/A	

	Radiated Emissions							
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until		
1	Preamplifier	EMCI	EMC330N	980850	2022/9/19	2023/9/18		
2	Preamplifier	EMCI	EMC118A45SE	980819	2023/3/7	2024/3/6		
3	Pre-Amplifier	EMCI	EMC184045SE	980907	2022/9/28	2023/9/27		
4	Preamplifier	EMCI	EMC001340	980579	2022/9/30	2023/9/29		
5	Test Cable	EMCI	EMC104-SM-SM- 1000	220319	2023/3/14	2024/3/13		
6	Test Cable	EMCI	EMC104-SM-SM- 3000	220322	2023/3/14	2024/3/13		
7	Test Cable	EMCI	EMC104-SM-SM- 7000	220324	2023/3/14	2024/3/13		
8	EXA Signal Analyzer	keysight	N9020B	MY57120120	2023/2/24	2024/2/23		
9	Loop Ant	Electro-Metrics	EMCI-LPA600	291	2022/9/19	2023/9/18		
10	Horn Antenna	RFSPIN	DRH18-E	211202A18EN	2023/5/12	2024/5/11		
11	Horn Ant	Schwarzbeck	BBHA 9170D	1136	2023/5/12	2024/5/11		
12	Log-bicon Antenna	Schwarzbeck	VULB9168	1369	2023/5/9	2024/5/8		
13	6dB Attenuator	EMCI	EMCI-N-6-06	AT-06001	2023/5/9	2024/5/8		
14	Test Cable	EMCI	EMC101G-KM-K M-3000	220329	2023/3/14	2024/3/13		
15	Test Cable	EMCI	EMC102-KM-KM- 1000	220327	2023/3/14	2024/3/13		
16	Measurement Software	EZ	EZ_EMC (Version NB-03A1-01)	N/A	N/A	N/A		

	Bandwidth						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until	
1	Spectrum Analyzer	R&S	FSP 40	100129	2022/10/7	2023/10/6	

	Output Power						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until	
1	Power Meter	Keysight	8990B	MY51000517	2023/3/15	2024/3/14	
2	Power Sensor	Keysight	N1923A	MY58310005	2023/3/15	2024/3/14	



Power Spectral Density							
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until	
1	Spectrum Analyzer	R&S	FSP 40	100129	2022/10/7	2023/10/6	

Antenna conducted Spurious Emission							
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until	
1	Spectrum Analyzer	R&S	FSP 40	100129	2022/10/7	2023/10/6	

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.





10 EUT TEST PHOTO
Please refer to document Appendix No.: TP-2212G057A-FCCP-1 (APPENDIX-TEST PHOTOS).
11 EUT PHOTOS
Please refer to document Appendix No.: EP-2212G057A-1 (APPENDIX-EUT PHOTOS).

Project No.: 2212G057A Page 26 of 63 Report Version: R02




APPENDIX A	AC POWER LINE CONDUCTED EMISSIONS

Project No.: 2212G057A Page 27 of 63 Report Version: R02



Test Mode	Normal	Tested Date	2023/5/17
Test Frequency	-	Phase	Line




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1522	41.95	9.66	51.61	65.88	-14.27	QP	
2		0.1522	22.71	9.66	32.37	55.88	-23.51	AVG	
3		0.5055	30.11	9.63	39.74	56.00	-16.26	QP	
4	*	0.5055	25.07	9.63	34.70	46.00	-11.30	AVG	
5		1.1220	17.60	9.64	27.24	56.00	-28.76	QP	
6		1.1220	9.64	9.64	19.28	46.00	-26.72	AVG	
7		3.0570	17.65	9.69	27.34	56.00	-28.66	QP	
8		3.0570	9.15	9.69	18.84	46.00	-27.16	AVG	
9		10.5248	14.41	9.81	24.22	60.00	-35.78	QP	
10		10.5248	7.31	9.81	17.12	50.00	-32.88	AVG	
11		27.5370	-1.30	9.94	8.64	60.00	-51.36	QP	
12		27.5370	-3.97	9.94	5.97	50.00	-44.03	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Test Mode	Normal	Tested Date	2023/5/17
ĺ	Test Frequency	-	Phase	Neutral




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1	*	0.1522	41.88	9.67	51.55	65.88	-14.33	QP	
2		0.1522	22.21	9.67	31.88	55.88	-24.00	AVG	
3		0.3772	27.57	9.64	37.21	58.34	-21.13	QP	
4		0.3772	11.16	9.64	20.80	48.34	-27.54	AVG	
5		0.6945	14.24	9.64	23.88	56.00	-32.12	QP	
6		0.6945	4.44	9.64	14.08	46.00	-31.92	AVG	
7		3.1043	10.40	9.70	20.10	56.00	-35.90	QP	
8		3.1043	4.93	9.70	14.63	46.00	-31.37	AVG	
9		10.5045	9.25	9.85	19.10	60.00	-40.90	QP	
10		10.5045	4.07	9.85	13.92	50.00	-36.08	AVG	
11		28.8060	0.17	10.17	10.34	60.00	-49.66	QP	
12		28.8060	-2.45	10.17	7.72	50.00	-42.28	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



Ī	Test Mode	Idle	Tested Date	2023/5/17
	Test Frequency	-	Phase	Line




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1		0.1522	41.76	9.66	51.42	65.88	-14.46	QP	
2		0.1522	22.59	9.66	32.25	55.88	-23.63	AVG	
3		0.5055	30.11	9.63	39.74	56.00	-16.26	QP	
4	*	0.5055	25.07	9.63	34.70	46.00	-11.30	AVG	
5		1.6485	17.84	9.68	27.52	56.00	-28.48	QP	
6		1.6485	9.43	9.68	19.11	46.00	-26.89	AVG	
7		3.5408	17.03	9.69	26.72	56.00	-29.28	QP	
8		3.5408	8.87	9.69	18.56	46.00	-27.44	AVG	
9		10.0028	16.06	9.81	25.87	60.00	-34.13	QP	
10		10.0028	8.80	9.81	18.61	50.00	-31.39	AVG	
11		28.1220	-1.07	9.95	8.88	60.00	-51.12	QP	
12		28.1220	-3.63	9.95	6.32	50.00	-43.68	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.




Test Mode	Idle	Tested Date	2023/5/17
Test Frequency	-	Phase	Neutral



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV	dBuV	dB	Detector	Comment
1	*	0.1522	41.74	9.67	51.41	65.88	-14.47	QP	
2		0.1522	22.09	9.67	31.76	55.88	-24.12	AVG	
3		0.3750	27.57	9.64	37.21	58.39	-21.18	QP	
4		0.3750	10.90	9.64	20.54	48.39	-27.85	AVG	
5		0.5257	25.50	9.64	35.14	56.00	-20.86	QP	
6		0.5257	12.38	9.64	22.02	46.00	-23.98	AVG	
7		2.1998	10.16	9.71	19.87	56.00	-36.13	QP	
8		2.1998	4.06	9.71	13.77	46.00	-32.23	AVG	
9		10.4010	8.74	9.84	18.58	60.00	-41.42	QP	
10		10.4010	3.80	9.84	13.64	50.00	-36.36	AVG	
11		29.2628	0.05	10.17	10.22	60.00	-49.78	QP	
12		29.2628	-2.75	10.17	7.42	50.00	-42.58	AVG	


- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.






Project No.: 2212G057A Page 32 of 63 Report Version: R02





- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value Limit Value.






- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value Limit Value.



APPENDIX C RADIATED EMISSIONS - ABOVE 1 GHZ

Project No.: 2212G057A Page 35 of 63 Report Version: R02






- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value Limit Value.



To	Test Mo) (1 Mbps) 0MHz		Test Date Polarization	,		3/5/22 tical
16	Temp			1°C		Hum.	I		110ai 3%
130.0 d	dBuV/m IG⊓II)		10		Huin.		30	J /0
120									
110									
100									
90									
80									
70									
I					111				
60									
	1						5		
50		donument was the light of early to be	er region and interest and	Manari markada makajima aproprij	warmen war	ar Inflitar aperac		enterestation de la contraction de la contractio	Cardin Salda Salda Ba
50		donumenten er Afrikalyst af staff toder.	de temperatural de la companya de la	Manageraphical and four afternoon	washing	and the second	5 ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	o production and the state of t	e zandowyski dowa hydrodyn
50 N////	1 Xuubilinging 2 X	innered seize of the light of the light terms	de april de la composition de la compo	Phase production and provide the	wante	non-profite and and	6	erighaas filosooddagaan agii haaferd	Cantonion graphic and a second a
40 2 30 2		danumahsah et thalpput sell t tilen	dinacrophiliadina	Phone was a survey or so we	Margarya.	rango prosessor and	6	o, special translation of the special security of	e grande and de service de lege
50		ionematical at the light of table them.	as announce de la constitución d	Manager and per de the	warps	nan makininan menengan	6	a a grand garant garant ang ang	e (madres/sed-decombrish-digg
50 40 2 30 20 10.0	2 X						6 X		
50 40 2 30 20 10.0 2380.0	2 X 000 2400.0	00 2420.00	2440.00	2460.00	2480.00 25	500.00 252	6 X 20.00 254	;««»«««««««»»»» «	2580.00 M
50 40 2 30 20 10.0	2 X		2440.00 Reading	2460.00 Correct	2480.00 29 Measure-		6 X		
50 40 2 30 20 10.0 2380.0	2 X 000 2400.0	00 2420.00 Freq.	2440.00 Reading Level	2460.00 Correct Factor	2480.00 29 Measure- ment	500.00 252 Limit	6 X 20.00 254 Over	10.00	2580.00 M
40 20 20 10.0 2380.0 No.	2 X 000 2400.0	00 2420.00 Freq.	2440.00 Reading Level dBuV	2460.00 Correct Factor dB	2480.00 29 Measure- ment dBuV/m	500.00 252 Limit dBuV/m	6 X 20.00 254 Over	Detector	
20 2380.0 No.	2 X 000 2400.0	00 2420.00 Freq. MHz 2387.100	2440.00 Reading Level dBuV 54.44	2460.00 Correct Factor dB -5.39	2480.00 29 Measure- ment dBuV/m 49.05	500.00 252 Limit dBuV/m 74.00	6 X 20.00 254 Over dB -24.95	Detector peak	2580.00 M
60 20 2380.0 No.	2 X 000 2400.0 Mk.	00 2420.00 Freq. MHz 2387.100 2387.100	2440.00 Reading Level dBuV 54.44 43.04	2460.00 Correct Factor dB -5.39 -5.39	2480.00 29 Measure- ment dBuV/m 49.05 37.65	500.00 252 Limit dBuV/m 74.00 54.00	6 X 20.00 254 Over dB -24.95 -16.35	Detector peak AVG	2580.00 M
50	2 X 000 2400.0	00 2420.00 Freq. MHz 2387.100 2387.100 2480.000	2440.00 Reading Level dBuV 54.44 43.04 102.39	2460.00 Correct Factor dB -5.39	2480.00 29 Measurement dBuV/m 49.05 37.65 97.17	500.00 252 Limit dBuV/m 74.00	6 X 20.00 254 Over dB -24.95	Detector peak	2580.00 M Comment
30 20 10.0 2380.0 No.	2 X 000 2400.1 Mk.	00 2420.00 Freq. MHz 2387.100 2387.100	2440.00 Reading Level dBuV 54.44 43.04	2460.00 Correct Factor dB -5.39 -5.39 -5.22	2480.00 29 Measure- ment dBuV/m 49.05 37.65	500.00 252 Limit dBuV/m 74.00 54.00 74.00	6 X 20.00 254 Over dB -24.95 -16.35 23.17	Detector peak AVG peak	2580.00 M

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.





- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value Limit Value.



	Test Mo) (2 Mbps)		Test Date			3/5/22
16	est Frequ			80MHz		Polarization			tical
130.0 d	Temp dBuV/m)		1°C		Hum.		58	3%
130.0	UDUY/III								
120									
110 -									
100					3				
90					$ \mathbb{A}$				
80									
70									
60									
00									
	ķ		100.00			5 X	and the a		414 41 41
50 40	2	Olytope to the participation of the squares.	demokrapalandenka	at representation and the second and	pyrod Morphon	~~whh~white	and the special control	the grant of the state of the s	polytypade and a special
50 www.		Different process trade, with the design.	dan may dipartificial free	ad region of the distribution for these	waren	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	, marine de la companya de la compa	4-4-5-4-18-18-18-18-18-18-18-18-18-18-18-18-18-	polity and
50 40 30	2	Defendant of the second	add the state of facilities of them.	artegaryen badafiran, dan gerikin	wastern and the second	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		oberphysika etgi/gyntyraphae dy	harring and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated and an indicated and an indicated an indicated and an indicated an indicated an indicated and an indicated an indicated and an indicated an indicated an indicated an indicated and an indicated and an indicated an indicated and an indicated an indicated an indicated and an
50 WAN 40 30 20	2	O Sparing and the sparing and	idan mangang pandapah dan	at express to the face state of the face o	man ware	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		they is a through the property of the second	johit ngadapanan ngaba
50 www.	2		2440.00	2460.00		eralderraktige *			2580.00 M
50 www.	2 X		2440.00 Reading	2460.00 Correct	2480.00 29 Measure-	eralderraktige *			
50 w/wh 40 30 20 10.0 2380.0	2 × 000 2400.0	00 2420.00	2440.00	2460.00	2480.00 25	× × × × × × × × × × × × × × × × × × ×	20.00 254		
50 www. 40 30 20 10.0 2380.0	2 × 000 2400.0	00 2420.00 Freq.	2440.00 Reading Level	2460.00 Correct Factor	2480.00 29 Measure- ment	500.00 252 Limit	20.00 254 Over	10.00	2580.00 M
80 80 0.0 2380.0 No.	2 × 000 2400.0	00 2420.00 Freq.	2440.00 Reading Level dBuV	2460.00 Correct Factor dB	2480.00 29 Measure- ment dBuV/m	500.00 252 Limit	0.00 254 Over dB	00.00 Detector	2580.00 M
60 60 60 0.0 2380.0 No.	2 × 000 2400.0	00 2420.00 Freq. MHz 2387.633	2440.00 Reading Level dBuV 54.82	2460.00 Correct Factor dB -5.39	2480.00 29 Measure- ment dBuV/m 49.43	500.00 252 Limit dBuV/m 74.00	0.00 254 Over dB -24.57	Detector peak	2580.00 M
10.0 2380.0 No.	000 2400.6 Mk.	00 2420.00 Freq. MHz 2387.633 2387.633	2440.00 Reading Level dBuV 54.82 43.46	2460.00 Correct Factor dB -5.39 -5.39	2480.00 29 Measure- ment dBuV/m 49.43 38.07	500.00 252 Limit dBuV/m 74.00 54.00	0.00 254 Over dB -24.57 -15.93	Detector peak AVG	2580.00 M
30 20 10.0 2380.0 No.	000 2400.0 Mk.	00 2420.00 Freq. MHz 2387.633 2387.633 2480.000	2440.00 Reading Level dBuV 54.82 43.46 101.69	2460.00 Correct Factor dB -5.39 -5.39 -5.22	2480.00 29 Measurement dBuV/m 49.43 38.07 96.47	500.00 252 Limit dBuV/m 74.00 54.00 74.00	Over dB -24.57 -15.93 22.47	Detector peak AVG peak	2580.00 M Comment

- (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value Limit Value.



		st Mo			BL		(1 Mk					Test D					3/5/22
			iency				2MHz				F	<u>Polariza</u>					tical
30.0	dBuV	Temp)			2	1°C					Hum	١.			58	3%
130.0	dBuv	'/m															
120 _																	
10																	
100																	
90																	
BO _																	
'o																	
60 —																	
50			1 X														
10			1 X 2 X														
30 <u> </u>																	
20																	
10.0																	
		3550.0			8650		11200		1375			300.00		50.00		00.00	26500.00 MI
No.	N	Иk.	Freq		Rea Le		Cor			easur ment	e-	Limi	t	Ove	er		
			MHz	<u>'</u>	dB	uV	dl	3	dE	3uV/r	n	dBuV.	/m	dB	}	Detector	Comment
1			4804.0	00	47.	67	0.5	53	۷	18.20		74.0	0	-25.8	30	peak	
2		*	4804.0	000	40.	29	0.5	53		10.82		54.0	0	-13.	18	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Test Mo			(1 Mbps)		Test Date			3/5/22
T	est Frequ			2MHz		Polarization	1		zontal
	Temp		2	1°C		Hum.		58	3%
130.0	dBuV/m								
120									
110									
100									
90									
80									
70									
60									
50		1 ¥ 2 ×							
40		X							
30									
20									
10.0									
1000.	000 3550.0	0 6100.00	8650.00	11200.00	13750.00		850.00 214	00.00	26500.00 MHz
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	- Limit	Over		
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comment
1_		4804.000		0.53	47.82	74.00	-26.18	peak	
2	*	4804.000	40.77	0.53	41.30	54.00	-12.70	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



		st Mo			BL		(1 M					Test D					3/5/22
			iency				0MHz	<u> </u>			- 1	Polariza		<u> </u>			tical
30.0	dBuV	Temp				2	1°C					Hun	۱.			58	3%
130.0	ubuv	/111															
120 _																	
10 _																	
00																	
0																	
:0																	
o																	
0 _																	
io =			1														
0			×														
:0																	
20																	
0.0																	
		3550.0			8650		11200			0.00		300.00		50.00		00.00	26500.00 MI
No.	N	Лk.	Freq		Rea Le			rect ctor		easur ment	e-	Limi	it 	Ove	er		
			MHz		dB	uV	d	В	dl	3uV/r	n	dBuV	/m	dB	3	Detector	Comment
1			4880.0	00	44.	56	0.	75	4	15.31		74.0	0	-28.0	69	peak	
2		*	4880.0	000	39.	93	0.	75		10.68		54.0	0	-13.3	32	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



		st Mo			BL	E 5.0						Test D					3/5/22	
			iency				OMH ₂	<u> </u>				<u>Polariza</u>					zontal	
30.0	dBuV	Temp				2	1°C					Hum	۱.			58	8%	
130.0	авич	7 M																
120 _																		
10																		
00																		
10																		
30 <u> </u>																		
o																		
io																		
io			1 Ž															
0			×															
:0																		
20																		
0.0																		
		3550.0			8650		1120			0.00		300.00		50.00		00.00	26500.00 N	ИH
No.	r	Иk.	Freq		Rea Le			rect ctor		easur ment	e-	Limi	t	Ove	er 			
			MHz		dB	uV	С	В	dl	3uV/r	n	dBuV	/m	dB		Detector	Commen	١t
1			4880.0	00	48.	07	0.	75	4	18.82		74.0	0	-25.′	18	peak		
2		*	4880.0	00	42.	62	0.	75		13.37		54.0	0	-10.6	63	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



		st Mo			BL		(1 M					Test D					3/5/22
			iency				0MHz				F	Polariza					tical
30.0	dBuV	Temp				2	1°C					Hun	۱.			58	3%
130.0	UDUY	7111															
120 _																	
10																	
00																	
90 <u> </u>																	
:o																	
o <u> </u>																	
0 _																	
io <u> </u>			1 X														
0			2 X														
io																	
20																	
0.0																	
		3550.0			8650		11200			0.00		300.00		50.00		00.00	26500.00 №
No.	ľ	Иk.	Freq	•	Rea Le			rect ctor		easur ment	e-	Limi	t	Ove	er		
			MHz		dB	uV	d	В	dE	3uV/r	n	dBuV	/m	dB	3	Detector	Commen
1			4960.0	00	47.	21	1.0	00	4	18.21		74.0	0	-25.7	79	peak	
2		*	4960.0	00	39.	02	1.0	00		10.02		54.0	0	-13.9	98	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



		st Mo			BL	E 5.0						Test D					3/5/22	
			iency				OMH:	Z			F	Polariza					zontal	
		Temp	1			2	1°C					Hum	١.			58	3%	
30.0	dBuV.	/m																7
20																		-
10																		-
00																		-
10																		-
:0																		-
o																		
io																		-
io			X 2															_
o			X															-
io																		-
20																		-
0.0																		
	0.000				8650		1120		1375			300.00		50.00	2140	0.00	26500.0	D MH
No.	N	∕lk.	Freq		Rea Le			rrect ctor		easur ment	9-	Limi	τ	Ove	:Г 			
			MHz		dB	uV	(lΒ	dl	3uV/n	n	dBuV	/m	dB		Detector	Comme	ent
1			4960.0	00	48.	76	1.	.00		9.76		74.0	0	-24.2	24	peak		
2		*	4960.0	00	41.	66	1.	.00		2.66		54.0	0	-11.3	34	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Test Mo			BL		(2 Mbp	s)				est Da				23/5/22
Te	est Freq					2MHz				Po	olarizat				ertical
	Tem	p			2	1°C					Hum.				58%
130.0	dBuV/m														
120															
110															
100															
90															
30															
o 🗀															
so															
io		1 X													
10		X 2 X													
		×													
10															
20															
10.0															
	000 3550.			8650		11200.0		13750				18850		1400.00	26500.00 MI
No.	Mk.	Freq	•	Read Lev		Corre Facto			asure nent	-	Limit		Over		
		MHz	<u>'</u>	dBı	uV	dB			uV/m		dBuV/r	m	dB	Detecto	or Comment
1		4804.0	000	47.	27	0.53	3	4	7.80		74.00		-26.20	peak	
2	*	4804.0	000	37.	31	0.53	3	3	7.84		54.00		-16.16	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Test				BL	E 5.0						Test D					3/5/22	
	Test F						2MHz	<u> </u>			F	Polariza					zontal	
		emp				2	1°C					Hum	۱.			58	3%	
130.0	dBuV/r	n																7
120																		-
110																		-
100																		-
30 <u> </u>																		-
30																		-
70 F																		-
io																		-
io			1 X															
10 <u> </u>			2 X															-
30 <u> </u>																		-
20																		-
10.0																		
	0.000 3				8650		1120			0.00		300.00		50.00	2140	0.00	26500.0	UMH
No.	M	K.	Freq	•	Rea Le	ding vel		rect ctor		easur ment	e- 	Limi	τ	Ove	er ——			
			MHz		dB	uV	C	В	dl	3uV/r	n	dBuV	/m	dB		Detector	Comme	ent
1			4804.0	00	48.	.21	0.	53		18.74		74.0	0	-25.2	26	peak		
2	*		4804.0	00	39	.13	0.	53	:	39.66		54.0	n	-14.3	34	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Te	st Mo	de		BL	E 5.0	(2 Mbps)		٦	Test Da	te		2023	3/5/22	
-	Test	Frequ	iency				0MHz			Р	olarizat	ion			tical	
		Temp)			2	1°C				Hum.			58	3%	
30.0	dBu∀	//m														_
20																-
10																-
00																-
0															$\frac{1}{1}$	
:0																$\frac{1}{1}$
0																
0																-
0			1,													1
0			1 2 X													$\ $
0																$\ $
0																-
0.0																
		3550.0			8650		11200.00					18850.00		4 00.00	26500.00) MI
No.		Иk.	Freq		Rea Le		Correct Factor		easure ment	-	Limit	O	ver			
			MHz		dB	uV	dB	d	BuV/m		dBuV/n	n (dΒ	Detector	Comme	ent
1			4880.0	00	44.	64	0.75		45.39		74.00	-28	3.61	peak		
2		*	4880.0	000	37.	85	0.75		38.60		54.00	-1!	5.40	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



	Test Mo			(2 Mbps)		Test Date			3/5/22
	Test Frequ			0MHz		Polarization	า		zontal
	Temp		2	1°C		Hum.		58	3%
130.0	dBuV/m								
120									
110									
100									
90									
80									
70 =									
60 _									
50		1 X 2							
40		X							
30									
20									
10.0									
	0.000 3550.0		8650.00	11200.00				100.00	26500.00 MHz
No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	- Limit	Over		
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comment
1		4880.000	49.95	0.75	50.70	74.00	-23.30	peak	
2	*	4880.000	41.61	0.75	42.36	54.00	-11.64	AVG	

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.




	Te	st Mo	de		BL	E 5.0						Test Da					3/5/22	
	Test Frequency			0MHz	<u> </u>			Polarization				Vertical						
		Temp)			2	1°C					Hum				58	3%	
130.0	dBuV	7m																\neg
120																		\perp
110 -																		4
100																		4
10																		_
30 <u> </u>																		_
o																		\dashv
io																		4
50 =			1 X															\dashv
ю			2 X															4
30			••															4
20																		4
10.0																		
	0.000				8650		1120		1375			00.00	1885		2140	0.00	26500.0	DO MI
No.	N	Лk.	Freq	Ī	Read Lev			rect ctor		easure ment) -	Limit		Ove	r			
			MHz		dBı	uV	C	ΙB	dE	3uV/n	1	dBuV/	m	dB		Detector	Comm	ent
1			4960.0	00	46.	73	1.	00	4	17.73		74.00)	-26.2	27	peak		
2		*	4960.0	00	36.	80	1.	00	3	37.80		54.00)	-16.2	20	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.



		st Mo			BL		(2 M					Test D				23/5/22	
			iency				0MHz	<u> </u>			F	Polariza				rizontal	
100.0		Temp)			2	1°C					Hum	١.			58%	
130.0	dBuV	/m															
120																	
110 -																	
100																	
30 <u> </u>																	
30																	
70 F																	
60 <u> </u>																	
50 =			1 X														
10 <u> </u>			X 2 X														
30			^														
20																	
10.0																	
		3550.0			8650		1120		1375			300.00			21400.00	26500.00 MI	
No.	N	Лk.	Freq	•	Read Lev			rect ctor		easure ment	9-	Limi	t	Over			
			MHz		dB	uV	C	В	dl	3uV/n	n	dBuV/	m′	dB	Detecto	r Comment	
1			4960.0	00	44.	25	1.	00	4	15.25		74.0	0	-28.75	5 peak		
2		*	4960.0	00	36.	09	1.	00	3	37.09		54.0	0	-16.91	AVG		

- (1) Measurement Value = Reading Level + Correct Factor.(2) Margin Level = Measurement Value Limit Value.






	Report No.: BTL-FCCP-2-2212G057A
APPENDIX D	

Project No.: 2212G057A Page 52 of 63 Report Version: R02



Test Mode: BLE 5.0_1 Mbps


Frequency (MHz)	6dB Bandwidth (MHz)	99% Occupied BW (MHz)	Min. Limit (kHz)	Test Result
2402	0.65	1.02	500	Pass
2440	0.65	1.03	500	Pass
2480	0.66	1.04	500	Pass





Test Mode: BLE 5.0_2 Mbps

Frequency (MHz)	6dB Bandwidth (MHz)	99% Occupied BW (MHz)	Min. Limit (kHz)	Test Result
2402	1.12	2.05	500	Pass
2440	0.94	2.06	500	Pass
2480	0.95	2.07	500	Pass





	Report No.: BTL-FCCF-2-2212G057A
APPENDIX E	OUTPUT POWER

Project No.: 2212G057A Page 55 of 63 Report Version: R02





Τe	est Mode :	BLE 5.0_1 Mbps	Tested Date	2023/5/23

Frequency (MHz)	Conducted Power (dBm)	Conducted Power (W)	Max. Limit (dBm)	Max. Limit (W)	Test Result
2402	2.96	0.0020	30.00	1.0000	Pass
2440	3.22	0.0021	30.00	1.0000	Pass
2480	3.59	0.0023	30.00	1.0000	Pass

Frequency (MHz)	Conducted Power (dBm)	Conducted Power (W)	Max. Limit (dBm)	Max. Limit (W)	Test Result
2402	3.22	0.0021	30.00	1.0000	Pass
2440	2.93	0.0020	30.00	1.0000	Pass
2480	2.65	0.0018	30.00	1.0000	Pass

Project No.: 2212G057A Page 56 of 63 Report Version: R02




APPENDIX F POWER SPECTRAL DENSITY TEST

Project No.: 2212G057A Page 57 of 63 Report Version: R02




Test Mode : BLE 5.0_1 Mbps

Frequency (MHz)	Power Density (dBm/3kHz)	Max. Limit (dBm/3kHz)	Test Result
2402	-12.99	8	Pass
2440	-12.55	8	Pass
2480	-11.63	8	Pass



Test Mode: BLE 5.0_2 Mbps

Frequency (MHz)	Power Density (dBm/3kHz)	Max. Limit (dBm/3kHz)	Test Result
2402	-16.10	8	Pass
2440	-15.46	8	Pass
2480	-17.05	8	Pass






APPENDIX G	ANTENNA CONDUCTED SPURIOUS EMISSION


Project No.: 2212G057A Page 59 of 63 Report Version: R02



Test Mode: BLE 5.0_1 Mbps









Test Mode : BLE 5.0_2 Mbps

