

1. Effective (Isotropic) Radiated Power Output Data

1.1 Band2_EIRP

1.1.1 Test Result

Band: 2									
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dbi)	EIRP (dBm)		Verdict	
	Network	Subset				Result	Limit		
NTNV	RMC	12.2kbps RMC	1852.4	22.37	-1.14	21.23	<=33.01	Pass	
			1880	22.71	-1.14	21.57	<=33.01	Pass	
			1907.6	22.75	-1.14	21.61	<=33.01	Pass	
	HSDPA	Subtest 1	1852.4	21.62	-1.14	20.48	<=33.01	Pass	
		Subtest 2	1852.4	21.63	-1.14	20.49	<=33.01	Pass	
		Subtest 3	1852.4	21.63	-1.14	20.49	<=33.01	Pass	
		Subtest 4	1852.4	21.57	-1.14	20.43	<=33.01	Pass	
		Subtest 1	1880	22.30	-1.14	21.16	<=33.01	Pass	
		Subtest 2	1880	22.31	-1.14	21.17	<=33.01	Pass	
		Subtest 3	1880	22.32	-1.14	21.18	<=33.01	Pass	
		Subtest 4	1880	22.27	-1.14	21.13	<=33.01	Pass	
		Subtest 1	1907.6	22.21	-1.14	21.07	<=33.01	Pass	
		Subtest 2	1907.6	22.21	-1.14	21.07	<=33.01	Pass	
		Subtest 3	1907.6	22.22	-1.14	21.08	<=33.01	Pass	
		Subtest 4	1907.6	22.16	-1.14	21.02	<=33.01	Pass	
		HSUPA	Subtest 1	1852.4	19.72	-1.14	18.58	<=33.01	Pass
			Subtest 2	1852.4	19.81	-1.14	18.67	<=33.01	Pass
			Subtest 3	1852.4	19.68	-1.14	18.54	<=33.01	Pass
			Subtest 4	1852.4	19.71	-1.14	18.57	<=33.01	Pass
	Subtest 5		1852.4	19.49	-1.14	18.35	<=33.01	Pass	
	Subtest 1		1880	19.95	-1.14	18.81	<=33.01	Pass	
	Subtest 2		1880	20.11	-1.14	18.97	<=33.01	Pass	
	Subtest 3		1880	20.38	-1.14	19.24	<=33.01	Pass	
	Subtest 4		1880	19.95	-1.14	18.81	<=33.01	Pass	
	Subtest 5		1880	20.39	-1.14	19.25	<=33.01	Pass	
	Subtest 1		1907.6	19.78	-1.14	18.64	<=33.01	Pass	
	Subtest 2		1907.6	19.91	-1.14	18.77	<=33.01	Pass	
	Subtest 3		1907.6	20.17	-1.14	19.03	<=33.01	Pass	
	Subtest 4		1907.6	20.17	-1.14	19.03	<=33.01	Pass	
	Subtest 5		1907.6	20.37	-1.14	19.23	<=33.01	Pass	

Note1: EIRP=Conducted Power+Antenna Gain

2. Effective (Isotropic) Radiated Power Output Data

2.1 Band5_ERP

2.1.1 Test Result

Band: 5									
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dbi)	ERP (dBm)		Verdict	
	Network	Subset				Result	Limit		
NTNV	RMC	12.2kbps RMC	826.4	23.04	-5.96	14.93	<=38.45	Pass	
			836.6	23.14	-5.96	15.03	<=38.45	Pass	
			846.6	23.14	-5.96	15.03	<=38.45	Pass	
	HSDPA	Subtest 1	826.4	21.79	-5.96	13.68	<=38.45	Pass	
		Subtest 2	826.4	21.79	-5.96	13.68	<=38.45	Pass	
		Subtest 3	826.4	21.78	-5.96	13.67	<=38.45	Pass	
		Subtest 4	826.4	21.74	-5.96	13.63	<=38.45	Pass	
		Subtest 1	836.6	21.94	-5.96	13.83	<=38.45	Pass	
		Subtest 2	836.6	21.94	-5.96	13.83	<=38.45	Pass	
		Subtest 3	836.6	21.95	-5.96	13.84	<=38.45	Pass	
		Subtest 4	836.6	21.95	-5.96	13.84	<=38.45	Pass	
		Subtest 1	846.6	22.23	-5.96	14.12	<=38.45	Pass	
		Subtest 2	846.6	22.22	-5.96	14.11	<=38.45	Pass	
		Subtest 3	846.6	22.25	-5.96	14.14	<=38.45	Pass	
		Subtest 4	846.6	22.20	-5.96	14.09	<=38.45	Pass	
		HSUPA	Subtest 1	826.4	19.99	-5.96	11.88	<=38.45	Pass
			Subtest 2	826.4	19.61	-5.96	11.5	<=38.45	Pass
			Subtest 3	826.4	20.01	-5.96	11.9	<=38.45	Pass
	Subtest 4		826.4	19.46	-5.96	11.35	<=38.45	Pass	
	Subtest 5		826.4	19.88	-5.96	11.77	<=38.45	Pass	
	Subtest 1		836.6	20.03	-5.96	11.92	<=38.45	Pass	
	Subtest 2		836.6	20.21	-5.96	12.1	<=38.45	Pass	
	Subtest 3		836.6	20.11	-5.96	12	<=38.45	Pass	
	Subtest 4		836.6	20.21	-5.96	12.1	<=38.45	Pass	
	Subtest 5		836.6	20.10	-5.96	11.99	<=38.45	Pass	
	Subtest 1		846.6	20.17	-5.96	12.06	<=38.45	Pass	
	Subtest 2		846.6	20.02	-5.96	11.91	<=38.45	Pass	
	Subtest 3		846.6	19.87	-5.96	11.76	<=38.45	Pass	
	Subtest 4		846.6	20.46	-5.96	12.35	<=38.45	Pass	
	Subtest 5		846.6	20.29	-5.96	12.18	<=38.45	Pass	

Note1: ERP=Conducted Power+Antenna Gain-2.15