

# REYAX TECHNOLOGY CO.,LTD.

4F.-15, No.26, Ln. 321, Yangguang St., Neihu Dist., Taipei City 11491, Taiwan

## Declaration of the Modular Approval

<b>Applicant / Grantee</b>	QLY
<b>FCC ID:</b>	QLYRYLR993
<b>Model:</b>	RYLR993

The single module transmitter has been evaluated then tested meeting the requirements under Part 15C Section 2.12 as below:

<b>Modular approval requirement</b>	<b>EUT Condition</b>	<b>Comply</b>
(a) The radio elements of the modular transmitter must have their own shielding. The physical crystal and tuning capacitors may be located external to the shielded radio elements.	Please refer to product photo.	YES
(b) The modular transmitter must have buffered modulation/data inputs (if such inputs are provided) to ensure that the module will comply with part 15 requirements under conditions of excessive data rates or over-modulation.	The module has buffered data inputs, it is integrated in chip. Please refer to the schematic.	YES
(c) The modular transmitter must have its own power supply regulation.	Please refer to the schematic or block diagram.	YES
(d) The modular transmitter must comply with the antenna and transmission system requirements of Sections 15.203, 15.204(b) and 15.204(c). The antenna must either be permanently attached or employ a "unique" antenna coupler (at all connections between the module and the antenna, including the cable). The "professional installation" provision of Section 15.203 is not applicable to modules but can apply to limited modular approvals under paragraph (b) of this section.	Yes, please refer to product photo.	YES
(e) The modular transmitter must be tested in a stand-alone configuration, i.e., the	Yes, please refer to the setup report.	YES

# REYAX TECHNOLOGY CO.,LTD.

4F.-15, No.26, Ln. 321, Yangguang St., Neihu Dist., Taipei City 11491, Taiwan

<p>module must not be inside another device during testing for compliance with part 15 requirements. Unless the transmitter module will be battery powered, it must comply with the AC line conducted requirements found in Section 15.207. AC or DC power lines and data input/output lines connected to the module must not contain ferrites, unless they will be marketed with the module (see Section 15.27(a)). The length of these lines shall be the length typical of actual use or, if that length is unknown, at least 10 centimeters to insure that there is no coupling between the case of the module and supporting equipment. Any accessories, peripherals, or support equipment connected to the module during testing shall be unmodified and commercially available (see Section 15.31(i)) must not be inside another device during testing.</p>		
<p>(f) The modular transmitter must be equipped with either a permanently affixed label or must be capable of electronically displaying its FCC identification number.</p>	<p>Yes,please refer to ID_label or location.</p>	<p>YES</p>
<p>(g) The modular transmitter must comply with any specific rules or operating requirements that ordinarily apply to a complete transmitter and the manufacturer must provide adequate instructions along with the module to explain any such requirements. A copy of these instructions must be included in the application for equipment authorization requirements, which are based on the intended use/configurations.</p>	<p>Yes,please refer to test report.</p>	<p>YES</p>
<p>(h) The modular transmitter must comply with any applicable RF exposure</p>	<p>Yes,please refer to test report.</p>	<p>YES</p>

# REYAX TECHNOLOGY CO.,LTD.

4F.-15, No.26, Ln. 321, Yangguang St., Neihu Dist., Taipei City 11491, Taiwan

requirements in its final configuration.		
--	--	--

Date: 8/28/2023

Name: Ritchie Chang

*Ritchie*

Title: Manager

E-mail: Ritchie@reyax.com

Tel.: +886-911867815