



Ubiquiti Networks Inc.
495-499 Montague Expwy
Milpitas, CA 95035

8/10/06

To Whom it May Concern:

The LiteStation2 (LS2) undergoes a manufacturing calibration program and test routine following printed circuit board assembly on a per unit basis. The routine encompasses the following:

- Programming I/Q chain offsets
- Programming and testing target output power levels per tested compliance limits within 1dB tolerance
- Testing carrier offset in +/- 10ppm tolerance
- Testing data throughput and overall receiver performance levels to internal specification
- Testing current consumption within +/-100mA of spec

Sincerely,

A handwritten signature in black ink, appearing to read "Robert J. Pera".

Robert J. Pera
Senior Engineer
Ubiquiti Networks