1	-CC/IC Ra	dio Test Report
	FCC ID	: UZZSFQ01
	IC: 76	33A-SFQ01
This report	concerns (check on	e) : Class II Change
	Model Name : Applicant : Address : :	1007C119 Hi Fi dock with bluetooth wireless Audio system
	Tested by:	
		ing Inc. EMC Laboratory
	Date of Receipt:	Jul. 13, 2010
	Date of Test:	10 2010
	Jul. 13, 2010 ~ Ju	T of a
	Testing Engineer	(Jeff Yang)
	Technical Manage	r : Sala

# Neutron Engineering Inc.

No.3, Jinshagang 1st Road, ShiXia, Dalang Town, Dong Guan, China. TEL : (0769) 8318-3000 FAX : (0769) 8319-6000



#### Declaration

**Neutron** represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with the standards traceable to National Measurement Laboratory (**NML**) of **R.O.C.**, or National Institute of Standards and Technology (**NIST**) of **U.S.A.** 

**Neutron's** reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **Neutron** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **Neutron** issued reports.

**Neutron**'s reports must not be used by the client to claim product endorsement by the authorities or any agency of the Government.

This report is the confidential property of the client. As a mutual protection to the clients, the public and **Neutron-self**, extracts from the test report shall not be reproduced except in full with **Neutron**'s authorized written approval.

**Neutron**'s laboratory quality assurance procedures are in compliance with the **ISO Guide 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

#### Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.



Table of Contents	Page
1. CERTIFICATION	6
2 . SUMMARY OF TEST RESULTS	7
2.1 TEST FACILITY	8
2.2 MEASUREMENT UNCERTAINTY	8
3 . GENERAL INFORMATION	9
3.1 GENERAL DESCRIPTION OF EUT	9
3.2 DESCRIPTION OF TEST MODES	11
3.3 TABLE OF PARAMETERS OF TEXT SOFTWARE SETTING	12
3.4 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TEST	TED 12
3.5 DESCRIPTION OF SUPPORT UNITS	13
4. EMC EMISSION TEST	14
4.1 CONDUCTED EMISSION MEASUREMENT	14
4.1.1 POWER LINE CONDUCTED EMISSION LIMITS	14
4.1.2 MEASUREMENT INSTRUMENTS LIST AND SETTING	14
4.1.3 TEST PROCEDURE 4.1.4 DEVIATION FROM TEST STANDARD	15 15
4.1.5 TEST SETUP	15
4.1.6 EUT OPERATING CONDITIONS	16
4.1.7 TEST RESULTS	17
4.2 RADIATED EMISSION MEASUREMENT	25
4.2.1 RADIATED EMISSION LIMITS	25
4.2.2 MEASUREMENT INSTRUMENTS LIST ANS SETTING 4.2.3 TEST PROCEDURE	26 27
4.2.4 DEVIATION FROM TEST STANDARD	27
4.2.5 TEST SETUP	28
	29
4.2.7 TEST RESULTS (BETWEEN 30 – 1000 MHZ) 4.2.8 TEST RESULTS (ABOVE 1000 MHZ)	30 34
5 . NUMBER OF HOPPING CHANNEL	54 64
	-
5.1 APPLIED PROCEDURES / LIMIT 5.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING	64 64
5.1.2 TEST PROCEDURE	64
5.1.3 DEVIATION FROM STANDARD	64
5.1.4 TEST SETUP	64
5.1.5 EUT OPERATION CONDITIONS 5.1.6 TEST RESULTS	64 65
J.I.U ILGI NLGULIG	05

Neutron Engineering Inc.\_\_\_\_\_

۶E

Table of Contents	Page
6. AVERAGE TIME OF OCCUPANCY	67
6.1 APPLIED PROCEDURES / LIMIT	67
6.1.1 MEASUREMENT INSTRUMENTS LIST	67
6.1.2 TEST PROCEDURE	67
6.1.3 DEVIATION FROM STANDARD	67
6.1.4 TEST SETUP	68
6.1.5 EUT OPERATION CONDITIONS	68
6.1.6 TEST RESULTS	69
7. HOPPING CHANNEL SEPARATION MEASUREMENT	81
7.1 APPLIED PROCEDURES / LIMIT	81
7.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING	81
7.1.2 TEST PROCEDURE	81
7.1.3 DEVIATION FROM STANDARD 7.1.4 TEST SETUP	81 81
7.1.5 EUT OPERATION CONDITIONS	81
7.1.6 TEST RESULTS	82
3. BANDWIDTH TEST	86
8.1 APPLIED PROCEDURES / LIMIT	86
8.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING	86
8.1.2 TEST PROCEDURE	86
8.1.3 DEVIATION FROM STANDARD	86
8.1.4 TEST SETUP	86
8.1.5 EUT OPERATION CONDITIONS	86
8.1.6 TEST RESULTS	87
9 . PEAK OUTPUT POWER TEST	91
9.1 APPLIED PROCEDURES / LIMIT	91
9.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING	91
9.1.2 TEST PROCEDURE 9.1.3 DEVIATION FROM STANDARD	91 91
9.1.4 TEST SETUP	91
9.1.5 EUT OPERATION CONDITIONS	91
9.1.6 TEST RESULTS	92
10 . ANTENNA CONDUCTED SPURIOUS EMISSION	96
10.1 APPLIED PROCEDURES / LIMIT	96
10.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING	96
10.1.2 TEST PROCEDURE	96
10.1.3 DEVIATION FROM STANDARD	96
10.1.4 TEST SETUP	97
10.1.5 EUT OPERATION CONDITIONS	9

	gineering Inc
MALE LOOK	g
	Table of Contents

**10.1.6 TEST RESULTS** 

**11.1 APPLIED PROCEDURES / LIMIT** 

**11.1.2 MPE CALCULATION METHOD** 

**11.1.1 MEASUREMENT INSTRUMENTS LIST** 

**11 . RF EXPOSURE TEST** 

102	
102	
102	
103	
103	
400	

Page

98

11.1.3 DEVIATION FROM STANDARD	103
11.1.4 TEST SETUP	103
11.1.5 EUT OPERATION CONDITIONS	103
11.1.6 TEST RESULTS	104
12 . EUT TEST PHOTO	105



# **1. CERTIFICATION**

Equipment: Brand Name: Model Name:	
Applicant:	Beautiful Enterprise Co., Ltd Shenzhen Synchron Electronics Co.,Ltd
Address:	No. 9 Mei Li Road, Xia Mei Lin, Fu Tian Area, Shenzhen, China Jul. 13, 2010 ~ Jul. 19, 2010
	ENGINEERING SAMPLE FCC Part15, Subpart C(15.247) / Canada RSS-210:2007

The above equipment has been tested and found compliance with the requirement of the relative standards by Neutron Engineering Inc. EMC Laboratory.

The test data, data evaluation, and equipment configuration contained in our test report (Ref No. NEI-FICP-1-1007C119) were obtained utilizing the test procedures, test instruments, test sites that has been accredited by the Authority of NVLAP and TAF according to the ISO-17025 quality assessment standard and technical standard(s).



# 2. SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

APPLIED STANDARD: 47 CFR Part 15, Subpart C; Canada RSS-210:2007						
Standard Section						
RSS-210	47 CFR Part 15	Test Item	Judgment	Remark		
RSS-GEN 7.2.2	15.207	Conducted Emission	PASS			
RSS-210 Annex 8 (A8.1d)	15.247 (c)	Antenna conducted Spurious Emission	PASS			
RSS-210 Annex 8 (A8.1d)	15.247 (a)(1)	Hopping Channel Separation	PASS			
RSS-210 Annex 8 (A8.1b)	15.247 (b)(1)	Peak Output Power	PASS			
RSS-210 Annex 8 (A8.1a)	15.247 (c)	Radiated Spurious Emission	PASS			
RSS-210 Annex 8 (A8.4(2))	15.247 (a)(1)(iii)	Number of Hopping Frequency	PASS			
RSS-210 Annex 8 (A8.5)	15.247 (a)(1)(iii)	Dwell Time	PASS			
RSS-Gen 7.2.3	15.205	Restricted Bands	PASS			
RSS-210 Annex 8 (A8.5)	15.203	Antenna Requirement	PASS			
	1.1307 1.1310 2.1091 2.1093	RF Exposure Compliance	PASS			

#### NOTE:

(1)" N/A" denotes test is not applicable in this Test Report



#### 2.1 TEST FACILITY

The test facilities used to collect the test data in this report is **DG-C03/CB03** at the location of No.3, Jinshagang 1st Road, ShiXia, Dalang Town, Dong Guan, China.523792 Neutron's test firm number for FCC 319330 Neutron's test firm number for IC 4428B-1

#### 2.2 MEASUREMENT UNCERTAINTY

Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the EUT as specified in CISPR 16-4-2:

The reported uncertainty of measurement y  $\pm$  U  $_{\rm 2}$  where expended uncertainty U is based on a standard uncertainty multiplied by a coverage factor of ~ k=2  $_{\rm 2}$  providing a level of confidence of approximately 95 %  $_{\rm 2}$ 

A. Conducted Measurement :

Test Site Method Measurement Frequency Range		U , (dB)	NOTE	
DG-C03	CISPR	150 KHz ~ 30MHz	1.94	

#### B. Radiated Measurement :

Test Site	Method	Measurement Frequency Range	Ant. H / V	U , (dB)	NOTE
CB03	CISPR	30MHz ~ 200MHz	V	3.82	
		30MHz ~ 200MHz	Н	3.60	
		200MHz ~ 1,000MHz	V	3.86	
		200MHz ~ 1,000MHz	Н	3.94	

# Neutron Engineering Inc.

# **3. GENERAL INFORMATION**

# 3.1 GENERAL DESCRIPTION OF EUT

Equipment	Hi Fi dock with bluetooth wireless Audio system			
Brand Name	N/A			
Model Name	SFQ-01			
OEM Brand/Model Name	N/A			
Model Difference	N/A			
Product Description	N/AThe EUT is a Hi Fi dock with bluetooth wireless Audio systemOperation Frequency: $2402 \sim 2480 \text{ MHz}$ Modulation Type:GFSK(1Mbps)Bit Rate of Transmitter $\pi$ /4-DQPSK(2Mbps) 8-DPSK(3Mbps)Number Of Channel79 CHAntenna Designation:Please see Note 3.Output Power: $3.75 \text{ dBm (1Mbps)}$ 1.82 dBm (3Mbps)Based on the application, features, or specification exhibited in User's Manual, the EUT is considered as an ITE/Computing Device. More details of EUT technical			
Channel List	Please refer to the Note 2.			
Power Source	DC Voltage supplied from AC/DC adapter. Brand name: KINGWALL Model name:AS600-180-AA330			
Power Rating	I/P AC100-240V~50/60Hz, 1.5A O/P 18V, 3.3A			
Connecting I/O Port(s)	Please refer to the User's Manual			
Products Covered	N/A			

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the User's Manual.

Neutron Engineering Inc.—

2.

Channel List						
Channel	Frequency (MHz)	Channel	Frequency (MHz)	Channel	Frequency (MHz)	
00	2402	27	2429	54	2456	
01	2403	28	2430	55	2457	
02	2404	29	2431	56	2458	
03	2405	30	2432	57	2459	
04	2406	31	2433	58	2460	
05	2407	32	2434	59	2461	
06	2408	33	2435	60	2462	
07	2409	34	2436	61	2463	
08	2410	35	2437	62	2464	
09	2411	36	2438	63	2465	
10	2412	37	2439	64	2466	
11	2413	38	2440	65	2467	
12	2414	39	2441	66	2468	
13	2415	40	2442	67	2469	
14	2416	41	2443	68	2470	
15	2417	42	2444	69	2471	
16	2418	43	2445	70	2472	
17	2419	44	2446	71	2473	
18	2420	45	2447	72	2474	
19	2421	46	2448	73	2475	
20	2422	47	2449	74	2476	
21	2423	48	2450	75	2477	
22	2424	49	2451	76	2478	
23	2425	50	2452	77	2479	
24	2426	51	2453	78	2480	
25	2427	52	2454			
26	2428	53	2455			

#### 3.

### Table for Filed Antenna

Ant	Brand	Model Name	Antenna Type	Connector	Gain (dBi)	NOTE
1	AMOTECH	ALA621C4	CHIP ANT	N/A	3.5	BT Antenna



#### 3.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generates from EUT, the test system was pre-scanning tested base on the consideration of following EUT operation mode or test configuration mode which possible have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.

Pretest Mode	Description
Mode 1	CH00 (1Mbps/3Mbps)
Mode 2	CH39 (1Mbps/3Mbps)
Mode 3	CH78 (1Mbps/3Mbps)
Mode 4	IPOD IN
Mode 5	AUX IN
Mode 6	FM 87.5MHz
Mode 7	Bluetooth

The EUT system operated these modes were found to be the worst case during the pre-scanning test as Following:

	For Conducted Emission					
Final Test Mode	Description					
Mode 4	IPOD IN					
Mode 5	AUX IN					
Mode 6	FM 87.5MHz					
Mode 7	Bluetooth					

For Radiated Emission					
Final Test Mode Description					
Mode 1	CH00 (1Mbps/3Mbps)				
Mode 2	CH39 (1Mbps/3Mbps)				
Mode 3	CH78 (1Mbps/3Mbps)				

Note:

(1) The measurements are performed at the highest, middle, lowest available channels.




#### 3.3 TABLE OF PARAMETERS OF TEXT SOFTWARE SETTING

During testing channel & power controlling software provided by the customer was used to control the operating channel as well as the output power level. The RF output power selection is for the setting of RF output power expected by the customer and is going to be fixed on the firmware of the final end product power parameters of FHSS

Test software Version	Test program: Bluetest.exe			
Frequency	2402 MHz	2441 MHz	2480 MHz	
Parameters-1Mbps	63	63	63	
Parameters-3Mbps	100	100	100	

#### 3.4 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED





#### 3.1 DESCRIPTION OF SUPPORT UNITS

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	FCC ID/IC	Series No.	Note
E-1	Hi Fi dock with bluetooth wireless Audio system	N/A	SFQ-01	UZZSFQ01 7633A-SFQ01	N/A	EUT
E-2	Adapter	KINGWALL	AS600-180-AA330	N/A	N/A	

Item	Shielded Type	Ferrite Core	Length	Note
C-1	NO	YES	1.0M	
C-2	NO	NO	1.8M	

Note:

- (1) The support equipment was authorized by Declaration of Confirmation.
- (2) For detachable type I/O cable should be specified the length in cm in <sup>[]</sup> Length <sup>[]</sup> column.

# Neutron Engineering Inc.

### 4. EMC EMISSION TEST

#### 4.1 CONDUCTED EMISSION MEASUREMENT

#### 4.1.1 POWER LINE CONDUCTED EMISSION Limits (Frequency Range 150KHz-30MHz)

FREQUENCY (MHz)	Class A (dBuV)		Class B	Standard	
	Quasi-peak	Average	Quasi-peak	Average	Stanuaru
0.15 -0.5	79.00	66.00	66 - 56 *	56 - 46 *	CISPR
0.50 -5.0	73.00	60.00	56.00	46.00	CISPR
5.0 -30.0	73.00	60.00	60.00	50.00	CISPR

0.15 -0.5	79.00	66.00	66 - 56 *	56 - 46 *	FCC
0.50 -5.0	73.00	60.00	56.00	46.00	FCC
5.0 -30.0	73.00	60.00	60.00	50.00	FCC

Note:

(1) The tighter limit applies at the band edges.

(2) The limit of " \* " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.

#### 4.1.2 MEASUREMENT INSTRUMENTS LIST AND SETTING

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	LISN	EMCO	3816/2	00052765	May.26.2011
2	LISN	Rolf Heine	NNB-2-16Z	99044	May.26.2011
3	50Ω Terminator	SHX	TF2-3G-A	08122901	May.26.2011
4	Transient Limiter	Transient Limiter Agilent		3107A03668	May.26.2011
5	Test Cable	N/A	C-06_C03	N/A	Nov.16.2010
6	EMI TEST RECEIVER			8333641017	May.26.2011

Remark: " N/A" denotes No Model No., Serial No. or No Calibration specified.

#### The following table is the setting of the receiver

Receiver Parameters	Setting		
Attenuation	10 dB		
Start Frequency	0.15 MHz		
Stop Frequency	30 MHz		
IF Bandwidth	9 kHz		




#### 4.1.3 TEST PROCEDURE

- a. The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipments powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- c. I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- d. LISN at least 80 cm from nearest part of EUT chassis.
- e. For the actual test configuration, please refer to the related Item –EUT Test Photos.

#### 4.1.4 DEVIATION FROM TEST STANDARD

No deviation

#### 4.1.5 TEST SETUP





#### 4.1.6 EUT OPERATING CONDITIONS

The EUT was configured for testing in a typical fashion (as a customer would normally use it). The EUT has been programmed to continuously transmit during test. This operating condition was tested and used to collect the included data.


# Neutron Engineering Inc.=

# 4.1.7 TEST RESULTS

EUT : Hi Fi dock with bluetooth wireless Audio system					ess	Model N	lame :	SFQ-01	
Temperati	ure :	23	°C			Relative	Humidity :	57 %	
Pressure :		101	0hPa			Test Vol	tage :	AC 120V/60I	Ηz
Test Mode : IPOD IN									
Freq.	Termi	nal	nal Measured(dBuV)			Limits(	(dBuV)	Margin	Note
(MHz)	L/N		QP-Mode	AV-Mode	QP	-Mode	AV-Mode	(dB)	NOLE
0.16	Line		56.88	36.61	6	5.52	55.52	-8.64	(QP)
0.18	Line	÷	54.90	35.32	6	4.63	54.63	-9.73	(QP)
0.21	Line	;	52.14	*	6	3.09	53.09	-10.95	(QP)
0.74	Line	e 27.65		*	5	6.00	46.00	-28.35	(QP)
0.94	Line	e 26.56 *		*	5	6.00	46.00	-29.44	(QP)
3.39	Line	;	26.46	*	5	6.00	46.00	-29.54	(QP)

#### Remark

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz;SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •
- (3) Measuring frequency range from 150KHz to 30MHz  $_{\circ}$






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> °C	Relative Humidity :	57 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	IPOD IN		

Freq.	Terminal	Measure	Measured(dBuV)		(dBuV)	Margin	Note
(MHz)	L/N	QP-Mode	AV-Mode	QP-Mode	AV-Mode	(dB)	NULE
0.15	Neutral	56.52	34.49	66.00	56.00	-9.48	(QP)
0.19	Neutral	52.98	33.74	64.21	54.21	-11.23	(QP)
0.69	Neutral	28.10	*	56.00	46.00	-27.90	(QP)
2.54	Neutral	24.71	*	56.00	46.00	-31.29	(QP)
3.19	Neutral	25.02	*	56.00	46.00	-30.98	(QP)
7.04	Neutral	24.72	*	60.00	50.00	-35.28	(QP)


- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz;SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •
- (3) Measuring frequency range from 150KHz to 30MHz •





EUT :			i dock with bl lio system	ess	Model N	lame :	SFQ-01		
Temperatu	ure :	23	°C			Relative	Humidity :	57 %	
Pressure :		101	0hPa			Test Vol	tage :	AC 120V/60I	Ηz
Test Mode : AUX IN									
Freq.	Termi	nal	nal Measured(dBu			Limits(dBuV)		Margin	Note
(MHz)	L/N		QP-Mode	AV-Mode	QP	-Mode	AV-Mode	(dB)	NOLE
0.15	Line		56.62	36.03	6	6.00	56.00	-9.38	(QP)
0.17	Line		54.88	35.22	6	5.06	55.06	-10.18	(QP)
0.67	Line	;	29.27	*	5	6.00	46.00	-26.73	(QP)
2.21	Line	;	25.55	*	5	6.00	46.00	-30.45	(QP)
3.36	Line	;	26.09	*	5	6.00	46.00	-29.91	(QP)
9.12	Line	;	24.50	*	6	0.00	50.00	-35.50	(QP)

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz;SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •




(3) Measuring frequency range from 150KHz to 30MHz  $_{\circ}$ 



IFUI .	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> °C	Relative Humidity :	57 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	AUX IN		

Freq.	Terminal	Measured(dBuV)		Limits(	(dBuV)	Margin	Note
(MHz)	L/N	QP-Mode	AV-Mode	QP-Mode	AV-Mode	(dB)	NULE
0.15	Neutral	55.18	35.23	66.00	56.00	-10.82	(QP)
0.17	Neutral	53.98	32.17	65.06	55.06	-11.08	(QP)
0.53	Neutral	30.09	*	56.00	46.00	-25.91	(QP)
1.01	Neutral	27.46	*	56.00	46.00	-28.54	(QP)
1.78	Neutral	25.31	*	56.00	46.00	-30.69	(QP)
4.90	Neutral	25.60	*	56.00	46.00	-30.40	(QP)


- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz, VBW =10KHz, Swp. Time = 0.2 sec./MHz • Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz •
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform • In this case, a " \* " marked in AVG Mode column of Interference Voltage Measured •
- (3) Measuring frequency range from 150KHz to 30MHz •





EUT :			Hi Fi dock with bluetooth wireless Audio system			Model N	lame :	SFQ-01	
Temperatu	ure :	23	°C			Relative	Humidity :	57 %	
Pressure :		101	0hPa			Test Vol	tage :	AC 120V/60I	Hz
Test Mode : FM 87.5MHz									
Freq.	Termi	nal	Measure	d(dBuV)		Limits(dBuV)		Margin	Note
(MHz)	L/N		QP-Mode	AV-Mode	QP	-Mode	AV-Mode	(dB)	NOLE
0.15	Line		56.13	38.24	6	6.00	56.00	-9.87	(QP)
0.16	Line	;	56.10	34.04	6	5.70	55.70	-9.60	(QP)
0.35	Line	;	38.49	*	5	9.01	49.01	-20.52	(QP)
0.51	Line	;	30.67	*	5	6.00	46.00	-25.33	(QP)
1.72	Line	;	24.75	*	5	6.00	46.00	-31.25	(QP)
6.22	Line	;	23.28	*	6	0.00	50.00	-36.72	(QP)

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz;SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •




(3) Measuring frequency range from 150KHz to 30MHz  $_{\circ}$ 



IFUI .	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> °C	Relative Humidity :	57 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	FM 87.5MHz	·	

Freq.	Terminal	Measured(dBuV)		Limits(	(dBuV)	Margin	Note
(MHz)	L/N	QP-Mode	AV-Mode	QP-Mode	AV-Mode	(dB)	NULE
0.15	Neutral	56.08	35.43	66.00	56.00	-9.92	(QP)
0.18	Neutral	53.13	36.50	64.63	54.63	-11.50	(QP)
0.56	Neutral	30.75	*	56.00	46.00	-25.25	(QP)
1.23	Neutral	24.09	*	56.00	46.00	-31.91	(QP)
3.26	Neutral	23.38	*	56.00	46.00	-32.62	(QP)
7.36	Neutral	24.19	*	60.00	50.00	-35.81	(QP)


- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz;SPA setting in RBW=10KHz,VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •
- (3) Measuring frequency range from 150KHz to 30MHz  $\circ$





EUT :			Hi Fi dock with bluetooth wireless Audio system			Model N	lame :	SFQ-01	
Temperatu	ure :	23	°C			Relative	Humidity :	57 %	
Pressure :		101	0hPa			Test Vol	tage :	AC 120V/60I	Hz
Test Mode : Bluetooth									
Freq.	Termi	nal	Measure	d(dBuV)		Limits(dBuV)		Margin	Note
(MHz)	L/N		QP-Mode	AV-Mode	QP	-Mode	AV-Mode	(dB)	NOLE
0.15	Line		56.60	34.93	6	6.00	56.00	-9.40	(QP)
0.18	Line	;	52.81	33.50	6	4.63	54.63	-11.82	(QP)
0.40	Line	;	38.44	*	5	7.81	47.81	-19.37	(QP)
1.22	Line	;	24.45	*	5	6.00	46.00	-31.55	(QP)
3.35	Line	;	25.19	*	5	6.00	46.00	-30.81	(QP)
6.64	Line	;	23.97	*	6	0.00	50.00	-36.03	(QP)

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz, VBW =10KHz, Swp. Time = 0.2 sec./MHz ° Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz, VBW=10KHz, Swp. Time =0.2 sec./MHz °
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform In this case, a "\*" marked in AVG Mode column of Interference Voltage Measured •




(3) Measuring frequency range from 150KHz to 30MHz  $_{\circ}$ 



	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	57 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	Bluetooth		

Freq.	Terminal	Measured(dBuV)		Limits(	(dBuV)	Margin	Note
(MHz)	L/N	QP-Mode	AV-Mode	QP-Mode	AV-Mode	(dB)	NOLE
0.15	Neutral	57.50	34.29	66.00	56.00	-8.50	(QP)
0.17	Neutral	55.47	33.96	65.21	55.21	-9.74	(QP)
0.61	Neutral	29.04	*	56.00	46.00	-26.96	(QP)
1.19	Neutral	23.48	*	56.00	46.00	-32.52	(QP)
3.35	Neutral	24.68	*	56.00	46.00	-31.32	(QP)
8.98	Neutral	23.83	*	60.00	50.00	-36.17	(QP)

- (1) Reading in which marked as QP means measurements by using are Quasi-Peak Mode with Detector BW=9KHz; SPA setting in RBW=10KHz, VBW =10KHz, Swp. Time = 0.2 sec./MHz • Reading in which marked as AV means measurements by using are Average Mode with instrument setting in RBW=10KHz,VBW=10KHz, Swp. Time =0.2 sec./MHz •
- (2) All readings are QP Mode value unless otherwise stated AVG in column of Note ... If the QP Mode Measured value compliance with the QP Limits and lower than AVG Limits, the EUT shall be deemed to meet both QP & AVG Limits and then only QP Mode was measured, but AVG Mode didn't perform • In this case, a " \* " marked in AVG Mode column of Interference Voltage Measured •
- (3) Measuring frequency range from 150KHz to 30MHz  $\circ$



# Neutron Engineering Inc.=

#### 4.2 RADIATED EMISSION MEASUREMENT

#### 4.2.1 RADIATED EMISSION LIMITS (Frequency Range 9kHz-1000MHz)

20dBc in any 100 kHz bandwidth outside the operating frequency band. In case the emission fall within the restricted band specified on 15.205(a), then the 15.209(a) limit in the table below has to be followed.

Frequencies	Field Strength	Measurement Distance
(MHz)	(micorvolts/meter)	(meters)
0.009~0.490	2400/F(KHz)	300
0.490~1.705	24000/F(KHz)	30
1.705~30.0	30	30
30~88	100	3
88~216	150	3
216~960	200	3
Above 960	500	3

LIMITS OF RADIATED EMISSION MEASUREMENT (Above 1000MHz)

FREQUENCY (MHz)	Class A (dBuV/m) (at 3M)		Class B (dBuV/m) (at 3M)	
	PEAK	AVERAGE	PEAK	AVERAGE
Above 1000	80	60	74	54

Notes:

(1) The limit for radiated test was performed according to FCC PART 15C.

(2) The tighter limit applies at the band edges.

(3) Emission level (dBuV/m)=20log Emission level (uV/m).

FREQUENCY RANGE OF RADIATED MEASUREMENT (For unintentional radiators)

Highest frequency generated or Upper frequency of measurement used in the device or on which the device operates or tunes (MHz)	Range (MHz)
Below 1.705	30
1.705 – 108	1000
108 – 500	2000
500 – 1000	5000
Above 1000	5 <sup>th</sup> harmonic of the highest frequency or 40 GHz, whichever is lower

Neutron Engineering Inc.\_\_\_\_\_

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Horn Antenna	ETS	3115	00075789	May.12.2011
2	Amplifier	Agilent	8449B	3008A02274	May.26.2011
3	Spectrum	Agilent	E4408B	US39240143	Nov.16.2010
4	Test Cable	HUBER+SUHNER	CB03 High Fre	N/A	May.03.2011
5	Bi-log Antenna	Schwarbeck	VULB9160	9160-3232	May.26.2011
6	Amplifier	HP	8447D	2944A09673	May.26.2011
7	Test Receiver	R&S	ESCI	100895	May.26.2011
8	Test Cable	N/A	C-01_CB03	N/A	Jul.05.2011
9	Controller	СТ	SC100	N/A	N/A
10	Triple Loop Antenna	R&S	HFH2-Z2	830749/020	May.27.2011
11	Broad-Band Horn Antenna	Schwarzbeck	BBHA 9170	9170319	May.12.2011

### 4.2.2 MEASUREMENT INSTRUMENTS LIST ANS SETTING

Remark: " N/A" denotes No Model Name / Serial No. and No Calibration specified.

Spectrum Parameter	Setting	
Attenuation	Auto	
Start Frequency	1000 MHz	
Stop Frequency	10th carrier harmonic	
RB / VB (emission in restricted	1 MUE / 1 MUE for Deck, 1 MUE / 10UE for Average	
band)	1 MHz / 1 MHz for Peak, 1 MHz / 10Hz for Average	

Receiver Parameter	Setting
Attenuation	Auto
Start ~ Stop Frequency	9kHz~150kHz / RB 200Hz for QP
Start ~ Stop Frequency	150kHz~30MHz / RB 9kHz for QP
Start ~ Stop Frequency	30MHz~1000MHz / RB 120kHz for QP



#### 4.2.3 TEST PROCEDURE

- a. The measuring distance of at 3 m shall be used for measurements at frequency up to 1GHz. For frequencies above 1GHz, any suitable measuring distance may be used.
- b. The EUT was placed on the top of a rotating table 0.8 meters above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.
- c. The height of the equipment or of the substitution antenna shall be 0.8 m; the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- d. The initial step in collecting conducted emission data is a spectrum analyzer peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- e. If the Peak Mode measured value compliance with and lower than Quasi Peak Mode Limit, the EUT shall be deemed to meet QP Limits and then no additional QP Mode measurement performed.
- f. For the actual test configuration, please refer to the related Item –EUT Test Photos.


#### 4.2.4 DEVIATION FROM TEST STANDARD


No deviation

# Neutron Engineering Inc.=

# 4.2.5 TEST SETUP

(A) Radiated Emission Test Set-Up Frequency Below 1 GHz





### 4.2.6 EUT OPERATING CONDITIONS


The EUT tested system was configured as the statements of **4.1.6** Unless otherwise a special operating condition is specified in the follows during the testing.

### 4.2.7 TEST RESULTS (BETWEEN 30 - 1000 MHZ)

EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	23 °C	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz –CH00-1Mbps	·	

Freq. (MHz)	Ant. H/V	Reading(RA) (dBuV)	Corr.Factor(CF) (dB)	Measured(FS) (dBuV/m)	Limits(QP) (dBuV/m)	Margin (dB)	Note
56.99	V	46.53	-23.67	22.86	40.00	- 17.14	
123.35	V	48.99	-20.49	28.50	43.50	- 15.00	
187.61	V	43.74	-21.92	21.82	43.50	- 21.68	
266.93	V	45.66	-17.18	28.48	46.00	- 17.52	
387.71	V	39.24	-15.16	24.08	46.00	- 21.92	
499.82	V	40.88	-15.24	25.64	46.00	- 20.36	

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz ∘
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\circ$
- (3) Measuring frequency range from 30MHz to 1000MHz  ${\scriptstyle \circ}$
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not show in table  ${}^{\circ}$






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz –CH00-1Mbps		

Freq.	Ant.	Reading(RA)	Corr.Factor(CF)	Measured(FS)	Limits(QP)	Margin	Nata
(MHz)	H/V	(dBuV)	(dB)	(dBuV/m)	(dBuV/m)	(dB)	Note
87.96	Н	48.33	-29.71	18.62	40.00	- 21.38	
125.66	Н	44.26	-23.41	20.85	43.50	- 22.65	
189.61	Н	43.21	-23.56	19.65	43.50	- 23.85	
256.73	Н	44.17	-21.63	22.54	46.00	- 23.46	
336.98	Н	42.50	-20.05	22.45	46.00	- 23.55	
599.40	Н	33.99	-10.57	23.42	46.00	- 22.58	

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz ; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz °
- (3) Measuring frequency range from 30MHz to 1000MHz  ${\scriptstyle \circ}$
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not show in table  $\circ$






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	RX 2402MHz –CH00-1Mbps	·	

ĺ	Freq.	Ant.	Reading(RA)	Corr.Factor(CF)	Measured(FS)	Limits(QP)	Margin	Note
	(MHz)	H/V	(dBuV)	(dB)	(dBuV/m)	(dBuV/m)	(dB)	NOLE
	89.63	V	42.32	-24.84	17.48	43.50	- 26.02	
	156.37	V	40.12	-19.19	20.93	43.50	- 22.57	
	254.28	V	39.96	-17.19	22.77	46.00	- 23.23	
	339.91	V	41.86	-17.55	24.31	46.00	- 21.69	
	415.53	V	42.53	-15.51	27.02	46.00	- 18.98	
	520.33	V	38.77	-15.28	23.49	46.00	- 22.51	

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz °
- (3) Measuring frequency range from 30MHz to 1000MHz  ${\scriptstyle \circ}$
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not show in table  ${\scriptstyle \circ}$






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	RX 2402MHz –CH00-1Mbps		

Freq.	Ant.	Reading(RA)	Corr.Factor(CF)	Measured(FS)	Limits(QP)	Margin	Note
(MHz)	H/V	(dBuV)	(dB)	(dBuV/m)	(dBuV/m)	(dB)	NOLE
187.60	Н	42.63	-23.46	19.17	43.50	- 24.33	
236.55	Н	41.18	-21.91	19.27	46.00	- 26.73	
376.80	Н	45.87	-18.38	27.49	46.00	- 18.51	
447.86	Н	36.55	-14.74	21.81	46.00	- 24.19	
619.30	Н	26.05	-10.07	15.98	46.00	- 30.02	
704.20	Н	27.42	-10.87	16.55	46.00	- 29.45	

- (1) Reading in which marked as QP or Peak means measurements by using are Quasi-Peak Mode or Peak Mode with Detector BW=120KHz; SPA setting in RBW=120KHz, VBW =120KHz, Swp. Time = 0.3 sec./MHz °
- (2) All readings are Peak unless otherwise stated QP in column of 『Note』. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\circ$
- (3) Measuring frequency range from 30MHz to 1000MHz  ${\scriptstyle \circ}$
- (4) If the peak scan value lower limit more than 20dB, then this signal data does not show in table  ${\scriptstyle \circ}$



#### 4.2.8 TEST RESULTS (ABOVE 1000 MHZ)

EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz – CH 00-1Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2390.00	V	21.87	10.77	31.61	53.48	42.38	74.00	54.00	X/E
2402.30	V	62.01	27.59	31.60	93.61	59.19			X/F
4804.26	V	55.46	41.02	5.18	60.64	46.20	74.00	54.00	X/H


Remark :

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand

(7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna

# Neutron Engineering Inc.=






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	56 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz – CH 00-1Mbps		

ſ	Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
			Peak	AV		Peak	AV	Peak	AV	Note
	(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
	2390.00	Н	22.32	10.74	31.61	53.93	42.35	74.00	54.00	X/E
	2402.30	Н	62.87	27.79	31.60	94.47	59.39			X/F
	4803.95	Н	48.79	36.19	5.17	53.96	41.36	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency. "F" denotes fundamental frequency; "H" denotes spurious frequency.
  "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna








IFUI .	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2441MHz –CH39-1Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2441.20	V	67.47	29.38	31.55	99.02	60.93			X/F
4882.05	V	55.63	41.29	5.56	61.19	46.85	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table; "Y" denotes Vertical Stand; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna






EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2441MHz –CH39-1Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2441.30	Н	65.28	28.53	31.55	96.83	60.08			X/F
4882.74	Н	50.31	38.29	5.56	55.87	43.85	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis : "X" denotes Laid on Table : "X" denotes Vertical Stand : "Z" denotes S
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna








EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2480MHz –CH78-1Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2480.20	V	67.03	29.79	31.50	98.53	61.29			X/F
2483.50	V	31.25	16.36	31.50	62.75	47.86	74.00	54.00	X/E
4960.87	V	55.39	40.12	5.94	61.33	46.06	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna







EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2480MHz –CH78-1Mbps		


Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2480.20	Н	62.97	28.34	31.50	94.47	59.84			X/F
2483.50	Н	27.54	15.20	31.50	59.04	46.70	74.00	54.00	X/E
4959.82	Н	52.36	39.91	5.94	58.30	45.85	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency. "F" denotes fundamental frequency; "H" denotes spurious frequency.
  "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand

(7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna








	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz – CH 00-3Mbps	·	

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2390.00	V	21.35	10.73	31.61	52.96	42.34	74.00	54.00	X/E
2402.10	V	65.03	26.76	31.60	96.63	58.36			X/F
4804.76	V	57.66	40.35	5.18	62.84	45.53	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table; "Y" - denotes Vertical Stand; "Z" - denotes Side Stand

(7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2402MHz – CH 00-3Mbps	·	

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2390.00	Н	20.91	10.69	31.61	52.52	42.30	74.00	54.00	X/E
2402.20	Н	62.98	26.50	31.60	94.58	58.10			X/F
4804.59	Н	52.33	38.47	5.18	57.51	43.65	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency. "F" denotes fundamental frequency; "H" denotes spurious frequency.
  "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna








	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2441MHz –CH39-3Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2441.00	V	65.65	29.00	31.55	97.20	60.55			X/F
4882.36	V	56.55	41.12	5.56	62.11	46.68	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table; "Y" denotes Vertical Stand; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna






EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2441MHz –CH39-3Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2441.20	Н	64.99	29.04	31.55	96.54	60.59			X/F
4882.76	Н	52.36	37.88	5.56	57.92	43.44	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis : "X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna








EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2480MHz –CH78-3Mbps		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2480.10	V	66.52	29.57	31.50	98.02	61.07			X/F
2483.50	V	31.88	16.45	31.50	63.38	47.95	74.00	54.00	X/E
4959.68	V	54.76	39.65	5.93	60.69	45.58	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand
- (7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna







	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	56 %
Pressure :	1010 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	TX 2480MHz –CH78-3Mbps		


Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
2480.20	Н	62.86	28.00	31.50	94.36	59.50			X/F
2483.50	Н	28.96	15.30	31.50	60.46	46.80	74.00	54.00	X/E
4960.50	Н	50.69	37.04	5.94	56.63	42.98	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 30MHz to 1000MHz or the 10th harmonic of highest fundamental frequency. "F" denotes fundamental frequency; "H" denotes spurious frequency.
  "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table; "Y" - denotes Vertical Stand; "Z" - denotes Side Stand

(7) During the measurements above 1 GHz it is taken care of that the EUT is always within the 3 dB cone of radiation BW of the used antenna






	Hi Fi dock with bluetooth wireless Audio system	Model Name. :	SFQ-01
Temperature :	<b>26</b> ℃	Relative Humidity :	54 %
Pressure :	1009 hPa	Test Power :	AC 120V/60Hz
Test Mode :	RX Mode 2441MHz		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Limit		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
1619.63	V	51.38	41.55	-5.10	46.28	36.45	74.00	54.00	X/H


- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$
- (2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission 。
- (4) Data of measurement within this frequency range shown "\*" in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand



EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name. :	SFQ-01
Temperature :	<b>26</b> ℃	Relative Humidity :	54 %
Pressure :	1009 hPa	Test Power :	AC 120V/60Hz
Test Mode :	RX Mode 2441MHz		

Freq.	Ant.Pol.	Reading		Ant./CF	Act.		Lir		
		Peak	AV		Peak	AV	Peak	AV	Note
(MHz)	H/V	(dBuV)	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	(dBuV/m)	(dBuV/m)	
1623.89	Н	48.77	39.65	-5.05	43.72	34.60	74.00	54.00	X/H

- (1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ\]$
- (2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup>"F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)
- (3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission 。
- (4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.
- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:
  - "X" denotes Laid on Table ; "Y" denotes Vertical Stand ; "Z" denotes Side Stand



	Hi Fi dock with bluetooth wireless Audio system	Model Name. :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	57 %
Pressure :	1009 hPa	Test Power :	AC 120V/60Hz
Test Mode :	FM 87.5MHz		

Freq.	Ant.Pol.	Reading	Ant./CF	Measurement	Limit	Note
(MHz)	H/V	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	NOLE
81.22	V	47.57	-20.32	27.25	30.00	
103.65	V	42.84	-18.73	24.11	30.00	
198.62	V	42.03	-15.52	26.51	30.00	
236.55	V	39.71	-13.26	26.54	37.00	
325.59	V	39.07	-10.05	29.02	37.00	
463.37	V	41.75	-6.69	35.06	37.00	

Remark


(1) All readings are Peak unless otherwise stated QP in column of "Note ... Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform •

(2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency • "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)

(3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission ...

(4) Data of measurement within this frequency range shown "\*" in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.

- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:



"X" - denotes Laid on Table; "Y" - denotes Vertical Stand; "Z" - denotes Side Stand

E	UT :			Fi dock with blue eless Audio syst		Model Name. : SFQ-01			
Te	emperature	:	23	°C		Rel	ative Humidity :	57 %	
Pi	ressure :		100	9 hPa		Tes	t Power :	AC 120V/60H	Ηz
Te	est Mode :		FM	87.5MHz					
	Freq.	Ant.l	Pol.	Reading	Ant./CF		Measurement	Limit	Note
	(MHz)	H/	V	(dBuV)	CF(dB)		(dBuV/m)	(dBuV/m)	NOLE
	69.97	F	ł	46.84	-20.29		26.55	30.00	
	111.32	F	ł	43.01	-18.98		24.03	30.00	
	187.65	F	ł	43.12	-15.58		27.54	30.00	
	254.46	F	1	42.33	-12.45		29.88	37.00	
	300.98	F	1	40.37	-11.25		29.12	37.00	
	387.56	F	1	40.69	-8.03		32.66	37.00	
_									

Remark :

(1) All readings are Peak unless otherwise stated QP in column of  ${\sc {\sc {\sc reading}}}$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  ${\sc {\sc o}}$ 


(2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency ° "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)

(3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission •

(4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.

- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand



E	UT :		Hi Fi dock with bluetooth wireless Audio system			Model Name. : SFQ-01			
Te	emperature	:	23	°C		Rel	ative Humidity :	57 %	
P	ressure :		100	9 hPa		Tes	t Power :	AC 120V/60H	Ηz
Te	est Mode :		FM	97.5MHz		<u> </u>			
	Freq.	Ant.F	Pol.	Reading	Ant./CF		Measurement	Limit	Note
	(MHz)	(MHz) H/V		(dBuV)	CF(dB)		(dBuV/m)	(dBuV/m)	nole
	78.44	V	/	45.62	-20.43		25.19	30.00	
	132.56	V	/	43.23	-19.14		24.09	30.00	
	158.79	V	/	44.27	-16.64		27.63	30.00	
	210.34	$\geq$	/	39.54	-14.82		24.72	30.00	
	287.93	V	/	39.54	-11.55		27.79	37.00	
	442.33	$\sim$	/	40.56	-7.55		33.01	37.00	

Remark :

(1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note  $\[\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$ 


(2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup>"F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)

(3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission

(4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.

- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand



CITRU			
EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name. :	SFQ-01
Temperature :	<b>23</b> ℃	Relative Humidity :	57 %
Pressure :	1009 hPa	Test Power :	AC 120V/60Hz
Test Mode :	FM 107.5MHz		

Freq.	Ant.Pol.	Reading	Ant./CF	Measurement	Limit	Note
(MHz)	H/V	(dBuV)	CF(dB)	(dBuV/m)	(dBuV/m)	NOLE
56.98	Н	42.99	-19.24	23.75	30.00	
168.99	Н	44.04	-16.46	27.58	30.00	
234.76	Н	41.95	-13.34	28.61	30.00	
268.49	Н	39.85	-12.03	27.82	37.00	
369.94	Н	35.75	-8.14	27.61	37.00	
468.12	Н	36.90	-6.44	30.46	37.00	

Remark :

(1) All readings are Peak unless otherwise stated QP in column of  $\[\]$  Note $\]$ . Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform  $\[\circ$ 


(2) Measuring frequency range from 1000MHz to 6000MHz or the 10th harmonic of highest fundamental frequency<sup>o</sup> "F" denotes fundamental frequency; "H" denotes spurious frequency. "E" denotes band edge frequency. (This judgment method includes the Band Edge Requirement.)

(3) Radiated emissions measured in frequency range above 1000MHz were made with an instrument using Peak detector mode and AV detector mode of the emission

(4) Data of measurement within this frequency range shown " \* " in the table above means the reading of emissions are attenuated more than 20dB below the permissible limits or the field strength is too small to be measured.

- (5) A preamp and high pass filter were used for this test in order to provide sufficient measurement sensitivity.
- (6) EUT Orthogonal Axis:

"X" - denotes Laid on Table ; "Y" - denotes Vertical Stand ; "Z" - denotes Side Stand



#### 5. NUMBER OF HOPPING CHANNEL

#### 5.1 APPLIED PROCEDURES / LIMIT

	FCC Part15 (15.247) , Subpart C									
Section	Test Item	Frequency Range (MHz)	Result							
15.247 (a)(1)(iii)	Number of Hopping Channel	2400-2483.5	PASS							

#### 5.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.

Spectrum Parameters	Setting
Attenuation	Auto
Span Frequency	> Operating Frequency Range
RB	100 kHz
VB	100 kHz
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

#### 5.1.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting : RBW= 100KHz, VBW=100KHz, Sweep time = Auto.

#### 5.1.3 DEVIATION FROM STANDARD

No deviation.

#### 5.1.4 TEST SETUP

EUT	SPECTRUM
	ANALYZER

#### 5.1.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 4.1.6 Unless otherwise a special operating condition is specified in the follows during the testing.




#### 5.1.6 TEST RESULTS

JT :		Hi Fi docł wireless A				lodel Na		SFQ		
mperatur	e:	<b>22</b> ℃			F	Relative Humidity :			)	
essure :		1010 hPa	l		Г	est Volta	age :	AC 1	20V/60I	Ηz
st Mode	:	Hopping I	Mode -1	Mbps						
N	umber	of Hoppir	ig Chani	nel				79		
~			* F	RBW 300	) kHz					
*	Att 2	0 dB	* \	/BW 300	) kHz	M2	[1]		3.3	L6 dBm
		0.0 dBm		SWT 2.5	ims			2.48		00 GHz
	M1					M1	[1]			90 ¢∦B₂m
1Pk	d Men	And Weller			<u>ANAAAA</u>		RAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA			
Мах		0   0   - 0 1	0 · [] 0 · 0 [] 0	enell. It.	,    , ,       , ,	-   -	0°°UUU~U~U	lolloo, o.	<u>רה הההראו ההווי</u>	Nn In .
	-10 dE	3m	*			•				
	-20 dE	3m <del></del>								
	-30 dE	 3m								
										ା ଏ
	-40 dE	3m								
										1
	-50 dE	3m								
	-60 dE	3m <del></del>								
	-70 dE	1 3m								
	, v u									
	-80 dE	3m								
	Ctart							Stop	7 402	
	Start	2.4 GI	72					stop	2.405	5 GHz
Date:	17.J	UL.2010	11:00	:22						

EUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1015 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	Hopping Mode -3Mbps		
	•		

79

Number of Hopping Channel



#### 6. AVERAGE TIME OF OCCUPANCY

#### 6.1 APPLIED PROCEDURES / LIMIT

FCC Part15 (15.247) , Subpart C					
Section	Test Item	Limit	Frequency Range (MHz)	Result	
15.247 (a)(1)(iii)	Average Time of Occupancy	0.4sec	2400-2483.5	PASS	

#### 6.1.1 MEASUREMENT INSTRUMENTS LIST

ltem	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010


Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.

#### 6.1.2 TEST PROCEDURE

- a. The transmitter output (antenna port) was connected to the spectrum analyzer
- b. Set RBW of spectrum analyzer to 1MHz and VBW to 1MHz.
- c. Use a video trigger with the trigger level set to enable triggering only on full pulses.
- d. Sweep Time is more than once pulse time.
- e. Set the center frequency on any frequency would be measure and set the frequency span to zero span.
- f. Measure the maximum time duration of one single pulse.
- g. Set the EUT for DH5, DH3 and DH1 packet transmitting.
- $\tilde{h}$ . Measure the maximum time duration of one single pulse.
- i. DH5 Packet permit maximum 1600/ 79 / 6 = 3.37 hops per second in each channel (5 time slots RX, 1 time slot TX). So, the dwell time is the time duration of the pulse times 3.37 x 31.6 = 106.6 within 31.6 seconds.
- j. DH3 Packet permit maximum 1600 / 79 / 4 = 5.06 hops per second in each channel (3 time slots RX, 1 time slot TX). So, the dwell time is the time duration of the pulse times 5.06 x 31.6 = 160 within 31.6 seconds.
- k. DH1 Packet permit maximum 1600 / 79 /2 = 10.12 hops per second in each channel (1 time slot RX, 1 time slot TX). So, the dwell time is the time duration of the pulse times 10.12 x 31.6 = 320 within 31.6 seconds.

#### 6.1.3 DEVIATION FROM STANDARD


No deviation.




#### 6.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00-DH1/DH3/DH5 -1Mbps		


Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2402 MHz	3.1200	0.3328	0.4000
DH3	2402 MHz	1.8400	0.2944	0.4000
DH1	2402 MHz	0.5600	0.1792	0.4000






IEUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH39 -DH1/DH3/DH5 -1Mbps		

Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2441 MHz	3.1000	0.3307	0.4000
DH3	2441 MHz	1.8400	0.2944	0.4000
DH1	2441 MHz	0.5500	0.1760	0.4000









IEUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH78 -DH1/DH3/DH5-1Mbps		

Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2480 MHz	3.0800	0.3285	0.4000
DH3	2480 MHz	1.8400	0.2944	0.4000
DH1	2480 MHz	0.5600	0.1792	0.4000









	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00-DH1/DH3/DH5 -3Mbps		


Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2402 MHz	3.1000	0.3307	0.4000
DH3	2402 MHz	1.8700	0.2992	0.4000
DH1	2402 MHz	0.5700	0.1824	0.4000






IEUT :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH39 -DH1/DH3/DH5 -3Mbps		


Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2441 MHz	3.1200	0.3328	0.4000
DH3	2441 MHz	1.8500	0.2960	0.4000
DH1	2441 MHz	0.5500	0.1760	0.4000






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH78 -DH1/DH3/DH5-3Mbps		

Data Packet	Frequency	Pulse Duration (ms)	Dwell Time (s)	Limits (s)
DH5	2480 MHz	3.1000	0.3307	0.4000
DH3	2480 MHz	1.8300	0.2928	0.4000
DH1	2480 MHz	0.5700	0.1824	0.4000







#### 7. HOPPING CHANNEL SEPARATION MEASUREMENT

#### 7.1 APPLIED PROCEDURES / LIMIT

Frequency hopping systems operating in the 2400-2483.5 MHz band may have hopping channel carrier frequencies that are separated by 25 kHz or two-thirds of the 20 dB bandwidth of the hopping channel, whichever is greater.

#### 7.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	> Measurement Bandwidth or Channel Separation
RB	30 kHz (20dB Bandwidth) / 100 kHz (Channel Separation)
VB	100 kHz (20dB Bandwidth) / 300 kHz (Channel Separation)
Detector	Peak
Trace	Max Hold
Sweep Time	Auto


#### 7.1.2 TEST PROCEDURE

- a. The transmitter output (antenna port) was connected to the spectrum analyser in peak hold mode.
- b. The resolution bandwidth of 30 kHz and the video bandwidth of 100 kHz were utilised for 20 dB bandwidth measurement.
- c. The resolution bandwidth of 100 kHz and the video bandwidth of 300 kHz were utilised for channel separation measurement.

#### 7.1.3 DEVIATION FROM STANDARD

No deviation.

#### 7.1.4 TEST SETUP



#### 7.1.5 EUT OPERATION CONDITIONS

The EUT was programmed to be in continuously transmitting mode.





#### 7.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH39 /CH78-1Mbps		

Frequency	Ch. Separation (MHz)	20d Bandwidth B (kHz)	Result
2402 MHz	1	918.00	Complies
2441 MHz	1	918.00	Complies
2480 MHz	1	948.00	Complies

#### Ch. Separation Limits: >20dB bandwidth or >2/3 of 20dB bandwidth









IFUI :	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH39 /CH78-3Mbps		

Frequency	Ch. Separation (MHz)	20d Bandwidth B (kHz)	Result
2402 MHz	1	1198.00	Complies
2441 MHz	1	1218.00	Complies
2480 MHz	1	1208.00	Complies

Ch. Separation Limits: >20dB bandwidth or >2/3 of 20dB bandwidth





#### 8. BANDWIDTH TEST

#### 8.1 APPLIED PROCEDURES / LIMIT

FCC Part15 (15.247) , Subpart C					
Section	Test Item	Limit	Frequency Range (MHz)	Result	
15.247 (a)(2)	Bandwidth	<= 1 MHz (20dB bandwidth)	2400-2483.5	PASS	

#### 8.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name, Serial No. or No Calibration specified.

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	> Measurement Bandwidth or Channel Separation
RB	30 kHz (20dB Bandwidth) / 100 kHz (Channel Separation)
VB	100 kHz (20dB Bandwidth) / 300 kHz (Channel Separation)
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

#### 8.1.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting : RBW= 10KHz, VBW=100KHz, Sweep time = Auto.

#### 8.1.3 DEVIATION FROM STANDARD

No deviation.

#### 8.1.4 TEST SETUP

EUT	SPECTRUM
	ANALYZER


#### 8.1.5 EUT OPERATION CONDITIONS


The EUT tested system was configured as the statements of 4.1.6 Unless otherwise a special operating condition is specified in the follows during the testing.

#### 8.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH39 /CH78-1Mbps		

Frequency	20dB Bandwidth (KHz)	99% Occupied Bandwidth (KHz)	Channel Separation (MHz)	Result
2402 MHz	918.00	878.24	<= 1MHz	PASS
2441 MHz	918.00	878.24	<= 1MHz	PASS
2480 MHz	948.00	888.22	<= 1MHz	PASS









	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH39 /CH78-3Mbps		

Frequency	20dB Bandwidth (KHz)	99% Occupied Bandwidth (KHz)	Channel Separation (MHz)	Result
2402 MHz	1198.00	1157.68	<= 1MHz	PASS
2441 MHz	1218.00	1157.68	<= 1MHz	PASS
2480 MHz	1208.00	1157.68	<= 1MHz	PASS





#### 9. PEAK OUTPUT POWER TEST

#### 9.1 APPLIED PROCEDURES / LIMIT

FCC Part15 (15.247) , Subpart C					
Section	Test Item	Limit	Frequency Range (MHz)	Result	
15.247 (b)(1)	Peak Output Power	1 watt or 30dBm	2400-2483.5	PASS	

#### 9.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.

#### 9.1.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting : RBW= 1MHz, VBW= 1MHz, Sweep time = Auto.

#### 9.1.3 DEVIATION FROM STANDARD

No deviation.

#### 9.1.4 TEST SETUP




#### 9.1.5 EUT OPERATION CONDITIONS


The EUT tested system was configured as the statements of 4.1.6 Unless otherwise a special operating condition is specified in the follows during the testing.

#### 9.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00/ CH39 /CH78 -1Mbps		

Test Channel	Frequency (MHz)	Peak Output Power (dBm)	LIMIT (dBm)	LIMIT (W)
CH00	2402	3.39	30	1
CH39	2441	3.75	30	1
CH78	2480	3.27	30	1









	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00/ CH39 /CH78 -3Mbps		

Test Channel	Frequency (MHz)	Peak Output Power (dBm)	LIMIT (dBm)	LIMIT (W)
CH00	2402	1.63	30	1
CH39	2441	1.82	30	1
CH78	2480	1.29	30	1







#### **10. ANTENNA CONDUCTED SPURIOUS EMISSION**

#### **10.1 APPLIED PROCEDURES / LIMIT**

20dBc in any 100 kHz bandwidth outside the operating frequency band. In case the emission fall within the restricted band specified on 15.205(a), then the 15.209(a) limit in the table below has to be followed.

Frequencies (MHz)	Field Strength (micorvolts/meter)	Measurement Distance (meters)
0.009~0.490	2400/F(KHz)	300
0.490~1.705	24000/F(KHz)	30
1.705~30.0	30	30
30~88	100	3
88~216	150	3
216~960	200	3
Above 960	500	3

#### **10.1.1 MEASUREMENT INSTRUMENTS LIST AND SETTING**

Iter	N Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.

The following table is the setting of the spectrum analyzer.


Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	100 MHz
RB / VB (emission in restricted band)	1MHz / 1MHz for Peak, 1 MHz / 10Hz for Average
RB / VB (other emission)	100 KHz /100 KHz for Peak

#### 10.1.2 TEST PROCEDURE

- a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
- b. Spectrum Setting : RBW= 100KHz, VBW=100KHz, Sweep time = Auto.

#### **10.1.3 DEVIATION FROM STANDARD**

No deviation.




#### 10.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH78-1Mbps		

The max. radio frequency power in any 100kHz bandwidth outside the frequency band		The max. radio frequence bandwidth within the		
FREQUENCY(MHz) POWER(dBm)		FREQUENCY(MHz)	POWER(dBm)	
2376.16	-58.75	2484.08	-43.14	
Result				

In any 100kHz bandwidth outside the frequency band, the radio frequency power is at least 20dB below that in the 100kHz bandwidth within the band that contains the highest lever of the desired power.






	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> ℃	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 / CH78-3Mbps		

	cy power in any 100kHz the frequency band	The max. radio frequend bandwidth within th	
FREQUENCY(MHz) POWER(dBm)		FREQUENCY(MHz)	POWER(dBm)
2376.16	-60.42	2484.08	-45.98
Result			

In any 100kHz bandwidth outside the frequency band, the radio frequency power is at least 20dB below that in the 100kHz bandwidth within the band that contains the highest lever of the desired power.





#### 11. RF EXPOSURE TEST

#### 11.1 APPLIED PROCEDURES / LIMIT

These devices are not exempted from compliance does not exceed the Commission's RF exposure guidelines.Unless a device operates at substantially low power levels, with a low gain antenna(s), supporting information is generally needed to establish the various potential operating configurations and exposure conditions of a transmitter and its antenna(s) in order to determine compliance with the RF exposure guidelines.

In order to demonstrate compliance with MPE requirement(see Section 2.1091), the following information is typically needed:

Calculation that estimates the minimum separation distance(20 cm or more)between an antenna and persons required to satisfy power density limits defined for free space.

Antenna installation and device operating instructions for installers(professional/unskilled users), and the parties responsible for ensuring compliance with the RF exposure requirement Any caution statements and/or warming labels that are necessary in order to comply with the exposure limits Any other RF exposure related issues that may affect MPE compliance.

FCC 1.1310: The criteria listed in the following table shall be used to evaluate the environmental impact of human exposure to radio-frequency(RF) radiation as specified in 1.1307(b).

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/ cm <sup>2</sup> )	Averaging Time  E  <sup>2</sup> , H  <sup>2</sup> or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842 / f	4.89 / f	(900 / f)*	6
30-300	61.4	0.163	1.0	6
300-1500			F/300	6
1500-100,000			5	6

(A) Limits for Occupational / Controlled Exposure

(B) Limits for General Population / Uncontrolled Exposure

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/ cm <sup>2</sup> )	Averaging Time  E  <sup>2</sup> , H  <sup>2</sup> or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f)*	30
30-300	27.5	0.073	0.2	30
300-1500			F/1500	30
1500-100,000			1.0	30

Note: f = frequency in MHz ; \*Plane-wave equivalent power density

#### 11.1.1 MEASUREMENT INSTRUMENTS LIST

	Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
ſ	1	Spectrum Analyzer	R&S	FSP 40	100185	Nov.27.2010

Remark: " N/A" denotes No Model Name , Serial No. or No Calibration specified.



#### 11.1.2 MPE CALCULATION METHOD

Calculation Method of RF Safety Distance:

$$S = \frac{PG}{4\pi r^2} = \frac{EIRP}{4\pi r^2}$$

P :power input to the antenna in Mw

EIRP : Equivalent (effective) isotropic radiated power.

- S :power density mW/ cm<sup>2</sup>
- G ;numeric gain of antenna relative to isotropic radiator
- R :distance to centre of radiation in cm

FCC radio frequency exposure limits may be exceeded at distances closer than r cm from the antenna of this device

$$r = \sqrt{\frac{PG}{4\pi S}} = \sqrt{\frac{EIRP}{4\pi S}}$$

#### 11.1.3 DEVIATION FROM STANDARD

No deviation.

#### 11.1.4 TEST SETUP



#### **11.1.5 EUT OPERATION CONDITIONS**

The EUT tested system was configured as the statements of 4.1.6 Unless otherwise a special operating condition is specified in the follows during the testing.

#### 11.1.6 TEST RESULTS

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 (2402 MHz), CH39(2441 MHz), CH78 (2480 MHz) -1Mbps		


Frequency (MHz)	Antenna Gain (dBi)	Peak Output Power (dBm)	Calculated EIRP (mW)	FCC Threshold (mW)	Test Result
2402	3.5	3.39	4.8865	24.98	Complies
2441	3.5	3.75	5.3088	24.58	Complies
2480	3.5	3.27	4.7534	24.19	Complies

Note: Shown calculated EIRP is "worst case" scenario (peak power value) showing definite compliance with the threshold level.

	Hi Fi dock with bluetooth wireless Audio system	Model Name :	SFQ-01
Temperature :	<b>22</b> °C	Relative Humidity :	60 %
Pressure :	1012 hPa	Test Voltage :	AC 120V/60Hz
Test Mode :	CH00 (2402 MHz), <b>CH39(2441 MHz)</b> , CH78 (2480 MHz) -3Mbps		


Frequency (MHz)	Antenna Gain (dBi)	Peak Output Power (dBm)	Calculated EIRP (mW)	FCC Threshold (mW)	Test Result
2402	3.5	1.63	3.2584	24.98	Complies
2441	3.5	1.82	3.4041	24.58	Complies
2480	3.5	1.29	3.0130	24.19	Complies


Note: Shown calculated EIRP is "worst case" scenario (peak power value) showing definite compliance with the threshold level.





Radiated Measurement Photos 30M~1000MHz







Radiated Measurement Photos Above 1000MHz

