


# Circuit operation explanation

---- Remote rf block diagram ----



- A basic carrier frequency consists of a1, a2, a3 (on picture 1).
- Receiver : super heterodyne receiver
- Modulation type : FM FSK(frequency shift keying)
- Remote transmitting frequency : 413.39MHz
- Remote receive local oscillation frequency : 413.39MHz
- Remote receive frequency : 434.79MHz

## 1. Remote control

### 1.1 Transmission

Press input button(1,2,3) Modulation signal is occurred at CPU(location u1) pin no 1. Modulation is formed at a1 (VD1), a2 (Q6). a3 (Q7) creates frequency 413.39MHz. The frequency of 413.39MHz is amplified through the components of a4(Q8,Q9) and b6(rx/tx switching) and transferred to antenna.

### 1.2 Receiver

A carrier frequency (434.79MHz) amplifies at b5 (Q1, Q2) pass through a5 (antenna) b4 (Q3) receives signals of a3 (Q7), b5 and makes 1st IF (21.4MHz) to send b2 (U1) b2 (U1) mixes with 2nd local oscillation frequency (20.945MHz) of b3 (X2) and makes 455Khz demodulates FM at b1 (X3) and quadrature detects. Sends Fsk out to CPU(location u1) pin no 2.