

APPLICATION FOR GATEWAY EARTH STATION

I. OVERVIEW

The Commission has authorized Space Exploration Holdings, LLC (“SpaceX”) to launch and operate a constellation of 4,408 non-geostationary orbit (“NGSO”) satellites (call sign S2983/S3018) using Ku- and Ka-band spectrum.¹ In doing so, the Commission recognized that granting the SpaceX Authorization would “allow SpaceX to make efficient use of valuable spectrum resources more safely, quickly, and cost-effectively as it initiates a new generation of broadband services available to customers worldwide, including those in areas previously underserved or even totally unserved by other broadband solutions.”² In May 2019, SpaceX began launching satellites to populate its constellation.

This application, filed by a sister company, SpaceX Services, Inc. (“SpaceX Services”), seeks authority to operate a Ka-band gateway earth station that SpaceX will use to deliver broadband data between the satellites of its NGSO system and terrestrial Internet exchange points. Specifically, SpaceX Services seeks authority for eight technically identical 1.5-meter antennas in North Bend, WA (the “North Bend Gateway”). Consistent with SpaceX’s space station authorization, these earth stations will transmit in the 27.5-29.1 GHz and 29.5-30.0 GHz bands and receive in the 17.8-18.6 GHz and 18.8-19.3 GHz bands.

Below, we discuss certain spectrum sharing issues relevant to the operation of these earth stations. We then demonstrate that grant of this application would serve the public interest. Lastly,

¹ See *Space Exploration Holdings, LLC*, 33 FCC Rcd. 3391 (2018) (“SpaceX Authorization”); *Space Exploration Holdings, LLC*, 34 FCC Rcd. 2526 (IB 2019) (“SpaceX Modification”). These authorizations anticipate that Ka-band spectrum would be used for gateway communications.

² SpaceX Modification, ¶ 1.

we provide technical information to supplement the information provided in Form 312. To support its ambitious timetable for launching satellites and deploying broadband services, SpaceX Services requests that the Commission grant the requested license as expeditiously as possible.

II. SPECTRUM SHARING ISSUES

Under the Commission’s spectrum allocations and the plan adopted for the Ka-band in particular,³ SpaceX Services will need to share with a variety of other systems operating in its bands. Below we demonstrate that the proposed North Bend Gateway will comply with all relevant sharing requirements.

A. Uplink Bands

The 27.5-28.35 GHz band has been designated for use by the Upper Microwave Flexible Use Service (“UMFUS”) on a primary basis, with a secondary designation for FSS. The Technical Appendix in this document demonstrates that the North Bend Gateway will satisfy the criteria set forth in Section 25.136(a)(4) of the Commission’s rules such that it may operate without providing additional interference protection to terrestrial UMFUS systems operating in the band.⁴

FSS is primary throughout the 28.35-29.1 GHz band, with NGSO designated as secondary to GSO in the 28.35-28.6 GHz portion and NGSO designated as primary in the 28.6-29.1 GHz portion. FSS is co-primary with Mobile Satellite Service (“MSS”) in the 29.5-30.0 GHz band, with NGSO designated as secondary to GSO.⁵

³ See *Update to Parts 2 and 25 Concerning Non-Geostationary, Fixed-Satellite Service Systems and Related Matters*, 32 FCC Rcd. 7809, App. B (2017) (“NGSO Update Order”).

⁴ See 47 C.F.R. § 25.146(a)(4).

⁵ See *id.*

The Comsearch Report submitted with this application confirms that SpaceX Services has coordinated with existing terrestrial licensees in these bands in compliance with the Commission's rules and can operate without causing harmful interference to any such deployments. SpaceX Services makes no claim of interference protection from U.S.-licensed GSO FSS systems in the 28.35-28.6 GHz and 29.5-30.0 GHz bands. In addition, SpaceX Services will comply with the applicable equivalent power flux-density ("EPFD") limits set forth in Article 22 and Resolution 76 of the ITU Radio Regulations, which the Commission has found to be sufficient to protect GSO systems against harmful interference.⁶ SpaceX has demonstrated that its NGSO system will comply with these EPFD limits, and doing so is a condition of its Authorization.⁷

B. Downlink Bands

The Commission has allocated the 17.8-18.3 GHz band on a primary basis to the terrestrial fixed service ("FS") and on a secondary basis for FSS. The 18.3-18.6 GHz band is allocated on a primary basis to FSS, with NGSO secondary to GSO and subject to international EPFD limits. The 18.8-19.3 GHz band is allocated to FSS on a primary basis, with NGSO designated as primary.

SpaceX has previously demonstrated that its NGSO system will protect terrestrial fixed stations in the 17.8-18.6 GHz and 18.8-19.3 GHz bands, in compliance with a condition placed on its license.⁸ Moreover, the Comsearch report submitted with this application confirms that there should be no additional limitations placed on operations of the North Bend Gateway. Similarly,

⁶ See, e.g., *Amendment of Parts 2 and 25 of the Commission's Rules to Permit Operation of NGSO FSS Systems Co-Frequency with GSO and Terrestrial Systems in the Ku-Band Frequency Range*, 16 FCC Rcd. 4096, ¶ 77 (2000) (concluding that implementation of EPFD limits "will adequately protect GSO FSS networks"); 47 C.F.R. § 25.289 (NGSO satellite systems that comply with EPFD limits will be deemed not to cause unacceptable interference to any GSO network). SpaceX believes that the EPFD limits designed to protect GSO FSS systems will also protect GSO MSS systems in the band.

⁷ See SpaceX Authorization, ¶¶ 40(b), (d), and (e); 47 C.F.R. § 25.115(f)(1) (incorporating certification requirement in 47 C.F.R. § 25.146(a)(2)).

⁸ See SpaceX Modification, ¶ 29.

SpaceX has demonstrated that its NGSO system will comply with the relevant EPFD limits in the 18.3-18.6 GHz band, which the Commission considers sufficient to protect GSO networks from unacceptable interference.⁹

III. GRANT OF THIS APPLICATION WOULD SERVE THE PUBLIC INTEREST

Granting this application would serve the public interest by helping to speed broadband deployment throughout the United States by authorizing the ground-based component of SpaceX's satellite system. U.S. and worldwide demand for broadband services and Internet connectivity continues to increase with escalating requirements for speed, capacity, and reliability and ongoing adaptations for usage. The volume of traffic flowing over the world's networks has exploded, with one report estimating that annual global Internet protocol traffic reached 1.5 zettabytes in 2017 – meaning that approximately 1,500 billion gigabytes of data were exchanged worldwide that year.¹⁰

Yet, as the Commission has recognized, many communities across the United States and the world still lack access to reliable broadband connectivity, preventing them from fully participating in economic, social, and civic activities.¹¹ To help close this digital divide, SpaceX

⁹ See SpaceX Authorization, ¶ 9.

¹⁰ See Cisco Visual Networking Index: Forecast and Methodology, 2017-2022, at 1, CISCO (Nov. 26, 2018), <https://www.cisco.com/c/en/us/solutions/collateral/service-provider/visual-networking-index-vni/white-paper/c11-741490.html>.

¹¹ See, e.g., *Inquiry Concerning the Deployment of Advanced Telecommunications Capability to All Americans in a Reasonable and Timely Fashion*, 33 FCC Rcd. 1660, ¶ 50 (2018) (noting that “over 24 million Americans still lack fixed terrestrial broadband at speeds of 25 Mbps/3 Mbps,” and that “the gap in rural and Tribal America remains notable: 30.7 percent of Americans in rural areas and 35.4 percent of Americans in Tribal lands lack access to fixed terrestrial 25 Mbps/3 Mbps broadband”). Internationally, the disparities between broadband access and absence are even greater, with 4.2 billion people (or 57% of the world's population) offline. See BROADBAND COMMISSION FOR SUSTAINABLE DEVELOPMENT, “Open Statement from the Broadband Commission for Sustainable Development to the UN High-Level Political Forum (HLPF)” (July 11, 2016), <http://broadbandcommission.org/Documents/publications/HLPF-July2016.pdf>. See also BROADBAND COMMISSION FOR SUSTAINABLE DEVELOPMENT, “The State of Broadband 2015,” at 8 (Sep. 2015), <http://www.broadbandcommission.org/Documents/reports/bb-annualreport2015.pdf> (“A large body of evidence

is designing, constructing, and deploying an innovative, cost-effective and spectrum-efficient satellite system capable of delivering robust broadband service to customers around the world. SpaceX has already secured U.S. authority for the space station components of its NGSO system. This application takes the next step by seeking authority for one of the gateway earth stations that will connect the satellite system to the terrestrial Internet. Accordingly, an expeditious grant of this application would serve the public interest.

Respectfully submitted,

SPACEX SERVICES, INC.

By: /s/ David Goldman
David Goldman
Director, Satellite Policy

SPACE EXPLORATION TECHNOLOGIES CORP.
1155 F Street, NW
Suite 475
Washington, DC 20004
202-649-2700 tel
202-649-2701 fax

William M. Wiltshire
Paul Caritj
HARRIS, WILTSHIRE & GRANNIS LLP 1919 M Street, N.W.
Suite 800
Washington, DC 20036
202-730-1300 tel
202-730-1301 fax

Counsel to SpaceX

has now been amassed that affordable and effective broadband connectivity is a vital enabler of economic growth, social inclusion and environmental protection.”

TECHNICAL APPENDIX

In this Technical Appendix, SpaceX Services provides additional information on the proposed operations of its gateway earth station to supplement the data provided in Schedule B to Form 312 filed with this narrative application.¹²

A. Minimum Elevation Angle

SpaceX Service's gateway earth stations will communicate only with those SpaceX satellites that are visible on the horizon above a minimum elevation angle. This angle may be as low as 25 degrees, and thus SpaceX Services has used this minimum elevation angle in its analysis in order to capture the full potential range of service.

B. UMFUS Coordination - Section 25.136(a)(4)

Section 25.136(a)(4) of the Commission's rules defines four elements that, if met, permit an earth station licensee to operate without providing additional interference protection to terrestrial systems in the Upper Microwave Flexible Use Service ("UMFUS") operating in the 27.5-28.35 GHz band.¹³ As demonstrated below, the proposed North Bend Gateway satisfies these criteria, and the Commission should authorize this earth station without requiring additional protection for future UMFUS systems.

¹² To the extent relevant, SpaceX Services hereby incorporates the technical information submitted with SpaceX's space station applications. See IBFS File Nos. SAT-LOA-20161115-00118, SAT-LOA-20170726-00110, SAT-MOD-20181108-00083, and SAT-MOD-20200417-00037.

¹³ See 47 C.F.R. § 25.146(a)(4).

Section 25.136(a)(4)(i)

There is currently one authorized earth station and one earth station pending authorization in the 27.5-28.35 GHz frequency range in King County, WA.¹⁴ As the 3rd earth station in King County, the North Bend Gateway complies with this section of the Commission's rules.

Section 25.136(a)(4)(ii)

Section 25.136(a)(4)(ii) provides that an earth station operator need not provide interference protection to future UMFUS systems if, in a UMFUS license area with a population greater than 450,000 people, the number of people that will be within the PFD contours equal to or exceeding -77.6 dBm/m2/MHz for all relevant gateways is no more than 0.1 percent of the population of the UMFUS license area. The North Bend Gateway is located in King County, which has a population of approximately 2,269,675 people.¹⁵ This translates to a population coverage limit of 2,269.68 people. As demonstrated below, the PFD contours of the North Bend gateway and other relevant earth stations in King County contain, in aggregate, fewer than 2,269.68 people.

In order to conduct a technical analysis to determine the region around the North Bend Gateway site that would fall within the PFD contour defined by Section 25.136(a)(4), SpaceX used the Visualyse Professional software tool created by Transfinite Systems Ltd., which implements the standard ITU-R Rec. P.452.16 propagation model.¹⁷ SpaceX accounted for clutter using the ITU-R P.452 model, as recommended by the Commission.¹⁸ The ITU P.452 clutter category used

¹⁴ For the authorized earth station, see callsign E150081. For the earth station pending authorization, see callsign E190676.

¹⁵ QuickFacts King County, WA, United States Census Bureau, <https://www.census.gov/quickfacts/kingcountywashington>.

¹⁷ Information on this software can be found at <https://www.transfinite.com/content/professional>.

¹⁸ See Report No. SPB-281 (<https://docs.fcc.gov/public/attachments/DA-20-631A1.pdf>)

in the analysis for this earth station was found to be the most appropriate category based on satellite and street view imagery in Google Earth, as well as in-person surveys at the proposed earth station location. Details on the clutter category and related assumptions can be found in Table 1 below. Because each of the eight antennas of the North Bend Gateway would track a different SpaceX satellite, SpaceX first determined the worst-case aggregate EIRP density toward the horizon to be -18.7 dBW/MHz.¹⁹ Next, SpaceX defined a reference antenna at 10 meters height above ground with 50.24 dBi gain pointed toward the North Bend Gateway. This is necessary because Visualyse performs its calculations using receive power density rather than PFD. The 50.24 dBi gain effectively converts the receive power density value to a PFD value so that Visualyse can display the results in terms of PFD.²⁰ SpaceX also loaded information on the surrounding terrain at a 3-arc second resolution (approximately 90 meters by 90 meters) from NASA's SRTM Digital Terrain Elevation Data profile, and ran the analysis both with the effect of the 3 dB of radiofrequency shielding that SpaceX will install surrounding the site. Table 1 below summarizes the North Bend Gateway parameters used for the analysis.

With the inputs listed in Table 1 and an omni-directional pattern centered at the gateway site, SpaceX ran the Visualyse software implementing the ITU propagation model to develop a composite (eight-antenna) PFD contour with a threshold of -107.6 dBW/m²/MHz²¹ at 10 meters above ground, as required under Section 25.136. The simulation works by moving the reference antenna in small steps all around the area surrounding the North Bend Gateway to measure the

¹⁹ This value is based on eight earth station antennas with -8 dBi gain toward the horizon, each operating at -20.7 dBW/MHz EIRP density toward the horizon, based on -19.7 dBW/MHz input power density.

²⁰ This is the gain of a meter square antenna at 27.5 GHz ($G = 10 \cdot \log_{10}(4\pi/\lambda^2)$), where $\lambda = 1.09$ cm at 27.5 GHz). This is a physical quantity corresponding to an antenna with one-meter square effective area, necessary to convert Visualyse's calculation in terms of receive power density into power flux density.

²¹ This is equivalent to the -77.6 dBm/m²/MHz value used in Section 25.136(a)(4).

value of received power at each location step. Figure 1 and 2 show the PFD contour as calculated by Visualyse, superimposed on Google satellite imagery.

The PFD contour can be used to determine the population that falls within the contour. SpaceX used 2010 US Census data, and projected the PFD contour onto a map of census blocks. Then SpaceX integrated the share of the population covered by the PFD contour in each block to reach an aggregate figure. Using this approach, the estimated population within the PFD contour is 770.81 people. See Figures 1 & 2 for detail.

Table 1: North Bend Gateway Parameters	
Site location	North Bend, WA
County	King County, WA
Site coordinates	47° 28' 56.62" N, 121° 45' 44.41" W
Simulation frequency	27.5 GHz
Antenna sidelobe level toward horizon²²	-8 dBi
Input power density²³	-19.7 dBW/MHz
Number of active antennas	8
Height to midline of antenna	1.7m
ITU P.452 clutter category	Sparse houses, irregularly-spaced sparse trees
Extra site shielding²⁴	3 dB
Worst-case aggregate EIRP	-18.7 dBW/MHz (without site shielding) -21.7 dBW/MHz (after adding site shielding)

²² There have been changes over time in the antenna sidelobe level toward the horizon used in SpaceX's earth station applications. The changes are due to improvements in SpaceX earth station antenna design over time.

²³ For this application, SpaceX conservatively uses worst-case input power density and does not change maximum power during rain fade conditions. Clear-sky maximum power is the same as during rain fade for this application.

²⁴ Most ground-based SpaceX earth stations in the US are surrounded with a solid metal panel fence, which is 8 feet in height and is set 11 feet and 6 inches from the centerline of the outermost antennas. Each earth station is analyzed independently to determine the shielding value required to comply with 47 CFR § 25.136(a)(4)(ii) and 47 CFR § 25.136(a)(4)(iii), based on PFD contours. The independent nature of the analysis explains the variation in shielding values between applications. SpaceX installs shielding at all sites with effectiveness equal to or greater than the value required to remain in compliance with 47 CFR § 25.136(a)(4)(ii) and 47 CFR § 25.136(a)(4)(iii).

When combined with the population coverage of earth stations operating in the 27.5-28.35 GHz frequency range that are authorized or pending authorization in King County, the total anticipated population coverage remains under the limit of 2,269.68 people. Therefore, the North Bend Gateway is in compliance with Section 25.136(a)(4)(ii).

Table 2: Population Coverage in King County, per Section 25.136(a)(4)(ii)

Callsign	File No.	Applicant	Population Coverage²⁵
E150083	SES-MOD-20170418-00407	HNS	244
E190676	SES-MOD-20220323-00346	SpaceX	199
TBD	TBD (North Bend Gateway)	SpaceX	770
Total Population Coverage in King County, WA			1213

Section 25.136(a)(4)(iii)

The North Bend Gateway complies with this section of the Commission’s rules because its PFD contour does not contain any “major event venue, urban mass transit route, passenger railroad, or cruise ship port.” In addition, the PFD contour does not cross any roadways classified as “Other Freeways and Expressways or Other Principal Arterials.”

To make the certification regarding roadways, SpaceX uses QGIS software to conduct an analysis of a comprehensive dataset of roadways obtained from the 2017 release of the HPMS²⁷ ARNOLD²⁸ dataset, belonging to the Federal Highway Administration of the Department of Transportation. To ensure compliance with 47 CFR § 25.136(a)(4)(iii), SpaceX analysis considers the following categories within the dataset: “Interstate,” “Principal Arterial – Other Freeways and Expressways,” and “Principal Arterial – Other”. SpaceX uses QGIS and the comprehensive dataset

²⁵ Population coverage for HNS grandfathered earth station represented by callsign 150083 was calculated in SpaceX filing SES-MOD-20220323-00346. Population coverage calculations were not provided by HNS with initial filing.

²⁷ Highway Performance Monitoring System.

²⁸ All Road Network of Linear Referenced Data.

of roadways to ensure that the PFD contour does not cross any roads classified as “Other Freeways and Expressways or Other Principal Arterials.” According to the website from which the dataset is obtained²⁹: “[the dataset] derives and is collected from State DOT road data. ARNOLD consists of locations of all roads in the U.S.”

Section 25.136(a)(4)(iv)

The Comsearch Report submitted demonstrates that SpaceX completed coordination in compliance with the Commission’s rules.

C. Antenna Patterns

SpaceX will comply with a mask similar to the one in Section 25.209(a)(3) applicable to earth station antennas operating in the 24.75-25.25 GHz and 28.35-30.0 GHz bands with geostationary satellites but will improve that pattern to -8 dBi (rather than 0 dBi) beyond 25 degrees off-axis. The mask can be stated as follows:

$29-25\log_{10}\theta$	dBi	for $2^\circ \leq \theta \leq 7^\circ$.
8	dBi	for $7^\circ < \theta \leq 9.2^\circ$.
$32-25\log_{10}\theta$	dBi	for $9.2^\circ < \theta \leq 25^\circ$.
-8	dBi	for $25^\circ < \theta \leq 180^\circ$.

Consistent with Section 25.209(a)(3), “[t]his envelope may be exceeded by up to 3 dB in 10% of the range of θ angles from ± 7 -180°, and by up to 6 dB in the region of main reflector spillover energy.”³¹ In addition, the half power beamwidth for the proposed antenna is 0.5 degrees at 30 GHz.

²⁹ Source: <https://www.bts.gov/geography/geospatial-portal/NTAD-direct-download>.

³¹ *Id.* § 25.209(a)(3).

Figure 1. Wide-area View Showing Census Block and County Boundaries




Figure 2. PFD Contour and Population Coverage

